

An aerial photograph of a vast, open field with a dirt path winding through it. In the background, a tall, rectangular building is visible under a clear blue sky. The field is a mix of green and brown, suggesting a natural or semi-natural landscape.

# Project X: Status, Strategy, Meeting Goals

**Steve Holmes**  
**Project X Muon Workshop**  
**November 8, 2010**



- 
- Project X Goals and the Reference Design
  - RD&D Plan
  - Strategy and Timeline

Our websites:

<http://projectx.fnal.gov>

<http://projectx-docdb.fnal.gov>


# Evolution of the Fermilab Accelerator Complex



- A multi-MW Proton Source, Project X, is the linchpin of Fermilab's strategy for future development of the accelerator complex.
- Project X provides long term flexibility for achieving leadership on the intensity and energy frontiers
  - Intensity Frontier:  
NuMI → NOvA → LBNE/mu2e → Project X → Rare Processes → NuFact
    - Continuously evolving world leading program in neutrino and rare processes physics; opportunities for applications outside EPP
  - Energy Frontier:  
Tevatron → ILC or Muon Collider
    - Technology alignment
    - Fermilab as host site for ILC or MC



- A neutrino beam for long baseline neutrino oscillation experiments
  - 2 MW proton source at 60-120 GeV
- High intensity, low energy protons for kaon and muon based precision experiments
  - Operations simultaneous with the neutrino program
- A path toward a muon source for a possible future Neutrino Factory and/or a Muon Collider
  - Requires ~4 MW at ~5-15 GeV .
- Possible non-HEP missions under consideration
  - Nuclear physics and ADS development







	Proton Energy (kinetic)	Beam Power	Beam Timing
Rare Muon decays	2-3 GeV	>500 kW	1 kHz – 160 MHz
(g-2) measurement	8 GeV	20-50 kW	30- 100 Hz.
Rare Kaon decays	2.6 – 4 GeV	>500 kW	20 – 160 MHz. (<50 psec pings)
Precision $K^0$ studies	2.6 – 3 GeV	> 100 $\mu$ A (internal target)	20 – 160 MHz. (<50 psec pings)
Neutron and exotic nuclei EDMs	1.5-2.5 GeV	>500 kW	> 100 Hz

# Since the November 2009 Workshop




- 
- 3 GeV established as a workable energy for the rare processes program
  - Reference Design established
    - Based on 3 GeV CW linac, 3-8 GeV pulsed linac, Recycler/MI modifications
    - Functional Requirements Specification (FRS) released
  - Updated RD&D plan, resource loaded schedule (RLS), and cost estimate corresponding to reference design
  - Project X collaboration now includes four Indian Institutes
  - Potential for nuclear physics and/or energy programs under investigation

# Since the November 2009 Workshop



- DOE Science & Technology Review
  - “The Project X machine design is sufficiently well developed for the pre-CD0 stage.”
  - “The physics program for Project X is not well defined at this time. The scientific community should be engaged in defining the potential program.”
- Five Physics/Experiments Task Forces established
  - Neutrinos
  - Kaons
  - Muons
  - Nuclear Physics
  - Nuclear Energy

Goal: define an initial experiment in each area  
Fall workshops
- ARRA
  - Significant investment in SRF infrastructure at Fermilab and development of domestic vendors
- New Fermilab Associate Director for Accelerators – Stuart Henderson



- 3 GeV, 1 mA, CW linac
- Greatly enhanced capabilities in the rare processes program
  - MW class beam power to multiple experiments with variable bunch configurations, simultaneous with neutrino operations
- Self-consistent concept for 3-8 GeV acceleration identified
  - Pulsed linac preferred to RCS due to long-term flexibility







- 
- Construct a 3 GeV continuous-wave superconducting H- linac, capable of delivering 1 mA of average beam current.
    - Supports rare processes and nuclear physics programs
    - Can support ADS development with beams energy <2 GeV
  - Construct a 3-8 GeV pulsed linac, utilizing an ILC-style RF system, with total beam power delivered to 8 GeV ovf 300 kW.
    - Required for the neutrino program
    - Establishes a path toward a muon based facility
  - Upgrade the Recycler and Main Injector to provide  $\geq 2$  MW to a neutrino production target at 60-120 GeV.
    - Supports the long baseline neutrino program
  - Simultaneous operations of the rare processes and neutrino programs
-



## 1 $\mu$ sec period at 3 GeV

mu2e pulse ( $9e7$ ) 162.5 MHz, 100 nsec	400 kW
Kaon pulse ( $9e7$ ) 27 MHz	800 kW
Other pulse ( $9e7$ ) 27 MHz	800 kW




# Functional Requirements

Requirement	Description	Value
L1	Delivered Beam Energy, maximum	3 GeV
L2	Delivered Beam Power at 3 GeV	3 MW
L3	Average Beam Current (averaged over >1 $\mu$ sec)	1 mA
L4	Maximum Beam Current (sustained for <1 $\mu$ sec)	10 mA
L5	The 3 GeV linac must be capable of delivering correctly formatted beam to a pulsed linac, for acceleration to 8 GeV	
L6	Charge delivered to pulsed linac	26 mA-msec in < 0.75 sec
L7	Maximum Bunch Intensity	$1.9 \times 10^8$
L8	Minimum Bunch Spacing	3.1 nsec (1/325 MHz)
L9	Bunch Length	<50 psec (full-width half max)
L10	Bunch Pattern	Programmable
L11	RF Duty Factor	100% (CW)
L12	RF Frequency	325 MHz and harmonics thereof
L13	3 GeV Beam Split	Three-way
P1	Maximum beam Energy	8 GeV
P2	The 3-8 GeV pulsed linac must be capable of delivering correctly formatted beam for injection into the recycler (or Main Injector).	
P3	Charge to fill Main Injector/cycle	26 mA-msec in <0.75 sec
P4	Maximum beam power delivered to 8 GeV	300 kW

# Functional Requirements

Requirement	Description	Value
M1	Delivered Beam Energy, maximum	120 GeV
M2	Delivered Beam Energy, minimum	60 GeV
M3	Minimum Injection Energy	6 GeV
M4	Beam Power (60-120 GeV)	> 2 MW
M5	Beam Particles	Protons
M6	Beam Intensity	$1.6 \times 10^{14}$ protons per pulse
M7	Beam Pulse Length	9.5 $\mu$ sec
M8	Bunches per Pulse	504
M9	Bunch Spacing	18.8 nsec (1/53.1 MHz)
M10	Bunch Length	<2 nsec (fullwidth half max)
M11	Pulse Repetition Rate (120 GeV)	1.333 sec
M12	Pulse Repetition Rate (60 GeV)	0.75 sec
M13	Max Momentum Spread at extraction	$2 \times 10^{-3}$
I1	The 3 GeV and neutrino programs must operate simultaneously	
I2	Residual Activation from Uncontrolled Beam Loss	<20 mrem/hour (average) <100 mrem/hour (peak) @ 1 ft
I3	Scheduled Maintenance Weeks/Year	4
I4	3 GeV Linac Operational Reliability	90%
I5	60-120 GeV Operational Reliability	85%
I6	Facility Lifetime	40 years
U1	Provisions should be made to support an upgrade of the CW linac to support an average current of 4 mA.	
U2	Provisions should be made to support an upgrade of the Main Injector to support a delivered beam power of ~4 MW at 120 GeV.	
U3	Provisions should be made to deliver CW proton beams as low as 1 GeV	
U4	Provision should be made to support an upgrade to the CW linac such that it can accelerate Protons	

# Reference Design Provisional Siting







Section	Freq	Energy (MeV)	Cav/mag/CM	Type
SSR0 ( $\beta_G=0.11$ )	325	2.5-10	26 /26/1	SSR, solenoid
SSR1 ( $\beta_G=0.22$ )	325	10-32	18 /18/ 2	SSR, solenoid
SSR2 ( $\beta_G=0.4$ )	325	32-160	44 /22/4	SSR, solenoid
LB 650 ( $\beta_G=0.61$ )	650	160-520	42 /42/7	5-cell elliptical, doublet
HB 650 ( $\beta_G=0.9$ )	650	520-2000	96 /24/12	5-cell elliptical, doublet
ILC 1.3 ( $\beta_G=1.0$ )	1300	2000-3000	72 /9 /9	9-cell elliptical, quad

Maybe 650



- A superconducting pulsed linac will be used for acceleration from 3 to 8 GeV
  - ILC style cavities and cryomodules
    - 1.3 GHz,  $\beta=1.0$
  - ILC style rf system
    - 5 MW klystron
    - Four cryomodules per rf source
  - Must deliver 26 mA-msec to the Recycler every 0.75 sec. Options:
    - 2 mA x 2.2 msec pulses at 10 Hz
      - Six pulses required to load Recycler/Main Injector
    - 1 mA x 2.2 msec pulses at 20 Hz
      - Twelve pulses required to load Recycler/Main Injector
    - 1 mA x 4.4 msec pulses at 10 Hz
      - Six pulses required to load Recycler/Main Injector
    - 1 mA x 26 msec pulses at 10 Hz
      - One pulse required to load Main Injector

# RD&D Plan Goals



- 
- RD&D = Research, Design, and Development
  - RD&D Plan corresponds to the Reference Design
    - Most recent version available at:  
<http://projectx-docdb.fnal.gov:8080/cgi-bin/ShowDocument?docid=628>
  - Goals
    - Complete design of the Project X facility including all technical and conventional construction elements
    - Identification of key accelerator physics and engineering challenges and validation of performance of critical technology items
      - Simulations, experimentation, and prototype construction as appropriate
    - Development of an acquisition strategy for key technical elements, including development/qualification of vendors for critical components
    - Development of a technical/cost/schedule baseline for construction
    - Preliminary identification of performance upgrade paths



- 
- **Scope**
    - All activities required to bring Project X from the Reference Design through final design (CD-3).
  - **Deliverables**
    - All documentation required by the Department of Energy prior to authorizing construction
    - Supporting technical R&D required to validate the design and establish fabrication methods
  - **Assumed Critical Decision dates**
    - CD-0: January 2011      Approve Mission Need
    - CD-1: July 2012      Approve Alternative Selection & Cost Range
    - CD-2: August 2013      Approve Performance Baseline
    - CD-3: September 2014      Approve Start of Construction
    - CD-4: September 2019      Project Complete
-



- 
- All srf programs at Fermilab are being integrated into a single, centrally managed program.
    - Effective FY2011
    - Brings all srf activities under the purview of the ILC/SRF Program Director
      - ILC and Project X management define requirements
  - Discontinue the High Intensity Neutrino Source (HINS) program as a stand-alone R&D program
    - Rescope the beam facility to support chopper and instrumentation development for Project X. Fund via Project X R&D
    - Retain low beta cavity development under the direction of the ILC/SRF Program Director
    - Eliminate HINS as a budget line item




# SRF Development Plan

(see Supplement I to MOU)



U.S. Fiscal Year	2008	FY09	FY10	FY11	FY12	FY13	FY14	FY15
<b>1.3 GHz</b>								
CM1 (Type III+)		Omnibus Delay	CM Ass'y	Install CM	CM Test		Operate Complete RF Unit @ Design Parameters	
CM2 (Type III+)			Process & VTS/Dress/HTS	CM Ass'y	sw ap			
CM3 (Type IV)			Design	Order Cav & CM Parts		2/3 CM		
CM4 (Type IV)						sw ap		
CM5 (Type IV)						sw ap		
CM6 (Type IV+) CW Design					Design CM 1.3 GHz CW			Install in CMTF
NML Extension Building		Design	Construction					
NML Beam					Move injector/install beam components	Beam Available to RF Unit test except during installation periods (contingent upon cryogenic load/capacity)		
CMTF Building			Design	Construction				
<b>650 MHz</b>								
Single Cell Design & Prototype								
Five Cell Design & Prototype								
CM650_1				Design	Order 650 Cav & CM Parts	Process & VTS/Dress/HTS	650 CM Ass'y	
<b>325 MHz</b>								
SSR0/SSR2 Design & Prototype				Design (RF & Mechanical) all varieties of Spoke Reonators	Prototype (as required)	Process & Test (as required)		
SSR1 Cavities in Fabrication (14)			Procurement (already in progress)	Process & VTS/Dress/HTS				
CM325_1			Design	Procure 325 CM Parts		325 CM Ass'y		





- A multi-institutional collaboration has been established to execute the Project X RD&D Program.
  - Organized as a “national project with international participation”.
    - Fermilab as lead laboratory
    - International participation via in-kind contributions, established through bi-lateral MOUs.
      - IIFC is the first international agreement
  - Collaboration MOUs for the RD&D phase outlines basic goals, and the means of organizing and executing the work. Signatories:

ANL	ORNL/SNS	BARC/Mumbai
BNL	MSU	IUAC/Delhi
Cornell	TJNAF	RRCAT/Indore
Fermilab	SLAC	VECC/Kolkata
LBNL	ILC/ART	
  - Collaborators to assume responsibility for components and sub-system design, development, cost estimating, and potentially construction.



- 
- Next month: Complete all preliminary design, configuration, and cost range documentation for CD-0.
    - Functional Requirements Specification
    - Reference Design Report
    - RD&D Plan
    - Cost estimate/range
    - Resource Loaded Schedule

⇒ Department of Energy briefing on November 16-17
  - Continue conceptual development on outstanding technical questions
    - Baseline concept for the chopper
    - Concepts for marrying the 3-8 GeV pulsed linac to CW front end
    - Injection into the Recycler/Main Injector
    - Emphasis of srf development at all relevant frequencies
  - The DOE has advised that the earliest possible construction start is FY2015
    - We are receiving very significant R&D support for Project X and SRF development (~\$40M in FY11, not including ARRA (stimulus))
  - Planning for a five year construction schedule

⇒ Project X could be up and running in ~2020
-



- 
- Project X is central to Fermilab's strategy for development of the accelerator complex over the coming decade
    - World leading programs in neutrinos and rare processes;
    - Potential applications beyond elementary particle physics;
    - Aligned with ILC, Muon Accelerators, and Nuclear Energy
  - Project X design concept is well developed and well aligned with the requirements of the physics program:
    - 3 GeV CW linac operating at 1 mA: 3 MW beam power
    - 3-8 GeV pulsed linac injecting into the Recycler/Main Injector complex
  - We are expecting CD-0 for Project X in early 2011
  - Project X could be constructed over the period ~2015 – 2019