

# RF Module Integration

Colin Whyte

University of Strathclyde  
on behalf of the MICE collaboration

# Outline



## Interfaces

- High power RF co-axial lines
- Vacuum
  - Window protection
  - Vacuum volume dimensions and pumping
- Temperature - control
- Cavity tuning – air
- Connections to magnets
  - Bellows
  - Flange bolt pattern
  - Quench force
- Sliding platforms
- Clean room
  - End flanges


## Controls and Monitoring

- Interlocks
  - RF Power amplifiers
  - Vacuum
  - Temperature – independent
- Cavity tuning – LabView
- LLRF – offline test
- Muon Timing

## Safety

- Ionising radiation
- High voltage for RF amplifiers


# Demonstration of Ionisation Cooling



- RF power transmission overhead
- SF6 filled co-ax lines
- Relatively easily de-mountable

# RF Power

- Simplified distribution network- overhead
- Off-centre mounting of hybrid takes up phase shift
- Minimised length of 4" line- minimises losses




# Co-axial line support



## Coax support structure

- Fasten Coax support frame to uprights

- Drill and tap PRY for 2 off vertical upright supports
- Steve Plate & Holger don't see this as a problem




# Offline support frame




# RF MODULE Co-Axial line trimmer supports

SUPPORT PILLAR POSITIONS  
TAKEN FROM DRG NO TD-1173-0919



# RF module vacuum




Large, complicated vacuum volume – 2 large turbo-pumps mounted to central spool, located behind south side of PRY with large bore pump path  
Note T Anderson talk on Be window protection.

# Cavity temperature



Temperature stabilisation system with heater, cold water and mixing valve control by high resolution process controller that self learns

- Cavity on frequency at 36.5 degrees
- Water flow rates on cavity restricted due to small cooling pipes
- 0.05 degrees cavity temperature stability can be achieved
- RF trips result in cavity detuning which can again take 5 minutes to recover from
- RF is always applied at effectively maximum



# MTA Cavity results



## **B=0**

0.5M+ pulses at  $>11\text{MV/m}$   
 $14\text{MV/m}$  for short periods.  
No evidence of breakdown


## **B=5T**

### **$>7.5\text{M}$ pulses**

- 1M @  $8\text{MV/m}$
- 3M @  $10.7\text{-}11.2\text{MV/m}$
- 1.3M @  $13\text{-}13.7\text{MV/m}$
- 0.36M @  $13.8\text{-}14.5\text{MV/m}$

No breakdown below  $\sim 14\text{MV/m}$


# Cavity Tuning



0.5M pulses

5Hz,  $B=5T$ , 1.6MW (10.3MV/m)

1.4kW ave, 1Hz update interval



# Vacuum connections



692.15mm OD x 539.75mm ID nested bellows :

Extended length 66mm

Closed length 14mm


Stroke 52mm

nom free length 40mm




Axial stiffness 200N/mm.

316L, 0.91mm thk.



End terminals: 316.




# Quench Forces




# RF CAVITY MODULE MOVING PLATFORM (TOP VIEW)



## RF CAVITY MODULE MOVING PLATFORM ARRANGEMENT OPTIONS (TOP VIEW)



# Cooling Demonstration




# Partial Return Yoke (PRY)



Flux return path to protect sensitive equipment from fringe field of magnet chain.

- 100mm thick soft iron plate
- Step IV PRY re-used and extended for cooling demonstration.
- Extension also made in the USA, drawings complete, ready to go to contract.
- New, extended support structure made in UK.
- New floor fixings required

# RF Module End Plates




RF Module end plates are heavy, 3-400kg. Require hoist/frame in clean room. Cannot flow significant clean gas to preserve cleanliness because of fragile windows. Replace Vac flanges with thin/light 'clean' plates which allow insertion into beamline. Build structure around magnets and fit to clean room extension.

# RF system overall control



- State machine control
- RF measurements
- Important vacuum /voltage/ temperature parameters
- Interlock status and trips
- Illustration shows the main operator panel for ALICE
- more in-depth control pages are clickable from this main screen






# Cooling Demonstration

Installation start 1<sup>st</sup> June 2016.

2 RF cavities, 2 secondary absorbers  
bracketing main absorber

- 2 x 2MW 201MHz amplifier chains – UK
- RF infrastructure support - UK
- RF controls and monitoring – UK
- Muon phase determination - UK
- Extended Partial Return Yoke – USA
- 2 x 201MHz cavities - USA
  - Be windows
  - Tested in B field to 14MV/m



7th February 2015

MICE

i