




Cryo-Module test experience at DESY for the European XFEL







1. E-XFEL CryoModule Layout
2. CM Test Stand AMTF
3. CM Test Program and Procedures
4. CM Test Results and Data
5. Summary


1.1 E-XFEL Module Layout




1.2 E-XFEL Module RF Power Coupler



2.1 AMTF Overview





2.2 AMTF Layout




2 cavity test stands (x4), 3 module test stands (5 MW klystron)



2.3 CM RF Test Diagram



2.4 CM Test Waveguide RF Power Distribution





adjustable RF power distribution




V. Katalev

2.5 CM RF Power Measurement



A.Goessel / DESY

2.6 CM RF Conditioning / Data / Controls



A.Goessel / DESY

3.1 CM Test Steps (1)

1. **RF Cables Calibration.**
 - TDR cables check
 - Dir.Couplers / Circulators: get calibration data.
 - Calibrate RF power measurement cables with attenuators at 1.3 GHz (P for/ref att. ~ 93 dB, P trans/HOM ~ 40 dB)
 - Calibrate RF power measurement cables with attenuators at 1...4 GHz (optional)
 - Make RF calibration summary table
2. **Technical Interlock / Sensors.**
 - Check the sensors (e-, Spark, Temperature)
 - Set the hardware interlock thresholds
 - Check the interlock
3. **RF source / Waveguides / LLRF.**
 - Klystron / LLRF check on the load
 - WGs visual check
 - System check / RF leak check at low power (1 kW pro coupler)
4. **Warm Input RF Couplers Conditioning (all / 1234 + 5678).**
 - Run the standard conditioning program:
20, 50, 100, 200, 400 μ s pulse lengths up to 750kW,
800, 1300 μ s pulse lengths up to 600 kW, 2 Hz rep.rate.
(If the klystron gives not enough of RF power divide the system into the successive tests in such a way that each coupler will be conditioned up to 750kW.)

3.1 CM Test Steps (2)

5. **Cooldown to 2K.**
6. **Cavities Fundamental Spectra measurements.**
 - Measure the fundamental mode spectra (before tuning at 2K)
 - Calibrate the cold RF cables at 2K and 1.3 GHz
7. **Cavities Tuners Test and Cavities Tuning.**
 - Test the cavities step-motor frequency tuners
 - Tune the cavities to the 1.3GHz using the Network Analyzer
8. **Couplers Q_{load} measurement.**
 - Measure the Q_{load} vs antennae positions, check $Q_{load.MIN}$ and $Q_{load.MAX}$ using the Network Analyzer
 - Set $Q_{load} = 4.6 \times 10^6$ for each coupler, adjust π -mode frequency
9. **Cavities HOM Spectra measurements.**
 - Measure the cavities HOMs spectra and Q_{load} (cavities tuned)

3.1 CM Test Steps (3)

10. Cavities On Resonance.

- Cavities fine-tuning to the 1.3GHz using LLRF system
- Q_{load} , K_t calibration ($E_{\text{acc}}=k_t \times (P_{\text{trans}})^{1/2}$)
- $Q_{\text{ext.HOM}}$ at 1.3 GHz measurement with low RF power ($Q_{\text{ext.HOM}}$ at 1.3 GHz must exceed 10^{12}). After this measurement HOM couplers must be disconnected from the RF power meters and connected to RF loads.

11. Cold Couplers and Cavities Conditioning (on resonance).

- Short RF pulse conditioning: 20, 50, 100 μs pulse lengths up to 700kW (max.power), 2 Hz rep.rate, on resonance.

12. Single Cavities Measurements.

- Detune all cavities except the one under test.
- Short RF pulse test at 2K on resonance (100 .. 500 μs pulse lengths up to 700kW, 2 Hz rep.rate), first cavity power-up, coupler / cavity conditioning (HPP).
- $E_{\text{acc.MAX}}$ measurement at 2 [10] Hz rep.rate with 750 + 100 μs short flat-top pulse. MP conditioning.
- Flat-top 750 + 650 μs pulse measurements at 10 Hz rep.rate with cryo losses (Q_o) if measurable and radiation measurements.
- Investigate the cavities limits at 10 Hz rep.rate.

3.1 CM Test Steps (4)

13. Module Performance Measurement.

- Module $E_{\text{acc.MAX}}$ measurement at 2 [10] Hz rep.rate
- Module accelerating gradient measurement at 10 Hz rep.rate with cryo losses (Q_0) and radiation measurements
- Radiation / Dark Current measurements.
- WG power redistribution possibilities check in case of too different cavities limits ($\Delta E_{\text{acc.MAX}} > 5 \text{ MV/m}$)

14. Cryo system performance test (if needed).

- Static Cryogenic Losses measurement, temperature measurements.
- Cold Magnet Tests.
- Cool-down cycles.

15. LLRF and piezo test.

CM Test Documents (EDMS):

1. CM Incoming Inspection
2. CM Final Test Report
3. CM Outgoing Inspection
4. Non-Conformity Reports

3.2 CM Test Data

- | | | |
|-----|---|-----------------------|
| 1. | Cold Cables Attenuations (A_t , $A_{HOM1/2}$) at 2K | 8 cavities |
| 2. | Cavity Probe Calibration: k_t | 8 cavities |
| 3. | Coupler Q_{load} [operating value] | 8 cavities |
| 4. | Coupler $Q_{load.MIN} / Q_{load.MAX}$ | 8 cavities [couplers] |
| 5. | $Q_{ext.probe}$, $Q_{ext.HOM1/2}$ | 8 cavities |
| 6. | frequency / spectra at 2K before tuning | 8 cavities |
| 7. | Tuner steps N_{tuner} to 1.3 GHz | 8 cavities |
| 8. | $E_{acc.X-start}$ (single) | 8 cavities |
| 9. | $E_{acc.X \leq 1e-2}$ (single) | 8 cavities |
| 10. | $E_{acc.MAX}$ (quench/power limit, single) | 8 cavities |
| 11. | $E_{acc.op}$ (operating limit, single) * | 8 cavities |
| 12. | $E_{acc.WG}$ XFEL binary distribution gradient | 8 cavities |
| 13. | E_{acc} FT pulse structure: pulse lengths
t_{rise} , t_{FT} [μs], $E_{acc.FT.min}$ and $E_{acc.FT.max}$ | 8 cavities |
| 14. | X-rays ($E_{acc.MAX}$) gun/dump | 8 cavities |
| 15. | $\langle E_{acc.MAX} \rangle$, $\langle E_{acc.op} \rangle$, $\langle E_{acc.WG} \rangle$ | module |
| 16. | $V_{module} = \sum E_{acc.WG}$, module voltage | module |
| 17. | $P_{cryo}(E_{acc})$ and $Q_0(E_{acc})$ [pulse data] | module |
| 18. | X-rays(E_{acc}) | module |
| 19. | E_{acc} FT pulse structure: pulse lengths
t_{rise} , t_{FT} [μs], $E_{acc.FT.min}$ and $E_{acc.FT.max}$ | module |
| 20. | HOM spectra $Q_{ext}(f_{HOM})$ at 2K, tuned cavities | 8 cavities |

* $E_{acc.op} = \min\{E_{acc.X < 1e-2}, E_{acc.MAX.BD} - 0.5[MV/m], E_{acc.MAX.PWR}\}$

3.3 CM Test Flow (remarks)

Measurement flow:


1. Coupler conditioning (warm) 2Hz.
2. Cooldown.
3. Cavities Fundamental Spectra measurement.
4. Cavities tuning. Q_{load} measurement and tuning.
5. Cavities HOM Spectra measurement.
6. Cavities calibration: k_t and Q_{load} , $Q_{\text{ext.probe}}$, $Q_{\text{ext.HOM1/2}}$ (8 cavities parallel)
7. Cold conditioning / HPP (short pulse) / single cavities.
8. FT measurement: single cavities (with detuning), no Q_0 measurement.
RF power, E_{acc} , X-rays measured. 10Hz.
FT pulse $E_{\text{acc.FT.min}}$ and $E_{\text{acc.FT.max}}$ are calculated/measured from FT pulse.
9. FT measurement: all cavities (up to the module limit) with Q_0 .
RF power, E_{acc} , X-rays, P_{cryo} measured. 10Hz.
FT pulse $E_{\text{acc.FT.min}}$ and $E_{\text{acc.FT.max}}$ are calculated/measured from FT pulse.
10. Piezo test: Loretz force detuning [Hz] vs E_{acc} [MV/m],
without/with piezo compensation.

Optimized test procedure takes 13..15 days.

Delays are caused by non-conformities:

- (cryogenic + vacuum) leaks (mainly at temporary connections to test stand)
- warm coupler part

3.4 CM Test Procedures



Defined and documented CM Test Procedures:

Procedure name	
1	Enabling of the Personal Interlock
2	Disabling of the personal interlock
3	Switching ON/OFF modulator and klystron. Locking modulator
4	Check the hardware interlock thresholds, set technical interlock to warm mode
5	Set technical interlock to cold mode
6	Vacuum level check before start of coupler conditioning
7	Warm input RF Coupler conditioning
8	Coupler conditioning during cooldown
9	Cavities fine tuning to 1.3 GHz using LLRF system
10	Set the cavity input power limitation
11	Q_{load} , K_t calibration, $Q_{load \cdot HOM}$ at 1.3GHz with low RF Power
12	Flat - top cavity measurement at 10 Hz repetition rate
13	Cryomodule High RF Power and Heat Loads measurements
14	Detune cavities
15	LLRF check
16	LLRF test


3.5 CM Test Flow (improvements)

MONDAY	SHIFT 1	LOW POWER MEASUREMENTS
	SHIFT 2	LOW POWER MEASUREMENTS CRYMODULE CALIBRATION FLAT TOP MEASUREMENTS
TUESDAY	SHIFT 1	FLAT TOP MEASUREMENTS
	SHIFT 2	FLAT TOP MEASUREMENTS LLRF TESTS
WEDNESDAY	SHIFT 1	HEAT LOADS: MAGNET + SHIELDS
	SHIFT 2	HEAT LOADS: MAGNET + SHIELDS
THURSDAY	SHIFT 1	HEAT LOADS: RF + SHIELDS
	SHIFT 2	HEAT LOADS: RF + SHIELDS
FRIDAY	SHIFT 1	HEAT LOADS: RF + 2K CIRCUIT
	SHIFT 2	LLRF TESTS PREPARATION TO WARM-UP WARM-UP



DAY 1	SHIFT 1	LOW POWER MEASUREMENTS ROUGH CALIBRATION
	SHIFT 2	FLAT TOP MEASUREMENTS-1 RUN CCC PROBES CRYMODULE CALIBRATION
DAY 2	SHIFT 1	FLAT TOP - CONFIRMATION RUN
	SHIFT 2	LLRF TESTS
DAY 3	SHIFT 1	HEAT LOADS: RF + 2K CIRCUIT
	SHIFT 2	PREPARATION TO WARM-UP WARM-UP

The most time consuming steps of the original CM test procedure: HOM spectra, reaching thermal equilibrium of "cold cables" for calibration and a long heat loads measurement on shields. Improved CM test procedure shortens the test time at 2K almost by a factor of two.



M. Wiencek / SRF2015


3.6 CM LLRF Test

■ LLRF relevant parameters

- ❖ Lorentz force detuning constant
- ❖ Microphonics behavior (resonances)
- ❖ Loaded Q variations with gradients
- ❖ Model: piezo diag -> detuning parameter (microphonics cancelation)
- ❖ $8/9 \pi$ & $7/9 \pi$ mode of each cavity (-> controller!)
- ❖ Changes of Q_L with gradient (thermal coefficients)
- ❖ Calibration for piezo DC/AC (actuator & diag, switching)
- ❖ Calibration stepper motor & hysteresis
- ❖ Q_L range and opportunistic effects on cavity

■ Accept / reject accelerator module

- ✓ Lorentz force detuning exceeds normal value
- ✓ Extreme sensitivity to microphonics
- ✓ Abnormal behavior during fill/decay
- ✓ Sudden Q_L variation (multipacting in couplers)
- ✓ piezo / tuners not operable




3.7 RF Power Coupler Warm Conditioning Steps

step N	pulse length [μs]	RF power [kW]	time [hr]	comments
1	20	750	5..50	activity onset 50kW
2	50	750	2..20	
3	100	750	2..20	
4	200	750	2..20	
5	400	750	2..20	
6	800	700	2..20	
7	1300	700	10..100	
8	1300	100..700	10	RF power sweep
total			50..200	normally 2..5 days


Warm coupler conditioning at AMTF is done in 3 steps (with 5MW total RF power):

1. all 8 couplers are conditioned up to 450 kW;
2. couplers 1,2,3,4 are conditioned up to 750 kW;
3. couplers 5,6,7,8 are conditioned up to 750 kW.



4.1 Warm Coupler Conditioning History



Module XM14 warm couplers conditioning at AMTF (XATB2):




4.2 Warm Coupler Conditioning Time



4.3 CM Cold Test / Software Tools




cavity frequency tuning



piezo tuning / operation

custom software tools for the optimized test flow



flat-top pulse test at 2K

4.4 CM Cold Test / Calibration

Typical CM calibration data (module XM64)

	Cav 1	Cav 2	Cav 3	Cav 4	Cav 5	Cav 6	Cav 7	Cav 8
$Q_{\text{ext}} [10^6]$	4.61	4.60	4.58	4.62	4.68	4.62	4.62	4.59
$K_t [10^7]$	1.55	1.72	1.87	1.96	1.81	1.93	1.67	1.83
$Q_{\text{trans}} [10^{11}]$	2.51	3.07	3.64	3.98	3.42	3.88	2.92	3.49
Q_{HOM1}	6.3E+12	4.5E+12	2.8E+13	6.0E+12	4.3E+12	2.9E+12	2.0E+12	1.4E+12
Q_{HOM2}	6.2E+12	6.5E+13	4.3E+14	1.2E+12	2.5E+12	1.6E+13	6.8E+12	3.6E+14

Module RF calibration measurement is done with LabVIEW test software at 1.3 GHz

$$k_t = \frac{2}{L} \sqrt{\frac{R_{sh}}{Q} Q_L \frac{P_{for}}{P_{trans}}} \times \left[1 - e^{-\frac{\pi f t}{Q_L}} \right], [V / (m \sqrt{W})]$$

$$E_{ACC} = k_t \sqrt{P_{trans}}, [V/m]$$

Acceptance criteria:

- $Q_{\text{HOM1}}, Q_{\text{HOM2}} > 1 \times 10^{11}$
- $Q_{\text{HOM1}}, Q_{\text{HOM2}} > Q_{\text{trans}}$


4.5 CM Cold Test Results

Typical module cold test data in final report (module XM61)

	Name	$K_t [10^7]$	X-START [MV/m]	BD LIMIT			X - rays [mGy/min]		Operating Gradient		X - rays 10^{-1} mGy/min [MV/m]
				[kW]	[MV/m]	Limitation	GUN	DUMP	[MV/m]	Limitation	
1	CAV00271	1.36	26.1	244.3	31	PWR	1e-3	-	31	PWR	
2	CAV00293	1.45	27.6	230.7	31	PWR	4e-3	-	31	PWR	
3	CAV00298	1.67	20.6	234	31	PWR	1e-3	-	31	PWR	
4	CAV00303	1.74	16.6	242	31	PWR	2.2e-3	-	31	PWR	
5	CAV00309	1.54	-	233.3	31	PWR	-	-	31	PWR	
6	CAV00324	1.81	28.5	221.3	31	PWR	1e-5	-	31	PWR	
7	CAV00323	1.85	30.1	224.9	31	PWR	1.1e-5	-	31	PWR	
8	CAV00915	1.65	24.8	234.9	31	PWR	1e-4	1.2e-5	31	PWR	

Power $E_{acc} \left[\frac{MV}{m} \right]$	Avg P_{forw} [kW]	X-rays $\left[\frac{mGy}{min} \right]$		Comment	Power $E_{acc} \left[\frac{MV}{m} \right]$	Avg P_{forw} [kW]	$P_{cryo} [W]$ Σ	$Q_0 [10^{10}]$
		GUN	DUMP					
23.6	240.1	2.2e-4	2.7e-4	Close-loop	23.6	240.1	5.2	1.25
	133.3			without				
31	238.9	1.35	0.64					

4.6 CM Performance / Gradient




23.6 MV/m

XFEL GOAL



Cavity **operating gradient** in the module is defined as minimum of:

- Quench limit (breakdown) reduced by 0.5 MV/m
- X-ray limit (10^{-2} Gy/min)
- PWR – infrastructure limit equal 31 Mv/m



Averaged maximum (grey) and operating (red) gradients for all tested cryomodules. Yellow line is the power limitation

4.7 CM Performance / Quality Factor




Average quality factor for all tested cryomodules.

4.8 CM – Vertical Test comparison: max. Gradient

individual cavity comparison


(upper limit due to 31 MV/m limit in module test)



- we lose between vertical and cryomodule test
- average VT: (33.8) **30.5 MV/m** (clipped at 31 MV/m)
average CT: **28.4 MV/m** (includes limit at 31MV/m)

	Vertical test	Cryomodule test
Number of cavities	415	415
Averaged Gradient [MV/m]	28.9	27.2
RMS [MV/m]	2.5	4.6
Min Gradient [MV/m]	20.4	9.2
Max Eacc [MV/m]	31	31



Cavities in cryomodules: statistics



Number of cavities, which do not meet XFEL operating gradient criteria

Limitation for singles cavity maximum accelerating field

The average operating gradient for all of the tested cavities is equal to **27.2 MV/m**.



Single cavity maximum accelerating field limitation

4.10 CM Cryogenic Measurements

Typical cryogenic losses data (module XM64)

area	static	dynamic	total	acceptance
	static	RF 23.6 MV/m	static + total dynamic	static + total dynamic
40/80K	97.96 W	not measured ⁽¹⁾	not measured ⁽¹⁾	125 W
5/8 K	10.93 W	0.55 W ^(2,3)	11.48 W	16 W
2 K	5.33 W ⁽⁴⁾	3.17 W ⁽³⁾	8.5 W ⁽⁴⁾	14 W

⁽¹⁾ Due to short measurement period, it is not possible to reach steady-state equilibrium value, and therefore to determine the dynamic heat load

⁽²⁾ As RF operation during the dynamic heat load on 2K system was below 4 hours, it is not possible to reach steady-state equilibrium value, and therefore to determine the dynamic heat load

⁽³⁾ RF power set to 21.7MV/m instead of 23.6MV/m

⁽⁴⁾ Static heat loads for Feed-cap and End-cap (1.55 W) are already subtracted

4.11 CM Test Data Base

Module Test Results

Marked: 14



Details: More detail information

Result Statistics (14)

Print Quit

Cavities	Module	Test Information				Gradient [MV/m]				Heat Load @ 2K [W]				Qo	
		Date	No	Place		Average max.	Average oper.	Average distr.	Voltage	Static	Dynamic Magnet	Dynamic RF @15[MV/m]	Dynamic RF @23[MV/m]	@15[MV/m]	@23[MV/m]
XM42 test 1	XM51	25.Jun.15	1	AMTF	xatb2	27.03	26.00	24.47	195.74	7.18	0.00	0.00	4.71	.00E+00	.00E+00
XM43 test 1	XM52	02.Jul.15	1	AMTF	xatb1	26.59	26.21	24.66	197.24	15.42	0.00	0.00	2.87	.00E+00	.00E+00
XM44 test 1	XM53	09.Jul.15	1	AMTF	xatb3	28.31	27.83	25.72	205.76	7.19	0.00	0.00	4.24	.00E+00	1.10E+10
XM45 test 1	XM55	23.Jul.15	1	AMTF	xatb2prep	29.91	29.75	28.50	228.00	8.60	0.00	0.00	5.46	.00E+00	1.02E+10
XM46 test 1	XM56	31.Jul.15	1	AMTF	xatb3	30.84	29.55	28.30	226.42	3.95	0.00	0.00	5.03	.00E+00	1.29E+10
XM47 test 1	XM57	31.Jul.15	1	AMTF	xatb2	30.12	29.88	29.14	233.12	7.26	0.00	0.00	5.84	.00E+00	1.11E+10
XM48 test 1	XM58	27.Aug.15	1	AMTF	xatb2	23.89	23.45	19.97	159.74	4.33	0.00	0.00	2.86	.00E+00	1.46E+10
XM49 test 1	XM59	28.Aug.15	1	AMTF	xatb1	31.00	31.00	31.00	248.00	5.96	0.00	0.00	2.19	.00E+00	2.16E+10
XM51 test 1	XM60	04.Sep.15	1	AMTF	xatb3	30.57	29.07	27.32	218.60	4.49	0.00	0.00	5.10	.00E+00	1.08E+10
XM52 test 1	XM61	17.Sep.15	1	AMTF	xatb2	31.00	31.00	31.00	248.00	5.40	0.00	0.00	5.20	.00E+00	1.25E+10
XM53 test 1	XM62	24.Sep.15	1	AMTF	xatb1	31.00	30.90	30.81	246.46						
XM55 test 1	XM63	01.Oct.15	1	AMTF	xatb2										
XM56 test 1	XM64	02.Oct.15	1	AMTF	xatb1										
XM57 test 1	XM65	08.Oct.15	1	AMTF	xatb2										
XM58 test 1															
XM59 test 1															
XM60 test 1															
XM61 test 1															

Oracle DB is set-up to present and analyze the CM test data



5. Summary

- E-XFEL CM Test at AMTF@DESY is an important step in CM production. It provides a critical data for later E-XFEL Linac operation as well as multiple CM quality checks.
- Among many important CM Test steps the critical ones are:
 - ❖ Warm input RF power coupler conditioning;
 - ❖ Vacuum / Cryo-System leak tests at cold (2K);
 - ❖ Single cavities performance tests at cold (2K);
 - ❖ Auxiliaries (tuners/actuators, magnets etc.) tests at cold (2K);
- Testing the cavities provides the final CM performance data and allows for individual adapted cavity RF power distribution.
- Customized / adapted CM Test Field equipment is critical.
- Customized / adapted CM Test software tools play an important role.
- Taking CM test-stand into operation takes rather long time.
- Optimized and well documented CM Test procedures are critical. CM Test flow and steps are to be adjusted / changed in operation.
- CM Test data storage and analysis are of great importance.