



Managed by Fermi Research Alliance, LLC for the U.S. Department of Energy Office of Science

PXIE Overview


Paul Derwent

PIP-II Collaboration Meeting

9-10 November 2015

PXIE Scope

- Development and integrated systems testing of PIP-II Front End components (PXIE)
 - Deliver 1 mA average current with 80% bunch-by-bunch chopping of beam delivered from the RFQ
 - Demonstrate efficient acceleration with minimal emittance dilution through at least 15 MeV



- All components are being designed and fabricated to PIP-II specifications and our intention is to reutilize as much as possible.

Beam requirements at the end of PXIE

Parameter	Value	Unit
Beam kinetic energy, Min/Max	15/30	MeV
Average beam power	≤ 30	kW
Nominal ion source and RFQ current	5	mA
Average beam current (averaged over $> 1\mu\text{s}$)	1	mA
Maximum bunch intensity	1.9×10^8	
Minimum bunch spacing	6.2	ns
Relative residual charge of removed bunches	$< 10^{-4}$	
Beam loss of pass-through bunches	$< 5\%$	
Nominal transverse emittance*	< 0.25	μm
Nominal longitudinal emittance*	< 1	eV- μs


* RMS, normalized

- Capability of an arbitrary micro-bunch structure

PXIE


- Scope:

- A CW H- source delivering 5 mA at 30 keV
- A low energy beam transport (LEBT) with beam pre-chopping
- A CW RFQ operating at 162.5 MHz and delivering 5 mA at 2.1 MeV
- A medium energy beam transport (MEBT) with integrated wide band chopper capable of generating arbitrary bunch patterns at 162.5 MHz, and disposing of up to 5 mA average beam current



- Low β superconducting cryomodules capable of accelerating 2 mA of beam to 25 MeV
- Associated beam diagnostics
- Beam dump capable of accommodating 2 mA at full beam energy for extended periods.
- Associated utilities and shielding

PXIE (PIP-II Injector Experiment)



PXIE will address the address/measure the following:

- LEBT pre-chopping : Demonstrated
- Vacuum management in the LEBT/RFQ region : Demonstrated
- Validation of chopper performance
 - Bunch extinction, effective emittance growth
- MEBT beam absorber
 - Reliability and lifetime
- MEBT vacuum management
- CW Operation of HWR
 - Degradation of cavity performance
 - Optimal distance to 10 kW absorber
- Operation of SSR1 with beam
 - CW and pulsed operation
 - resonance control and LFD compensation in pulsed operations
- Emittance preservation and beam halo formation through the front end

Collaborators

ANL: HWR


LBL: LEBT, RFQ

SNS: LEBT

IIFC: MEBT, RF, SSR1

PXIE Ion source and LEBT



- Commercial ion source
 - D-Pace, Inc.
 - 30 kV, 10 mA DC
- 3 Solenoids
- Bending dipole
 - Accommodate 2 IS for PIP-II
 - Part of Personnel Protection System
 - No direct line of sight between IS and SRF
- Chopper
 - Pre-chopping, MPS, pulse mode
- Possibility of partially un-neutralized transport
- Possibility of scraping the beam at various locations
 - Tail particles management



Scheme of
PXIE IS and LEBT
in final configuration



Ion source and LEBT status

- IS and LEBT are assembled, fully commissioned
 - Straight configuration; dipole will be installed in FY16
 - Beam current up to 10 mA in pulse and DC modes
 - 24 and 72 hrs runs at 5 mA; current stabilization loops
 - At 5 mA, Twiss parameters reconstructed to the RFQ entrance are on target



LEBT diagnostics

- DCCT, toroid, electrically isolated electrodes, Faraday cup (not permanent)
 - Beam current, controlled beam loss
- Allison-type emittance scanner
 - Designed and built in collaboration with SNS
 - Front-slit made of TZM pressed against water-cooled aluminum blocks
 - Workhorse for beam measurements
 - Located at the end of the beam line
 - Moves as more elements are added
 - Final permanent location is in the IS vacuum chamber
 - Baseline for MEBT Allison scanner design





RFQ

- Designed and fabricated by LBNL
 - 4 vane, 4 module brazed copper body
 - Fixed tuners
 - Output energy: 2.1 MeV
 - Below neutron production level
 - Similar RFQ has been commissioned at IMP (Lanzhou, China) with 10 mA CW
 - Delivered beginning of September
- Two 75 kW 162.5 MHz solid-state amplifiers are installed and partially commissioned



RFQ setup

- Installation in progress
- Resonance control via cooling water circuit
- Identical and cross-calibrated current transformers before and after RFQ to directly measure transmission



MEBT


- Goals for PXIE MEBT
 - Demonstrate creation of an arbitrary bunch pattern from initially CW 5-10 mA, 2.1 MeV H^- beam
 - Compatible with SRF downstream
- All major components have been prototyped and most have been ordered or in fabrication
 - Except for some of the diagnostics
 - Mechanical design of the integrated beam line is in progress
- Parts of MEBT will be used to characterize the beam from the RFQ

First configuration of the MEBT to commission the RFQ is being assembled





MEBT concept

- Transverse focusing with 2 doublets and 7 triplets
 - First short section for beam matching; 1.14 m period after
- Longitudinal focusing with 3 bunching cavities
- Chopping system: Two TW kickers in sync + absorber
- Last ~2 m are particle-free, UHV
- Scrapers: 4 sets by 4 jaws in each
 - Independently moving, electrically isolated, radiation-cooled plates




MEBT plan: upcoming year

- Build it out in sections
 - MEBT 1:
 - 2 doublets + 1 buncher
 - diagnostics section varies for different measurement
 - MEBT-2:
 - add 4 triplets, 1 buncher, kicker prototypes




PXIE: HWR

- Half Wave Resonator Cryomodule:
 - 8 162.5 MHz $\beta=0.11$ Half Wave cavities
 - 8 SC focusing solenoids (&BPM)
 - 2.1 MeV \rightarrow 11 MeV
- In collaboration with Argonne
- Design complete, under fabrication at Argonne
 - Testing of all production components in 2016
 - Assembly in 2017
 - Delivery/Installation Q3s 2017



PXIE: SSR1


- Single Spoke Resonator Cryomodule:
 - 8 325 MHz $\beta=0.22$ Single Spoke cavities
 - 4 SC focusing solenoids (& BPM)
 - 11 MeV \rightarrow 25 MeV
- India Institutes Fermilab Collaboration (IIFC)
 - Cavity and Solenoid Design (FNAL) complete
 - 12 cavities fabricated (10 FNAL, 2 IUAC New Delhi)
 - CM design underway
 - Fabrication/Assembly 2017



dressed SSR1 cavity in
test cryostat

PXIE infrastructure

- CMTF building, housing PXIE, has all required capacity
 - Cryo, power, water
 - Distribution systems are being designed and implemented
- All components for the PXIE cave are on hand



PXIE plan

- FY16
 - Commission RFQ (RF and beam)
 - Install most of the MEBT magnets
 - Install and test kicker prototypes
- FY17
 - Finalize design of all MEBT components
 - Receive HWR
 - Installation of Cryo distribution, HWR, MEBT 3
- FY18
 - RF commissioning of HWR,
 - Installation of SSR1 & HEBT
 - RF Commissioning of SSR1
 - Beam operation?
- FY19
 - Final beam parameters

Collaborations in PXIE

- LBNL: Ion source, RFQ
 - SNS: Emittance Scanner
- } In hand
- ANL: HWR Cryomodule – FY17
 - delivery dependent on funding availability
 - IIFC:
 - MEBT magnets: Quad and Dipole delivery through FY16 & 17
 - SSR1 cavities/He vessel/Tuners: FY16
 - SRF Interlocks, 325 MHz amplifiers, LLRF system
 - FY16, 17, 18
 - WG1: address opportunities for additional collaboration

Working group 1: PXIE

- We would like to focus on the plan for the next three years:
 - What are the goals and deliverables of the R&D phase of PXIE during this time frame?
 - What are the identified responsibilities among collaborators and where are opportunities for additional collaboration?

12:30 - 17:15 Working Group Meetings: Working Group 1

Location: Floating Point

12:30 **PXIE Plan: 2016, 2017, 2018** 30'

Speaker: Paul Derwent (Fermilab)

13:00 **RFQ Commissioning Plan** 30'

Speaker: Mr. James Steimel (Fermilab)

13:30 **MEBT Components: Buncher cavities, kicker/absorber, vacuum system** 30'

Speaker: Alexander Shemyakin (Fermilab)

14:00 **Instrumentation Development** 30'

Speaker: Vic Scarpine (Fermilab)

14:30 **HWR** 30'

Speaker: Dr. Peter Ostroumov (Argonne National Laboratory)

15:00 **Break** 30' (IARC Auditorium)

15:30 **LLRF and Resonance Control for PXIE: RFQ, HWR, SSR1** 30' (IARC Auditorium)

Speaker: Mr. Brian Chase (FNAL)

16:00 **PXIE Cryo Distribution** 20'

Speaker: Michael White (Fermilab)

16:20 **Integration of HWR, SSR1, and Cryo Distribution into PXIE enclosure** 20'

Speaker: Mr. Curtis Baffes (Fermilab)

16:40 **Discussion / Preparation for WG1 Report** 20'

Joint with WG2

Summary
