



## SBND TPC Status

Kostas Mavrokoridis -TPC Manager ([k.mavrokoridis@liverpool.ac.uk](mailto:k.mavrokoridis@liverpool.ac.uk))

Directors' Progress Review of SBN

15-17 Dec 2015, Fermilab



# Outline -Key TPC Components

- APA
  - APA frames
  - Geometry boards, mounting platforms
  - Wire mesh, wire support, E-diverter
  - APA assembly procedure and tooling
  - Interface to electronics; faraday cage
  - APA winding
- CPA
  - CPA frames & panels
  - HV Cup
  - CPA suspension features
- Field Cage
  - Field cage panels
  - Roll-formed metallic profiles
  - Resistor divider board
  - Supporting beams
- HV Feedthrough
- TPC Integration
  - APA Interconnect and alignment
  - TPC suspension features
  - TPC assembly procedure and tooling

***Preliminary Design Report (docdb ID 613)***      **Review was held Sept 2015**

<http://sbn-docdb.fnal.gov:8080/cgi-bin/RetrieveFile?docid=613&filename=sbnd-tpc-PDR-review.pdf&version=1>



# The SBND TPC Working Group



Collaboration between UK and USA Institutions,  
funded by NSF and STFC

<b>Deliverables</b>	<b>Institution</b>
Four APA Frames (2UK&2US)	University of Sheffield
Winding two APAs	University of Manchester
Winding two APAs	Chicago, Syracuse and Yale
CPAs	University of Liverpool
HV Feedthrough	UCL and Yale
Field Cage	BNL and Yale
QA/APA cold tests	Lancaster University
Integration, Assembly, and Installation	Chicago, BNL and Fermilab

# The SBND TPC Working Group



## The WBS Managers

40SBN/2	<u>SBND Construction</u>	WBS Managers	WBS deputies
40SBN/2.3	<u>TPC Construction</u>	Kostas <u>Mavrokoridis</u>	-
40SBN/2.3.1	TPC Preliminary Design	Bo Yu	-
40SBN/2.3.2	TPC Final Design	Bo Yu&Peter Sutcliffe	-
40SBN/2.3.3	APA Frame Construction - (UK)	Trevor Gamble & Nicola <u>McConkey</u>	-
40SBN/2.3.4	APA Geometry Boards Production - (US)	Bo Yu	<u>Serhan Tufanli</u>
40SBN/2.3.5	APA Construction - (UK)	Stefan <u>Soldner-Rembold</u>	<u>Jarek Nowak</u>
40SBN/2.3.6	APA Construction - (US)	Mitch <u>Soderberg</u>	-
40SBN/2.3.7	CPA Construction - (UK)	Peter Sutcliffe & David Payne	-
40SBN/2.3.8	HV Supply and Feed Through Construction - (US-UK)	Anna <u>Holin</u> & Bonnie Fleming	<u>Serhan Tufanli</u>
40SBN/2.3.9	Field Cage Construction - (US)	Bo Yu	<u>Serhan Tufanli</u>
40SBN/2.3.10	TPC Connection Frame Construction - (US)	Rich Northrop & Dave Schmitz & Bo Yu	-
40SBN/2.3.11	TPC Assembly Preparations - (US)	Rich Northrop & Dave Schmitz & Bo Yu	-



# TPC Requirements

- The TPC volume is large enough to achieve the physics goals of the experiment.
- The 3 mm wire pitch is chosen, as in the MicroBooNE and ICARUS detectors, to enable electron/photon separation to be achieved with identical efficiency.
- Limit variation in the wire sag to  $< 0.5$  mm such that it does not significantly impact the position and energy resolution of the detector.
- The APAs are constructed in a manner that guarantees no wires will break during the operational life of the experiment.
- The electric field must not exceed 30 kV/cm inside the liquid, and not exceed 5 kV/cm in the argon gas to prevent HV breakdown.
- Minimize dead space in the active volume: place the cathode in the center of the TPC.
- The wire plane and HV cathode designs must be compatible with the photon detection system designs being considered for the experiment.
- Use only materials that are compatible with high-purity liquid argon.


# TPC Parameters



Parameter	Value
TPC active volume	5m (L) x 4m (H) x 4m (W), 112 metric ton active LAr mass
Number of TPC cells	2 drift volumes, 2m drift length in each
Anode Plane Assembly (APA)	2.5m x 4m active area, with cold electronics mounted on 2 sides.
Wire properties	150 $\mu$ m diameter, CuBe
Wire planes	3 planes on either side of an APA U & V at $\pm 60^\circ$ to vertical, Y vertical
Cathode bias	-100 kV @ 500V/cm drift field
Number of Wires	2816 channels/APA. 11264 wires total in TPC.
Wire tension	0.5 kg at room temperature




# SBND TPC Layout



SBN





"mobile" cryostat lid plate



60 cm insulation

"fixed" cryostat lid plate

Outer mechanical support. Membrane cryostat built inside.

# APA Frame



University of Sheffield & Chicago



Leveling plate

- For 3 mm wire plane separation need better than  $\pm 2$  mm flatness, plate adjustable to  $\pm 0.5$  mm

- Fabricated from 150 x 100 x 5mm 304 Stainless Steel rectangular hollow sections (RHS)



FEA: Max X displacement 0.85 mm

- Bare frame weight = 480 kg
- $\pm 2$  mm flat welded frame

SBN






# APA Frame



Prototyping levelling plates -deformation check at Sheffield



Shims








# APA Frame




## Full Assembly Deflection


Type: Displacement  
Unit: in  
7/9/2015, 5:09:57 AM




Top & Bottom inserts  
plus 9 12mm bolts



# APA Frame




Lifting fixture



Screw mounted attachment - 8 M6 screws


Tack welded Tube attachments



Deformation while lifting at horizontal position 0.7 mm

# APA Frame

## Final bare frame design



APA bare frame and jig review on Dec 17<sup>th</sup>


Almost ready to place an order

*Quote from Portobello:  
4 APAs and Jig 129k GBP*


*Levelling bars and laser surveys 43k GBP*



# APA Construction




APA leveling plates to achieve flat surface for the geometry boards ( $\pm 0.5$  mm adjustment)




Three layers of the Geometry Boards

- All geometry boards are modeled in 3D
- Layout of the Y\_top Geometry Board Complete





PRELIMINARY - FOR QUOTING ONLY  
 BROOKHAVEN NATIONAL LABORATORY  
 Y PLANE WIRE CARRIER - TOP  
 10-1605-1 REV -  
 KJW 10-30-15  
 TOP ASSEMBLY





Total Estimate for all boards: ~80k\$

# APA Construction – Electron Deflector



Electron deflector to recover the “dead” region (15mm) between the two interconnected APAs

- To be tested in 35t
- Preliminary studies with the Liverpool camera readout TPC in gas




# APA Winding



Two winding Facilities { Daresbury, UK (Manchester group)  
Yale, USA (Syracuse group)

## UK Daresbury Space





# APA Winding



UK Daresbury space ready to be used






# APA Winding



## Winding Procedure UK: Semi automated



- Frame is supported on a turntable which rotates to three working angles.
  - Working space  $\sim 6 \times 6 \text{ m}^2$
  - Full access for operator(s)
- Wiring head traverses on cross beam, which itself travels on fixed side rails.
- Wires are strung one at a time:
  - Ease of design/development
  - Quality control is wire by wire
  - Minimal working area
  - Scalable to any size frame

- Procedure:

1. Solder wire at one side.
2. Draw wire over guides to other side.
3. Tension.
4. Solder on other side.
5. Cut wire.


- Finishing:

- Glue over soldered joints and board edges to fix against possible creep

- Automated option:

- Computer-controlled stepper motors ensure precise positioning. (otherwise manually)

Turntable framework and bridge design is complete



# APA Winding Yale The New Wright Laboratory



## Facilities

- 85,200 sf of lab and office space include
- PI laboratories
  - Specialized laboratories
  - Prototyping, teaching, fabrication shops



# APA Winding




## The New Wright Laboratory



## Winding Procedure US: Manual

*Detector assembly and staging areas.  
Currently undergoing renovations.  
Available in summer 2016*

## Syracuse group works with PSL




# APA Winding Winding Procedure US: Manual




Prototype expected delivery  
February 2016

Cost prototype ~40k USD  
Cost for full machine ~50k USD


Load wires here




Place wires in desired location




Procedure for wires to be placed over the edge:



1. Starting position





2. The 1<sup>st</sup> fold brings the wire outside the APA perpendicular to the side



3. The 2<sup>nd</sup> fold brings the wires down along the edge geometry boards where they are then soldered






**Cost 39k GBP**


- 5 mm aperture
- 1 mm wire ID
- 70% transparency

Baseline design transparent mesh



Weight:  
 half CPA Frame 130Kg  
 each Mesh Panel 8.5Kg  
 Total for 2 CPAs around 440Kg

CPA Made up of a Stainless steel frame and 8 stainless steel wire mesh smaller frames.




FEA: Deflection 0.116 mm

# HV supply & Feedthrough

Yale and UCL groups





100 kV FT, Spring loaded tip based on 35ton design



Heinzinger PNChp 150000 – 1 neg  
High Precision – High Voltage – Power Supply


*Material cost is 67k \$*

- Simulations:
  - electric field
  - thermal




# Field Cage

Work led by BNL and Yale



PCB based design


Roll-formed metallic profiles  
Field cage Design





# Field Cage

PCB design based on 35t




Cost ~250k USD




## Roll-formed metallic profiles design

A pre-assembled module:  
 32 bars @ 6cm pitch to cover 2m drift.  
 There is no electrical connection  
 between adjacent field cage modules.  
 Each module has its own  
 resistive divider chain.



Profile and cap locking scheme  
 Resistive divider and surge suppressor chain



Cost ~67k USD




Awaiting performance of 35t and Roll-formed field cage prototype test at CERN

# TPC Integration & Installation




Work led by Chicago, BNL and Fermilab

## APA sub-assembly scheme



M12 bolt connecting the frames




Connected using two custom connection fixtures, allowing uniform gap and ensure alignment of U/V wires across two frames

# TPC Integration & Installation




## CPA Integration

G10 connecting brackets



G10 hanging brackets






# TPC Integration & Installation





TPC assembly in the DAB tent

Work led by Chicago, BNL and Fermilab




(See Joe Howell's talk for more details)



Model of SBND assembly

# TPC Schedule



All TPC components to be delivered to Fermilab by March 2017