



Exceptional service in the national interest




Z Machine Overview

Joel Lash, Ph. D.
Senior Manager, Z Facility R&D



Sandia National Laboratories is a multi-program laboratory managed and operated by Sandia Corporation, a wholly owned subsidiary of Lockheed Martin Corporation, for the U.S. Department of Energy's National Nuclear Security Administration under contract DE-AC04-94AL85000.



Summary

Pulsed Power / Facility

- 22 MJ stored energy
- 3 MJ delivered to the load
- 26 MA peak current
- 1 - 100 Megabar
- 100 - 1000 ns pulse length
- ~1 shot per day / ~150 shots per year

Experimental Loads


- Wire Arrays – Radiation Sciences
- Liners – Inertial Confinement Fusion, Material Sciences
- Gas Puff – Radiation Sciences
- Flyer Plates – Material Sciences

Subsystems


- Laser X-ray Backlighter
- Cryogenics
- External Magnetic Fields
- Gas Fills
- Explosive Containment for High Z Materials

Diagnostics

- X-Ray
- Neutron
- Optical
- ZBL Backlighter




Z is a unique world class pulsed power facility at Sandia National Laboratories



36 Marx generators
2160 capacitors


~ 1M gallons of transformer oil
~ 0.5M gallons of deionized water

66,000 liter
vacuum vessel




Z compresses electrical energy in both space and time . . .

Charge for 3 minutes to reach 85 kV




330 TWs & 2.5 MJ of x-ray output in a few ns

. . . and literally shakes the earth almost every day!




A complex series of conductors combine currents for the load

Z vacuum insulator stack and MITLs




Post hole convolute system and load




ICF liner load




DMP load





Z Shot Rate and Shot Planning


Z Shots by Calendar Year



~767 Shot Days were requested by LANL, LLNL, and SNL in CY16 – 3X more shot requests than available!

Z Shot Planning

- Typically plan for 140 – 160 shots a year based on budget
- Single shift operation:
 - 6 am work day start
 - 5 pm shot window closes
- Nominally 1 shot per shot day
 - 3 – 6 days for containment shots
- Most maintenance performed in parallel with daily shot preparations
- External PIs work with internal PIs for planning and execution



Z Core Capabilities: Z-Beamlet

Z-Beamlet Basics


Z-Beamlet High Bay




Z facility



- ZBL is routinely used to deliver ~ 2.4 kJ of 2ω light in 2 pulses for backlighting experiments on Z
- In 2014 we added bandwidth to the laser; can now deliver ~4.5 kJ of 2ω in a 4 ns pulse.
- It should be possible to reach 6-10 kJ of laser energy (e.g., as on the NIF)
- ZBL Parameters:
 - Up to 6 kJ @ 1053nm
 - Up to 4.5 kJ @ 527nm
 - Up to 4 shots per day
 - Typically 0.3 – 4 ns pulse length in a 31x31 cm² beam
 - 1 - 9 keV radiography




Z Core Capabilities: High Z




Post-shot cross section of UCV showing metal to metal seal between anode closure tube and cathode

- Valve closes in $\sim 40 \mu\text{s}$
- Leak spec is $< 1\text{e-}5 \text{ atm-cc/sec}$
- Typical leak rates are $1\text{e-}8 \text{ atm-cc/sec}$





We have a proven containment system for Pu experiments used many times




Upcoming Capabilities: Tritium

A Sandia Grand Challenge LDRD project is assessing the feasibility of using an explosive containment system

- Conducted three tritium containment development experiments using light gas surrogates
- Validated use of the existing hazardous material containment system as a viable test platform for tritium




- Developed and demonstrated the Z Gas Transfer System (ZGTS)
- Planning to conduct two trace tritium (0.1% - 1.0%) experiments in CY16 using the ZGTS in a containment system




Daily Z Activities: Unload and Refurb of Z's Center Section

Before Shot





After Shot



During a Z experiment several kilograms of material is destroyed and vaporized. Significant refurbishment activities are required between each shot which consist of:



1. Removal of in-chamber diagnostics and blast shield
2. Removal of Post Hole Convolute
3. Removal of Magnetically Insulated Transmission Lines (MITL)
4. MITLs are flipped and placed into a HEPA filtered 'garage'
5. Cleaning / Grinding of MITLs and plastic insulator stack. All work requires Tyvek and Respirators due to Beryllium exposure






Daily Z Activities: Loading and Diagnostic Activities

1. Install Magnetically Insulated Transmission Lines
2. Install post hole convolutes
3. Install the target
4. Install in-chamber diagnostics
5. Align diagnostics





Daily Z Activities: Oil & Water Processing


- Drain/Fill ~400,000 gallons of water
 - 30 minutes to drain or fill
- Drain/Fill ~600,000 gallons of oil
 - 80 minutes to fill and 65 minutes to drain



- Water is stored in twelve 50,000 gallon underground tanks
- Oil is stored in four 250,000 gallon tanks outside of the building



Oil System Control Panel (circa 1985)



Daily Z Activities: Pulsed Power Inspections, Repairs & Configuration

- Drain oil and water tanks
- Teams will first 'ground' the machine
- Inspection of over 4000 components consisting of capacitors, resistors, gas switches, laser alignment, plastic rods
- Perform repairs and preventative maintenance as needed




Removal of a Pulse Forming Line (PFL)

Inspection of a Marx Trigger Generator (MTG)



Shorting of Marx Banks



Daily Z Activities: Shot Preparations



Vacuum System

- 20 Vacuum Pumps (Cryo, Turbo & Roughing) on a 66,000 liter vessel
- Able to achieve shot pressure in 90 minutes (3×10^{-5} Torr)
- Control system is circa 1985




Sulfur Hexafluoride (SF6) System

- System contains ~3000 lbs. of SF6
- SF6 is used as an insulating gas for laser trigger gas switches, Marx spark gaps, and Marx trigger generators.
- Infrastructure is circa 1985



Control Monitor & Data Acquisition System

- We record ~800 fast signals on each shot.
- A 2-man team operates the machine for downline activities



Safety and Facility Upgrades

Vacuum Chamber Air Exchange



Replacing Aging/Legacy Equipment

- Over the past few years, many legacy control and monitoring systems have been replaced and/or upgraded.
- We are developing new systems to improve the capability, safety and reliability of control and data acquisition systems for Z.

Replacing the Be Refurbishment Tent



Z's control system computer. In place since 1993.
Replaced May 2015



Z's vacuum control system In place since 1985.



Z's water drain/fill control system In place since 1985.

Improved Information Management and Communications

Z Shot Schedule

Z Shot Schedule [Log In] Home Change Log Administration

Scheduled Shots: 11/06/2015 From: 11/06/2015 To: 11/06/2015 Export filtered data to Excel

Drag a column header and drop it here to group by that column

Day	Date	Program	Experiment Name	Hardware Set	Shot Number	Principal Investigator	Shot Director	ESD	CS	DMS	ESK	Shot Size	Fit Check	Engineering POC	Setup Hardware Set	Plan Type
Mon	11/09/15	RD	Arriba 10a	AD25A	2295	M. Gomez	Schaffner	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	ESU	<input checked="" type="checkbox"/>	Robertson	N/A	Planned
Tue	11/10/15	RD	Arriba 10a	AD25A	2296	M. Gomez	Schaffner	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	ESU	<input checked="" type="checkbox"/>	Robertson	N/A	Planned
Wed	11/11/15	RD	Arriba 10a	AD25A	2297	M. Gomez	Schaffner	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	ESU	<input checked="" type="checkbox"/>	Robertson	N/A	Planned
Thu	11/12/15	RD	Arriba 10a	AD25A	2298	M. Gomez	Schaffner	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	ESU	<input checked="" type="checkbox"/>	Robertson	N/A	Planned
Fri	11/13/15	RD	Arriba 10a	AD25A	2299	M. Gomez	Schaffner	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	ESU	<input checked="" type="checkbox"/>	Robertson	N/A	Planned
Sat	11/14/15	Weekend	Weekend	N/A	N/A	N/A	Schaffner	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	ESU	<input type="checkbox"/>	N/A	N/A	None
Sun	11/15/15	Weekend	Weekend	N/A	N/A	N/A	Schaffner	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	ESU	<input type="checkbox"/>	N/A	N/A	None

Lab-Wide Z Status Page

Est. Time Until Shot: TBD Est. Shot Time: 13:39:39 Current Time: 02/04/2016 Shot #: 2298 Hardware #: AD25A Shot Director: Schaffner Experiment: Arriba 10a Experiment #: M. Gomez

Access: Single Point

Remove MITL Refurb MITL Install MITL Install Load Hardware Diagnostic Alignment Pumpdown Chamber

Water Drain Water Inspections Water Fill Debubble Dye Stack Debubble Preheat Checklists 15 Minute Lockup Downtime Shot

Oil Drain Oil Inspections Leak Checks & Light Tests Oil Fill

Vacuum Status

Top (TC24.1G4) 1.2E-4 Bottom (IG1) 6.5E-5

Summary Messages: Debubble System Minutes remaining: 20.0 Debubble System Minutes remaining: 17.5 Debubble System Minutes remaining: 15.0 Debubble System Minutes remaining: 12.5 Debubble System Minutes remaining: 10.0

Preheat: All further requests for CM/DAS Change for the current shot must be made in person or by telephone and may result in delays to the downtime shot. Thaddeus Preston # 1324 on 2/4/2016

Debubble System Minutes remaining: 7.5 Debubble System Minutes remaining: 5.0 Debubble System Minutes remaining: 2.5 Debubble System Stack debubble has finished

Z Shot Roster

Experiment Name	Mon 04/20/2015	Tues 04/21/2015	Wed 04/22/2015	Thurs 04/23/2015	Fri 04/24/2015
Shot Director	De Luna	De Luna	De Luna	De Luna	De Luna
Principal Investigator	Knapp	Knapp	Knatson	Lambie	JP Davis
Engineering POC	Reneker	TBD	Williams	Tereyfort	Williams
CM Operator	Baker	Baker	Radovich	Preston	Bock
CM Coordinator	Floor	Floor	Preston	Floor	Preston
DAS Operator (CM POC)	Baker	Floor	Preston	Floor	Preston
Vacuum Shot Support	Bock	Bock	Bock	Bock	Bock
ESS Shot Support	Roznowski / Reeves	Divett / Jostle	Cortez / Spees	McCarthy / Avila	Cortez / Avila
LTS Shot Support	Potter	Potter	Potter	Potter	Potter
Access Evacuator (Top)	Roznowski / Potter	Jostle / De Luna	Spees / Potter	Avila / De Luna	Cortez / Potter
Access Evacuator (Bottom)	De Luna / Potter	Divett / Baker	Cortez / De Luna	McCarthy / Potter	Avila / Bock
MITL Refurb & Wipe	York / Cline / White	York / Cline / White	York / Cline / White	York / Cline / White	York / Cline / White
Stack Refurb & Wipe	Justus / Roebuck / White	Justus / Roebuck / Macroneels			
Lab 101	York / Olivias	York / Olivias	York / Olivias	York / Olivias	York / Olivias
Top Side Load	York / Olivias	Macroneels / Cline	Macroneels / Cline	Macroneels / Cline	Macroneels / Cline
Bottom Side Load	Roebuck / White	Roebuck / White	Roebuck / Olivias	Roebuck / Justus	Roebuck / White

Z Diagnostic Request System

Diagnostics & Subsystems [Log Out] Home Set Favorites Change Log Shot Schedule I-machine Status

Diagnostics & Subsystems Request

Experiment Name: Arriba 10a Scheduled Date: 02/04/2016 Hardware Set Number: AD25A Copy from Shot Number Hardware Set: 2297

Overall Status: 0% Overall Quality Code: 0% Principal Investigator: M. Gomez Co-Principal Investigator: N/A Shot Number: Reports Diagnostic Configuration Details Last Modified By: Dunham 12/8/2015 1:35 PM

1 - EXPERIMENT OVERVIEW 2 - DIAGNOSTICS 3 - SUBSYSTEMS & LIDS 4 - OTHERS


LOS 50: PCD, XRD, TEP, BOLO, nTOF, TITXL, LOS 130, LOS 150, LOS 170, PCD/XRD/BOLO, MLM

LOS 210: PCD/XRD/BOLO, nTOF, LOS 270, LOS 310, Be Probe, LOS 330, TREX, ZBL, Backlighting, XRYS, Preheat

BOTTOM: 4-A, 4-B, 0-A, 0-B, 10-A, 10-B, XRD

CHAMBER: CRIB, VISAR, PDV, Shock Breakout, SVS, SVS3, TIPC

Legend: Not Requested, Requested with No Configuration, Requested with Configuration Submitted, Requested with Configuration Submitted and Approved, Required



WP&C at Z leverages Sandia's corporate processes and structure

Work Planning and Control Criteria for Safe Design and Operations (MN471021)

Division 1000 Implementation of MN471021 Work Planning and Control Criteria for Safe Design and Operations

Center 1600 Engineered Safety and Work Planning and Controls (DRAFT)

Requirements for New or Changed Systems at the Z Facility (ADM_REQMTSYS_ADPRO)

Acceptance of Work Scope


Acceptance of Safety Case

Work Authorization

Procedures (Technical Work Documents) to Perform Work


Safety Case is documented in WP&C Repository

Procedures (or SWP) and JSA approved and available for use




Z facility activities involve many similar and some unique and complex hazards

- High voltage – 10's of Kilovolts to Megavolts
- High currents – up to 26 Million amps in Z
- X-rays – 2 Megajoules (~ stick of dynamite equivalent)
- Neutrons
- Radioactive materials
- Beryllium operations
- Underwater diving
- Heavy lifting – the Z voltage insulator stack is ~39,000 lbs
- Large fluid movement – e.g. ~600,000 gallons of oil
- Laser light – 6,000 Joules at ZBL
- Adhesives, solvents, rad and Be waste
- Complex mechanical structures with human interaction hazards



Commonality and consequence drives our WP&C/Safety Case approach


- Many hazards are common to our AWL that span and cross-cut multiple organizations
- High consequence puts the focus on those hazards which create the greatest personnel risk
- With Z having 10s of people from many organizations working together in parallel and in proximity, our initial approach was to think about 'safety areas' as a synonym for 'safety case'
- This forces more of the discussion to be at the system level looking at interfaces and communications and motivates critical questions from a different vantage point – this will provide us the greatest value
- **Focus on the discussions and critical thinking which become embodied in the Manager Safety Case narrative.**



We created a Safety Case universe to envelope Z activity-level work


Safety Area
Gas House Systems
Oil Systems
Water Systems
Craining / Rigging / Hoisting
General Lab: B-Dot Calibration Lab
Gas Puffs on Z
Diving at Z
Beryllium Safety
General Lab: Cable and Component Assembly (MO2)
Diagnostic Operations at 983
Z Shot Execution (CM/DAS)
Dark Room (960/2097A)
MCP Lab (970/211) NSTec Ops
General Labs: Imaging & Spectroscopy Light Labs
1600 Storage Facilities
ZBL Ops on Z
Z Pulsed Power
Center Section Ops
Vacuum at Z
Laser Trigger Section at Z
Load Assembly (Lab101)
Z Shot Planning
General Lab: Neutron Diagnostics for Z
Applied B-Field on Z
Cryo / Gas Fill Operations
Pu/U Handling and Experiments





Management led Safety Case development has shown benefits

- Identified a potential improvement by adding an audible high-bay alarm if diver air quality does not meet specified standards
- Examining technical basis for 2 kV Marx bank discharge threshold being the safe-entry level for post-shot operations
- Investigating Control Monitor system reliability in measuring 'zero energy' in the Pulsed Power system
- Added second air monitoring system to mitigate asphyxiation hazard in Z gas house
- Gas feed line caps were installed for the Z Gas Puff system to prevent the potential spread of Be contamination between shots
- Purchased and installed Smoke Absorbers at soldering stations
- Implemented periodic inspection of wall mounted cable rack in trailer lab
- Designing engineered system to replace manual system currently in place to move fluids in and out of Z (primarily a facility safety concern)
- Identified mitigations for head injuries while working in Z diagnostic boats



Questions?

