



Managed by Fermi Research Alliance, LLC for the U.S. Department of Energy Office of Science

R&D Program Overview

Paul Derwent


PIP-II Machine Advisory Committee Meeting

15-17 March 2016

PIP-II Proposed Technical Approach

- Construct a modern 800-MeV superconducting linac, of CW-capable components, operated initially in pulsed mode
 - Increase Booster/Recycler/Main Injector per pulse intensity by ~50%
- Increase Booster repetition rate to 20 Hz
 - Maintain 1 MW down to 60 GeV or,
 - Provide factor of 2.5 increase in power to 8 GeV program
 - Improve slip-stacking efficiency via larger orbit separation
- Modest modifications to Booster/Recycler/Main Injector
 - Accommodate higher intensities and higher Booster injection energy
- This approach is described in the Reference Design Report:
 - Builds on significant existing infrastructure
 - Capitalizes on major investment in superconducting RF technologies
 - Eliminates significant operational risks inherent in existing 400 MeV linac
 - Existing linac removed from service upon completion of PIP-II
 - Siting consistent with eventual replacement of the Booster as the source of protons for injection into Main Injector (PIP-III)

PIP-II Technology Map



Section	Freq	Energy (MeV)	Cav/mag/CM	Type
RFQ	162.5	0.03-2.1		
HWR ($\beta_{opt}=0.11$)	162.5	2.1-10.3	8/8/1	HWR, solenoid
SSR1 ($\beta_{opt}=0.22$)	325	10.3-35	16/8/ 2	SSR, solenoid
SSR2 ($\beta_{opt}=0.47$)	325	35-185	35/21/7	SSR, solenoid
LB 650 ($\beta_g=0.61$)	650	185-500	33/22/11	5-cell elliptical, doublet*
HB 650 ($\beta_g=0.92$)	650	500-800	24/8/4	5-cell elliptical, doublet*

*Warm doublets external to cryomodules

All components CW-capable

Booster/Recycler/MI Requirements

- Booster
 - New injection region to accept 800 MeV H⁻ and enable transverse beam painting
 - RF sufficient to support acceleration and transition crossing manipulations (22 cavities total)
 - 20 Hz operations
 - Upgrades to damper and collimator systems
- Recycler/Main Injector
 - RF:
 - Cavities for Recycler: slip stacking at 0.7 sec cycles
 - Power for Main Injector: Intensity at 240 GeV/sec acceleration
 - Loss Control
 - Transition crossing in MI -> γ_t jump
 - Electron Cloud and instabilities
 - Collimation: losses in designated areas
 - implementing now with future in mind

The PIP-II R&D Program

- The purpose of the R&D program is to mitigate technical and cost risks, by validating the choices made in the PIP-II facility design and by establishing fabrication methods for major sub-systems and components, including the qualification of suppliers
 - Technical risk: impair the ability to meet fundamental performance goals
 - Cost/Schedule risk: compromise the ability to meet currently understood cost or schedule goals
 - CD-2: Approve performance baseline
 - CD-3: Approve start of construction
 - To be ready for CD-3 in 2019

PIP-II Scope

- An 800 MeV superconducting linac (SCL), constructed of CW-capable accelerating structures and cryomodules, initially operating with a peak current of 2 mA and a beam duty factor of 1%;
- Beam transport from the end of the SCL to the new Booster injection point, and to a new 800 MeV dump;
- Upgrades to the Booster to accommodate 800 MeV injection, and acceleration of 6.4×10^{12} protons per pulse;
- Upgrades to the Recycler to accommodate slip-stacking of 7.7×10^{13} protons delivered over twelve Booster batches;
- Upgrades to the Main Injector to accommodate acceleration of 7.5×10^{13} protons per pulse to 120 GeV with a 1.2 second cycle time, and to 60 GeV with a 0.8 second cycle time.

Primary Risks and Required R&D

- PXIE should mitigate most risks related to the frontend
 - HWR and SSR1 prototype cryomodules are in fabrication
- Design and testing of SC cryomodules is time consuming process
 - 5 new types of SC cavities: vigorous design work for SSR2, LB650 and HB650 has been initiated
 - Microphonics and LFD detuning suppression
- Major challenge for SC linac – reliable operation in pulsed regime
 - Task force was organized and is working on this problem
- Longitudinal emittance growth at transition crossing in Booster can increase beam loss at slip stacking. It can limit the beam intensity and, consequently, the beam power
 - Detailed simulations of transition crossing are carried out
- Suppression of fast beam instabilities at slip stacking can be challenging enterprise
 - Better understanding of present limitations is required


Primary areas to address technical Risk

1. Development and integrated systems testing of PIP-II Front End components (PXIE)
2. Development and demonstration of cost effective superconducting radio frequency acceleration systems at three different frequencies and with rf duty factors ranging from 10% to 100%
3. Development of requisite capabilities at international partner institutions to successfully contribute to PIP-II construction
4. Development of a Booster injection system design capable of accepting extended beam pulses from the PIP-II linac
5. Development of systems designs capable of supporting a 50% increase in the proton beam intensity accelerated and extracted from the Booster/Recycler/Main Injector complex

PXIE


- Scope:

- A CW H- source delivering 5 mA at 30 keV
- A low energy beam transport (LEBT) with beam pre-chopping
- A CW RFQ operating at 162.5 MHz and delivering 5 mA at 2.1 MeV
- A medium energy beam transport (MEBT) with integrated wide band chopper and beam absorbers capable of generating arbitrary bunch patterns at 162.5 MHz, and disposing of up to 5 mA average beam current



- Low β superconducting cryomodules capable of accelerating 2 mA of beam to 25 MeV
- Associated beam diagnostics
- Beam dump capable of accommodating 2 mA at full beam energy for extended periods.
- Associated utilities and shielding

PXIE (PIP-II Injector Experiment): Deliverables



PXIE will address the address/measure the following:

- LEBT pre-chopping : Demonstrated
- Vacuum management in the LEBT/RFQ region : Demonstrated
- Validation of chopper performance
 - Bunch extinction, effective emittance growth
- MEBT beam absorber
 - Reliability and lifetime
- MEBT vacuum management
- CW Operation of HWR
 - Degradation of cavity performance
 - Optimal distance to 10 kW absorber
- Operation of SSR1 with beam
 - CW and pulsed operation
 - resonance control and LFD compensation in pulsed operations
- Emittance preservation and beam halo formation through the front end

Collaborators

ANL: HWR

LBL: LEBT, RFQ

SNS: LEBT

BARC: MEBT, RF

IUAC: SSR1

Status: PXIE elements

- Ion Source & LEBT: **L. Prost**
 - has met beam requirements for injection into RFQ
- RFQ: **J. Steimel**
 - Full field value at 5 msec, 2 Hz operation
- MEBT: **A. Shemyakin**
 - First stage **installed**, design going forward
- HWR: **Z. Conway**
 - delivery in summer 2017
- SSR1: **L. Ristori**
 - delivery in spring 2018
- LLRF: **B. Chase**
 - Working for RFQ, ready for MEBT
- RF Power: **R. Pasquinelli**
 - Working for RFQ (pulsed mode), 162.5 MHz amplifiers for MEBT not settled
- Instrumentation: **V. Scarpine**
 - Installing and commissioning for MEBT

Schedule: PXIE

- FY16:
 - Characterize beam through the RFQ
 - Pulsed operation, measurements through different stages of the MEBT
- FY17:
 - Characterize chopping and beam parameters at entrance of SRF section
- FY18:
 - Installation of Cyro Distribution, HWR, SSR1, ancillary components
- Critical path to HWR & SSR1 operation
 - cryogenic distribution system
 - 162.5 MHz amplifiers for HWR
 - 325 MHz amplifiers for SSR1

Collaborations Role

- Lawrence Berkeley National Lab:
 - Ion Source: Complete
 - design & build RFQ: delivered!
- Argonne National Lab:
 - design & build Half Wave Resonator CryoModule
- IIFC: PXIE
 - MEBT Magnets
 - 325 MHz RF sources
 - LLRF / RFPI
 - 2 SSR1 cavities
- IIFC: SRF
 - SSR2 Cavity Design
 - LB650 Cavity Design
 - HB650 End Group, He Vessel, Tuner
 - 650 CryoModule Design
 - SSR2, LB650 cavities for power test
 - HB650 cavities for CM test
 - 650 MHz Horizontal Test Stand design, fabrication, commissioning



SRF

- PIP-II includes
 - 5 different SRF cavity types and cryomodules
 - Half Wave Resonator
 - 2 Single Spoke Resonators
 - 2 elliptical cavities
 - 3 different frequencies (162.5 MHz, 325 MHz, 650 MHz)
- R&D program:
 - test one complete cryomodule of each frequency to full power
 - HWR & SSR1 @ PXIE with beam
 - HB650 in a test stand
 - test dressed cavities with RF power
 - SSR2 & LB650 in test stands
 - Resonance control of cavities in pulsed mode operation
 - Microphonics
 - Lorentz Force Detuning
 - active frequency control with fast piezo-based tuners

PIP-II R&D: SRF

- R&D deliverables include:
 - Prototype HWR cryomodule (ANL)
 - Prototype SSR1 cryomodule (FNAL, IUAC)
 - Two SSR2 dressed cavities (BARC)
 - Two LB650 dressed cavities (VECC)
 - Prototype HB650 cryomodule (FNAL, RRCAT)
- RF sources, LLRF, and RFPI jointly developed by Fermilab and India in support of testing of the above
 - 325 and 650 MHz

} PXIE



SRF: Resonance Control

- Combination of High Q0, pulsed operation
 - Lorentz Force Detuning large compared to cavity bandwidth
 - Active resonance control system
- Passive means: Mechanical design
 - Reduction of sensitivity to He pressure and LFD
 - Engineering aimed at noise reduction in the tunnel
- Developing a peizo-based feed forward and feedback system
 - Testing on individual cavities now at STC
 - Test on SSR1 cryomodule at PXIE

Section	Frequency (MHz)	Maximal detune (peak, Hz)	LFD at operating gradient, Hz	Minimal Half Bandwidth (Hz)	Max Required Power (kW)
HWR	162.5	20	-122	33	6.5
SSR1	325	20	-440	43	6.1
SSR2	325	20	-	28	17.0
LB650	650	20	-192	29	38.0
HB650	650	20	-136	29	64.0

Rings: 50% more intensity, total power loss budget constant

- Booster: a 33% pulse frequency increase
 - Injection
 - 20 Hz operation
 - RF: beam dynamics studies
 - injection : direct injection into bucket (chopping in MEBT)
 - longitudinal emittance preservation, especially through transition
 - Beam quality: beam dynamics studies
 - Emittance and Loss control
 - Collimation
- Recycler: 20 Hz operation & 60 GeV option for LBNF
 - new 53 MHz RF Cavity
 - Cooling: CW at 60 GeV
 - larger separation for slip stacking -> higher peak voltage
 - Beam dynamics and loss control
- Main Injector: Two areas of R&D:
 - RF Power: for $7.5e13$ ppp
 - Transition crossing: need a γ_t jump for loss control

Lack of funding has restricted progress in these R&D areas

PXIE and SRF Deliverables:

PIP-II R&D Plan thru FY 2019

Responsible Institution	Deliverable	Due Date	Program
3.1 PIP-II Source, LEPT and MEPT			
IIFC Deliverable	MEBT Dipoles and Quadrupoles	Jul-16	PXIE
3.2 Radio Frequency Quadrupole (RFQ)			
Fermilab/LBNL Deliverable	RFQ	Jan-16	PXIE
3.3 Half Wave Resonator (HWR)			
Fermilab/ANL Deliverable	162.5 MHz, HWR Cryomodule with 8 cavities	Sep-17	PXIE
Fermilab Deliverable	Eight 162.5 MHz, RF system and it distribution system	Jan-18	PXIE
Fermilab Deliverable	Integration and Commissioning	Jun-18	PXIE
3.4 Single Spoke Resonator-1 325 MHz Cryomodule			
Fermilab Deliverable	One SSR1 Cryomodule	Feb-18	PXIE
3.9 System Test of SSR1 CM and RF Power with Beam			
Fermilab Deliverable	SSR1 CM to PXIE	Feb-18	PXIE
Fermilab Deliverable	10 MeV Beam from PXIE	Sep-18	PXIE
DAE Deliverable	Eight, 10 kWatt 325 MHz Solid State RF with Circulator	Jan-18	PXIE
Fermilab Deliverable	Integration and Commissioning	Oct-18	PXIE
3.5 High Beta 650 MHz Cryomodule			
IIFC Deliverable	HB650 CM Design	Dec-16	SRF
Fermilab Deliverable	One HB650 Cryomodule	Sep-18	SRF
3.6 Low Beta 650 MHz Cavity			
IIFC Deliverable	Two LB650 High Power Tested Dressed Cavity	Feb-19	SRF
3.7 Single Spoke Resonator 2 Cavity			
IIFC Deliverable	Two SSR2 Low Power Tested Cavity	Dec-18	SRF
3.8 650 MHz Cavity Horizontal Test Stand			
IIFC Deliverable	HTS-2 Cryostat to Fermilab	Jan-17	SRF
DAE Deliverable	Two 30 kWatt Solid State RF Amplifire with Circulator	Jan-17	SRF
Fermilab Deliverable	Integration and Commissioning	May-17	SRF
Fermilab Deliverable	Test of 1st 650 MHZ Dressed HB650 Cavity	Aug-17	SRF
3.10 System Test of HB650 CM and RF Power			
Fermilab Deliverable	HB650 CM to CMTF	Sep-18	SRF
DAE Deliverable	Six, 30 kWatt 650 MHz Solid State RF with Circulator	Apr-18	SRF
Fermilab Deliverable	Integration and Commissioning	Nov-18	SRF

Booster/MI/RR Deliverables:

PIP-II R&D Plan thru FY 2018


Responsible Institution	Deliverable	Due Date	Program
3.11 Booster			
Fermilab Deliverable	20 Hz Girder Test Complete	Sep-18	Booster
Fermilab Deliverable	Qualification of Existing Collimation System Complete	Sep-18	Booster
Fermilab Deliverable	Initial Gradient Magnet / Absorber Design Complete	Sep-18	Booster
3.12 Main Injector			
Fermilab Deliverable	MI RF Station Modified to operate with 2 PAs	Sep-17	MI
Fermilab Deliverable	MI RF Station High Power Tube Delivered	Sep-17	MI
Fermilab Deliverable	Prototype γ t quad tested	Jul-19	MI
3.13 Recycler Ring			
Fermilab Deliverable	Prototype RF Cavity Design Complete	Mar-18	RR
Fermilab Deliverable	Prototype RF Cavity Fabrication Complete	Sep-19	RR

Summary

- Making good progress at PXIE
 - FY16: characterize beam through RFQ
- Have defined R&D deliverables, working towards meeting them
 - Building strong collaborations with Indian Institutions
 - RLS development in FY16 will help us understand schedule and needs to meet the deliverables
- Rings R&D has been delayed because of funding constraints, looking to get going later this year

Backups

PXIE Schedule: to HEBT operation



PXIE Schedule: to HEBT operation

71	Vacuum Connection	2/27/18	2/28/18	2 days	2m
72	Instrumentation Connections	3/27/18	Apr 2, 2018	1 week	2.6 weeks
73	Magnet Connections	Apr 3, 2018	Apr 9, 2018	1 week	2.6 weeks
74	Commissioning	4/24/18	6/11/18	1.8m	2.6 weeks
75	Cryo Cooldown	4/24/18	5/21/18	1 month	2.6 weeks
76	Power Conditioning	5/29/18	6/11/18	2 weeks	2.6 weeks
77	Magnet Conditioning	5/29/18	6/11/18	2 weeks	2.6 weeks
78	Interlock Testing	5/22/18	5/28/18	1 week	2.6 weeks
79	BPMs	5/29/18	Jun 4, 2018	1 week	3.6 weeks
80	Ready For Beam	6/11/18	6/11/18		2.6 weeks
81	SSR1 Requirement	3/1/18	6/28/18	4.3m	0 days
82	CryoModule	3/1/18	Mar 1, 2018	0 days	1.2 weeks
83	Delivery	3/1/18	Mar 1, 2018		1.2 weeks
84	Installation	3/6/18	5/10/18	2.4m	0 days
85	Cryomodule	3/6/18	3/26/18	3 weeks	3 days
86	Cryo Connection	3/27/18	Apr 9, 2018	2 weeks	3 days
87	RF Power Connection	4/13/18	4/26/18	2 weeks	0 days
88	Vacuum Connection	3/27/18	3/28/18	2 days	1.6m
89	Instrumentation Connections	4/27/18	May 3, 2018	1 week	0 days
90	Magnet Connections	5/4/18	5/10/18	1 week	0 days
91	Commissioning	5/25/18	6/28/18	1.2m	0 days
92	Cryo Cooldown	5/25/18	Jun 7, 2018	2 weeks	0 days
93	Power Conditioning	6/15/18	6/28/18	2 weeks	0 days
94	Magnet Conditioning	6/15/18	6/28/18	2 weeks	0 days
95	Interlock Testing	Jun 8, 2018	6/14/18	1 week	0 days
96	BPMs	Jun 8, 2018	6/14/18	1 week	2 weeks
97	Ready For Beam	6/28/18	6/28/18		0 days
98	10 MeV HEBT	2/9/16	6/11/18	2.54 years	2.6 weeks
103	25 MeV HEBT	2/9/16	6/28/18	2.6 years	0 days

