#### Overview and Motivation for the HV Test at PC4

Sarah Lockwitz

July 28, 2016





DUNE ——ProtoDUNE

Sanford Underground Ash River Test


HV Test at PC4

Fermilab

#### DUNE:

- Flagship project (first data in 2024)
- Long baseline 40 kT liquid argon detectors (4x10 kT modules)
- Single phase (SP) detector option

Each module: 12 m tall, 58 m long,
(4) 3.6 m drift regions







DUNE ProtoDUNE Ash River Test
HV Test at PC4

ProtoDUNE-SP

- Two-drift volume single phase TPC
  - 6 m tall, 6.9 m in beam direction
  - (2) 3.6 m drift lengths
    - Typically aim for 500 V/cm → -180 kV on the cathode
- CERN test beam (sub- to several GeV particles) installation summer/fall of 2017
- Develop fabrication & installation methods
- Evaluate the detector performance with full scale DUNE components
- Study particle interactions & reconstruction methods in the DUNE energy range
- Compare single to the dual phase technology









Mechanical prototype in Ash River, MN

- Full scale ProtoDUNE-SP components
- Tests interfaces and handling




- HV Test at PC4
  - Will evaluate the design of ProtoDUNE from a high voltage perspective
    - Design verification
    - Expose any design weaknesses.
      - What voltage can be held?




#### Motivation

- We need ProtoDUNE to succeed
- High voltage issues in liquid argon are not well understood
  - A breakdown will likely set the operating voltage of the experiment
  - Breakdown can damage the detector



#### **Introduction to the Test**

- The test will take place in the 35 T at PC4
- We cannot fit full-sized
   ProtoDUNE TPC components
   in the cryostat
- However, this test will be a full-field test. The device will have the first 10 profiles of a TPC at their planned voltages






#### **Introduction to the Test**


- The test will take place in the 35 T at PC4
- We cannot fit full-sized
   ProtoDUNE TPC components
   in the cryostat
- However, this test will be a full-field test. The device will have the first 10 profiles of a TPC at their planned voltages






#### Will Evaluate

- Individual components:
  - High field areas → corners near cathode
  - New aspects of the design (profiles, resistive plate cathode, ground planes)
- And the integration of the pieces
  - Do the pieces of the design work together?



How to Evaluate: Planned Monitoring

- Current monitoring and logging
  - Monitor the current out of the power supply
- Field cage termination/Pick-off point
  - Monitor the voltage near the end of the resistor network to look for activity in the chain
- Toroid/Corona monitor
  - Sensitive to a change in current flowing through the HV cable just outside of the cryostat
- Cameras
  - William & Mary are working on installing cameras that can help diagnose potential issues.



# Run Plan and Grading the Test

- Keep low voltage (~2 kV) on the feedthrough after the cryostat is closed up
  - Monitor the PS voltage, PS current, FCT, and toroid
  - Provides a baseline and assures of the chain's health before high voltage is applied
- Purge & fill with liquid argon
- Keep HV at 2 kV for starting the pump
- Start to purify! Previously, this has taken ~2 weeks
- Try to raise the voltage to -180 kV (rate: ~60 V/s) over the first week while purifying
- Monitor....


- What if we believe there is a breakdown?
  - Can we tell where it is?
    - → Improve the ProtoDUNE design!
  - What voltage can be held stably (> days)?
  - How long can we hold V (just below troubled voltage)?
  - Try to go as high as we can in the last week again.




### **Schedule**

- By 9/15/2016
  - Design, fabricate, and deliver parts to William & Mary
- 9/16/2016 10/13/2016
  - Clean and Preassemble parts
- 10/14/2016 10/27/2016
  - Parts delivered to Fermilab

- 10/28/2016 11/10/2016
  - Test installed in cryostat
- 11/11/2016 12/6/2016: Purge, cool down, fill the cryostat
- 12/7/2016 1/5/2017: Perform test



## **Organizational Chart**



### **Agenda**

- Plan for ProtoDUNE-SP HV
  - Overview and background of the apparatus and device motivating the planned test
- Technical Review: Mechanical Specifications
  - Details on the time projection chamber (TPC)
- Technical Review: Electrical Specifications
  - Details on the electrical chain of the test
- Cryogenics and Plan for Instrumentation
  - Schedule and outlook of the cryogenics
- Stage II Plans
  - ProtoDUNE has a beam plug that will be tested separately

