



Design of the LBNF Beamline

Vaia Papadimitriou (for LBNF/DUNE)

LBNF Beamline Manager

Fermilab Accelerator Division Headquarters

38th International Conference on High Energy Physics


August 3-10, 2016

Outline


- LBNF/DUNE Science Goals
- The Fermilab Accelerator Complex
- Overview of the reference design of the LBNF Beamline
- Considered design upgrades
- LBNF/DUNE Milestones
- Conclusion

Neutrino Program at Fermilab

Online since 2014
(designed for 700 kW)




Operated
2005 – June 2016
(up to 615 kW)



LBNF/DUNE under development

1300 km

735 km
810 km



Far detector (LAr TPC)
at SURF

New Neutrino Beam
at Fermilab and a
precision Near
Detector

MicroBooNE (LAr TPC)
Online since 2015

SBN Program under
further development


LBNF scope: Near and Far Site Facility Infrastructure
DUNE scope: Near and Far Site Detectors

LBNF/DUNE Science Goals

LBNF/DUNE is a comprehensive program to:

- **Measure neutrino oscillations**

- Direct determination of CP violation in the leptonic sector
- Measurement of the CP phase δ
- Determination of the neutrino mass hierarchy
- Determination of the θ_{23} octant and other precision measurements
- Testing the 3-flavor mixing paradigm
- Precision measurements of neutrino interactions with matter
- Searching for new physics



Start data taking ~ 2026

- **Study other fundamental physics enabled by a massive, underground detector**

- Search for nucleon decays (e.g. targeting SUSY-favored modes)
- Measurement of neutrinos from galactic core collapse supernovae
- Measurements with atmospheric neutrinos

Start data taking ~ 2024


In a single experiment

Fermilab Accelerator Complex

- H^- linac
 - 400 MeV
- Booster
 - $h = 84$
 - 15 Hz
 - 400 MeV \rightarrow 8 GeV
- Recycler
 - $h = 588$
 - Slip-stack 12 batches (double bunch intensity)
- Main Injector
 - 8 GeV \rightarrow 120 GeV





LBNF proton beam extracted from MI-10 straight section




701 kW on the NuMI/NOvA target in one supercycle on June 13, 2016!!
Proton Improvement Plan (PIP)

PIP-II (~2025)


- Key elements:
 - Replace existing 400 MeV linac with an 800 MeV linac capable of CW operation.
 - Higher energy + painting = more beam in Booster
 - Increase Booster rate to 20 Hz
 - “Modest” improvements to Recycler and MI
- Goals:
 - 1.2 MW @ 120 GeV
 - 100+ kW @ 800 MeV
 - Thanks to cryoplant from India



LBNF Beamline




Designed to run at 1.2 MW beam power (PIP-II)
and upgradable to 2.4 MW




Primary Beamline

The **primary beam** designed to transport high intensity **protons in the energy range of 60-120 GeV** to the LBNF target, with **repetition rate of 0.7-1.2 sec**, and **10 μ s pulse duration**



Target Hall Layout

~ 40% of beam power in target pile/chase





Decay Pipe

Target Chase: 2.2 m/2.0 m wide, 34.3 m long air-filled and air & water-cooled (cooling panels). Sufficiently big to fit in alternative target/horns.

Main alternatives for Chase gas atmosphere: N₂ or He

Decay Pipe Layout

- 194 m long, 4 m inside diameter
- Helium filled
- Double-wall, carbon steel decay pipe, with 20 cm annular gap
- 5.6 m thick concrete shielding
- It collects ~30% of the beam power, removed by an air cooling system



Hadron Absorber

Absorber Hall and Service Building



The Absorber is designed for 2.4 MW
~ 30% of beam power in Absorber
515 kW in central core
225 kw in steel shielding

Absorber Cooling

Core: water-cooled

Shielding: forced air-cooled

Flexible, modular design



Overview of Beamline Muon Monitors


1. Array of Ionization Detectors that measure flux of all muons passing through (diamonds, Si)
 - Measure beam center and intensity
 - Spill by spill monitoring of beam

2. Threshold Gas Cherenkov Detector

- Measure signal intensity at different gas pressures and detector orientations
- Extract muon spectrum in alcove with the intention to constrain the neutrino flux

3. Stopped muon counters

- Measure muon flux at several different energies
- Robust measurement of beam flux and composition
- Use to constrain neutrino flux




Testing prototypes at the NuMI beamline

Reference design baffle, target and horns - Viable for 1.2 MW


NuMI-like (low energy), with modest modifications

Baffle




Protects target cooling structure and horns from errant beam pulses

47 graphite target segments, each 2 cm long and spaced 0.2 mm apart, 10 mm in width



Two interaction lengths, 95 cm



1.2 MW Horn # 1

Strong target R&D program in place



Inner Conductor of NuMI Horn



Operated at 230 kA for LBNF



New Horn power supply needed to reduce the pulse width to 0.8 ms.

Mechanical model for optimized horns & target



Horns constructed from 75% 6061-T6 aluminum forgings. Minimum fatigue life requirements of 100 million pulses for each design in the energy range from 60 – 120 GeV.

Preliminary optimization results



LBNF/DUNE Milestones

- Critical Decision-0 (CD-0) approved, January 8, 2010.
- CD-1 Refresh approved, November 5, 2015.
- CD-3a approval expected in December 2016 (far-site pre-excavation and excavation).
- Beamline optimization conceptual design ready for review, September 2017.
- CD-3b approval expected in April 2019 (near-site embankment placement).
- CD-2/CD-3c expected in March 2020 (baselining and start of construction).
- Beamline installation and checkout complete, August 2026.
- LBNF complete, December 2026.

Conclusions

- Significant progress with preliminary design and beam optimization effort in all Beamline systems.
- Need to advance the conceptual design and take decisions on alternative/optimized options very soon since in October 2017 we need to start working on a definite preliminary design.
- Lots of opportunities for collaboration on the design of specific Beamline components as well as on beam simulations and R&D efforts.
- Now is the time to join the Beamline effort and make a substantial difference.
- We are excited and looking forward to design and build this Beamline working together with all our international partners!!




Backup

Fermilab Accelerator Complex

701 kW on the NuMI/NOvA target in one supercycle on June 13, 2016

Proton Improvement Plan (PIP)

618.5 KW
06/13/16




- Protons
- Neutrinos
- Muons
- Targets
- R&D Areas

Main Injector

Facility and Experiment

- **LBNF**: provides facility infrastructure at two locations to support the experiment:
 - **Near site**: Fermilab, Batavia, IL – facilities and infrastructure to create neutrino beam and host the near DUNE detector
 - **Far site**: Sanford Underground Research Facility, Lead, SD – facilities to support the far DUNE detectors
- **DUNE**: Deep Underground Neutrino Experiment
 - **Near and far site detectors**



LBNF Beam Operating Parameters

Summary of key Beamline design parameters for ≤ 1.2 MW and ≤ 2.4 MW operation


Parameter	Protons per cycle	Cycle Time (sec)	Beam Power (MW)
≤ 1.2 MW Operation - Current Maximum Value for LBNF			
Proton Beam Energy (GeV):			
60	7.5E+13	0.7	1.03
80	7.5E+13	0.9	1.07
120	7.5E+13	1.2	1.20
≤ 2.4 MW Operation - Planned Maximum Value for LBNF 2nd Phase			
Proton Beam Energy (GeV):			
60	1.5E+14	0.7	2.06
80	1.5E+14	0.9	2.14
120	1.5E+14	1.2	2.40

$(1.1 - 1.9) \times 10^{21}$ POT/yr

Pulse duration: 10 μ s

Beamline for a new Long-Baseline Neutrino Facility MI-10 Extraction, Shallow Beam

Beamline Facility contained within Fermilab property



Primary beam designed to transport high intensity protons (60-120 GeV) to the LBNF target

Not to Scale

Constructed as
Tunneled excavation


Constructed in Open Cut

All systems designed for **1.2 MW initial proton beam power (PIP-II)**.
Facility is **upgradeable to 2.4 MW** proton beam power.


Pictures of NuMI Horns & Power Supplies




Inner Conductor of NuMI Horn




Operated at 230 kA for LBNF



New Horn power supply needed for LBNF to reduce the pulse width to 0.8 ms.



Current Work on Muon Monitors




Stopped Muon Counter

- Small Cherenkov volume surrounded by scintillating veto
- Measure stopped μ decays downstream of the absorber after beam pulse ends

- Stopping muons have a fixed range: an array of detectors can measure a spectrum instead of just an integral above a threshold
- Muon lifetime fit allows for subtraction of any non-muon background
- Prototype production/testing underway at U. Colorado
- Will use custom PMT bases developed at Drexel to gate off PMTs during high-rate beam pulse, only operate tube after beam later, when muons are decaying



- Testing several possible technologies at the NuMI beamline
 - Diamond detectors, gas Cherenkov detector
- Studying detector operation and long-term stability
- Hope to measure muon flux using scans of Cherenkov detector angle and pressure



Scope of re-optimization

- Horns (long lead items)
- Target
- Integration/mounting of target into horn, baffle mounting, etc.
- Alternative option of gas in target chase
- Absorber
- Associated Modeling
- Associated Radiation Protection
- Horn support modules (three)
- Horn power supply (ies) (0.8 ms)
- Remote handling (casks, morgue capacity analysis, workcell,..)
- Associated Conventional Facilities


Preliminary optimization results




Beryllium R&D

K. Ammigan, C.Densham, P. Hurh et al.

- Be Strength Model Testing and Development at Southwest Research Institute
 - Testing complete
 - Strength model development on track to be complete in June
 - Will be used to benchmark with HiRadMat BeGrid results
- HiRadMat (CERN) BeGrid Experiment PIE
 - Profilometry of all exposed samples completed
 - Preliminary results indicate
 - less deformation than predicted with extrapolated strength model
 - One Be grade (S200FH) shows consistently less deformation than the others
 - Repeated pulses resulted in plastic strain ratcheting



Major axis



Graphite R&D

- NuMI Target (NT-02) graphite PIE at PNNL preliminary results:
 - Evidence of swelling in highly irradiated areas (2 - 5%)
 - Nature of impurities on fracture surface indicates cracking occurred during operation
 - Not much evidence of displacement damage in area away from beam
 - Currently examining area near beam center via TEM
 - Will use these results to bench-mark with other irradiations (lower energy, higher current)

