

Stage II Plans

(a.k.a. Beam Plug Test)


Cheng-Ju Lin

Lawrence Berkeley National Lab

Mini-Review of the HV Test at PC4

28-July 2016

Possible Beam Window Locations for ProtoDUNE-SP



- Beam plug displaces about 50 cm of passive LAr layer
- Without beam plug, electron would shower before reaching TPC
- Plan is to install beam plug for beam position #3

Stage 2 plans:



- After completion of stage 1 test, replace one field cage end-wall with one that has beam plug attached
- Verify beam plug does not interfere with the operations of the TPC (i.e. same HV performance w/ and w/o the beam plug)

Beam plug team:

- C-J Lin - coordination
- Tim Loew - overall design
- Will Waldron - HV engineer
- Joe Wallig - Beam test and Ash River trial-assembly
- + students/postdoc from UCB/LBNL and inputs from campus faculty (H. Steiner, K-B Luk)



Stage 1 groups will also be involved in stage 2 tests

Stage 2 Configuration




Note: mounting scheme with the FC is not finalized

Beam plug



Beam Plug




Sections are bonded using cryogenically-rated adhesive to ensure leak-free joint

Beam Plug Design Requirements

Parameter	Value	Notes
Dimensions		See CAD model
Internal Diameter	20 cm	
Length	480 mm 537 mm 659 mm	Ground Cap to Flange Overall (Flat to Flat) Overall (Maximum)
End Cap Angle	16.2°	
Flange Angle	16.2°	
Tolerances	ASME Y14.5 2009	Where Useful to Convey Design Intent & Function
Material	180 kV end to end	Electrically Insulating Selected from or tested per FNAL LAr purity list.
Operating Temperature	25° C -185 °C	Room Temperature LAr Temperature
Interface	Cryostat Wall; HV Field Cage	Minimize Distance; Rigid Structural; Electrode at HV Potential
Electrode Rings	304/316 Stainless Steel	
Operating Pressure (Internal)	78.6 psi 22.9 psi	Ambient Temperature LAr Temperature
Pressure Environment (External)	14.7 psi 19.9 psi	Ambient Temperature LAr Temperature
Pressure Ratios (Internal/External)	5.3 1.15	Ambient Temperature LAr Temperature
Internal Volume	15.5 liter (est.) 22 liter (est.)	Internal External displacement
Minimum Safety Factor	3	
Pressure Test Factor	2	
High Voltage Test	180 kV equivalent	HV tests conducted by LBL
Flange Interface		Geometry per LBL ICD
Weight Load	75 lb [34 kg]	Estimated
Buoyancy Load	67.5 lb [31 kg]	Estimated
Pressure Port		
Permeability	6.6 x 10 ⁻⁵ torr-l/s 5.9 x 10 ⁻⁵ torr-l/s	Total Volumetric, N ₂ gas He gas Equivalent
Operating Lifetime	1 yr	
Thermal Cycles	3	Per Lifetime
Shock Loading		No shock loading



Electrostatic Calculation for Electrodes



Electric Fields for 180kV:


E_{\max} in LAr = 15.7kV/cm on grading ring at HV end

E_{\max} in N₂ = 14.4kV/cm on grading ring at HV end



Peak field is acceptably low

RESISTOR DIVIDER CHAIN



Tapping off voltage at field-cage profile #5 (165kV)



Working with FC, APA, and CPA groups to finalize the resistor values

Beam Plug Testing Program

A suite of tests are planned leading up to the HV test @ PC4

Mechanical bonding test (completed):

- Validate electrode ring/composite material joint for adhesive shear strength
- Performed at cryogenic temperature (LN) by the vendor
- Excellent result -> nominal safety factor of 6 for shear failure



Beam Plug Testing Program

Measure dielectric strength of composite (ongoing):



- Samples received from vendor
- We are setting up the test apparatus at LBNL
- Study electric breakdown along the surface and through the bulk of the composite material
- Results available within a week



Beam Plug Testing Program

Beam test (planned):

- Electron beam through the beam plug with the grading rings at nominal HV (~ 160 kV across the beam plug)
- Verify the design does not cause HV breakdown inside the plug when running with charged particle beam
- Test as a function of N_2 gas pressure and beam rate
- Test at room temperature; will adjust the internal pressure to cover all range relevant to cryogenic operations
- Test beam at either SLAC ESA or Fermilab M-Center this Fall



(J. Wallig)

Beam Plug Testing Program

Material compatibility (starting soon):

- Testing all components (grading ring, fiber composite, resistors) for compatibility with LAr
- Using the Material Test-stand (LUKE) in PAB @ Fermilab

Radioactivity (as components become available):

- Measure radioactivity of fiber composite materials and grading ring electrodes
- Using the Low-Background Counting Facility at LBNL

Full-scale cryogenic test(planned):

- Testing the production unit in LAr using the BLANCHE test-stand at PAB
- Stand-alone testing up to the maximum voltage allowed by BLANCHE (~150 kV)
- Time frame: late November to December

Summary

- Beam plug is critical to the physics program of ProtoDUNE-SP
- A suite of tests are planned leading up to the Stage II PC4 test
- Stage II is the “grand finale” of the beam plug test program:
 - Full integration with the FC and other TPC HV systems
 - Identical mechanical mount to the field cage as ProtoDUNE-SP
 - In LAr with nominal HV
- Will have a review for Stage II later in the year