### **Asia ILC Activity Report**

J. Gao

IHEP

LCB Meeting, August 7, 2016 Chicago, USA

# Contents

- Japan
- China
- Korea
- India

#### ILC Progress at KEK/Japan during a period of Feb. ~ Aug. 2016

#### ILC R&D Progress, in Japan/KEK January ~ July, 2016

#### SRF Technology:

#### • STF2 SRF Accelerator Construction at KEK

- Completion of RF distribution system installation for STF2 Cryomodules (CMs)
  - Cavity gradient: 34.9 MV/m with best 8 cavities (of 12 cavities, CM1 + CM2a)
- Cool-down and RF power test to be realized in October, 2016.

#### • SRF Cavity R&D cooperation in Asia

- A 9-cell cavity developed by IHEP processed and vertically tested at KEK, in 2016.
- "Marx" Modulator (Solid State, RF Power Supply) R&D at KEK
  - A prototype development in progress in cooperation with Japanese industry

#### Nano-beam Technology:


- ATF2, FF beam-size and the stability
  - A beam size of 41 nm (preliminary) achieved with FONT feed-back ON.
  - Non-linear magnetic field effect being studied.

#### **KEK-ILC Action Plan:**

#### SRF Cost Reduction R&D plan proposed

- SRF cost reduction R&D proposed in close communication b/w Fermilab and KEK

# **KEK-STF SRF Accelerator Plan**



- Charge: 2nC/bunch, 2437bunch, 0.9ms, 5Hz
- Pulse Current: 5.7mA in train
- Pulse Train: 369ns spacing



Capture CM (2 cavities)



ILC R&D Progress in Japan

Chicane 2


Beam

CM-2a (4 cavities) CM-1 (8 cavities)



2016/07/25

#### KEK-STF: Cavity/CM Performance, and RF-Power/Control and Beam Test Preparation



FY14: CM1+CM2a (8+4) assembly
FY15: Cavity individually tested in CM
RF power system in preparation
FY16: 8-cavity string to be RF tested
FY17: Beam Acceleration anticipated
(to reach > 250 MeV)




#### Marx Modulator Development at KEK


- A prototype "Marx" modulator being developed at KEK in cooperation with a company in Japan, base on preliminary effort between SLAC and KEK.
  - It features "parallel charging and series discharging" by using SiC devices (instead of Si) to cost-effectively generate RF high-voltage,




# Progress in KEK-ATF2, 2016

- Int'l Collaboration for "Nano-beam" Research
  - ~25 Lab. , and > 100 Collaborators
- Modeling of ILC BDS
  - Same Optics: as ILC-BDS
- Goal
  - FF Beam Size: 37 nm (→ 5.9 nm at ILC)
- Progress
  - 41 nm (preliminary) reached with FONT FB ON
  - Non-linear magnetic field effect being studied.







https://agenda.linearcollider.org/event/7014/contributions/36882/attachme 500 nts/30069/44951/ATF2\_okugi\_20160601.pdf 450 Size [nm] 400 Preliminary 350 300 Vertical Beam **1 Skew Sextupole Installed** 250 **Orbit Stabilization** 5 FF sextupole 200 4 Skew Sextupole Installed Skew Sextupole Modification 150 **4 FF Sextupoles** 100 43nm 50 41nm 44nm 0 2010 2011 2012 2013 2014 2015 2016 Sextupole Swapped **EONT FB ON** 

T. Okugi, ECFA-LCW, Santander June, 2016

#### **KEK-ILC Action Plan Issued**, 2016

#### https://www.kek.jp/en/NewsRoom/Release/20160106140000/





#### KEK issues action plan for the International Linear Collider

January 6, 2016

Japan's High Energy Accelerator Research Organization (KEK) issued an KEK-ILC action plan 2<sup>th</sup> for how KEK should start its preparation toward the International Linear Collider when the Ministry of Education, Culture, Sports, Science and Technology (MEXT), decides to initiate negotiations with foreign countries.

KEK has been promoting the development of linear collider accelerator technology for a long time and has greatly contributed to the publication of the ILC Technical Design Report (TDR). KEK considers the promotion of the ILC project to be a strategic part of organization's future, described in the KEK Roadmap published in May 2013. Its activities are currently centered around three facilities: the Superconducting RF Test Facility (STF), the Accelerator Test Facility (ATF), and the Cavity Fabrication Facility (CFF). In addition to the efforts in the technical development, KEK established the Planning Office for the ILC in February 2014, to promote the ILC project and the technical development activities at KEK.

# **KEK ILC Action Plan**

- plan the technical actions, organization, human resources and training to realize formal approval of the ILC project
- ensure a smooth start of the construction phase through the preparation phase from the current status

	Pre-preparation Phase	Main Preparation Phase								
	Present	P1	P2	Р3	P4					
ADI	Establish main parameters	Verify parameters w/ simulations								
SRF	Accelerate beam with SRF cavity string and cryomodule	Demonstrate mass-production technology and stability Demonstrate Hub-lab functioning and global sharing								
Nanobeam	Achieve the ILC beam-size goal	Demonstrate the nanobeam size and stabilize the beam position								
Positron source	Demonstrate technological feasibility	oth the undulator and e-driven e+ sources								
CFS	Pre-survey and basic design Geology survey, engineering design, specification, and draw									
Common technical support	Support engineering and safety Common engineering supports (network, radiation safety, etc									
Administration	AdministrationProject planning and promotion Preparation for the ILC pre-labGeneral affairs, finance, international relations, public relat Establishing the ILC pre-lab and managing the ILC prepara									

#### **ILC Cost-Reduction R&D Proposal**

#### focusing on SRF in 2~3 years

The R&D proposal addresses the International Linear Collider (ILC) cost reduction feasibility, followed by industrialization R&D during the "main preparation" phase.

A-1. Nb material preparation


- with optimum RRR and clean processing for sheeting/piping
- A-2. SRF cavity fabrication for high-G and high-Q
  - with a new surface process provided by Fermilab
- A-3. Power input coupler fabrication
  - using new ceramic requiring no coating
- A-4. Cavity chemical treatment

- vertical EP and easier handling w/ safer solution

## Contents

- Japan
- China
- Korea
- India

# IHEP TESLA Cavity Industrialization (July 28, 2016)



- Joint effort of IHEP ILC Group and HE-Racing Technology Corporation (IHEP workshop) for ILC cavity technology transfer and industrialization study.
- First 1.3 GHz TESLA 9-cell cavity (HERT001) has been completed on July 28<sup>th</sup>, 2016 and passed vacuum test.
- Expect to surface-process by EP and test at KEK in Autumn.

# HE-Racing Technology (HERT)

- Rich experience in accelerator components manufacture:
  - S-band and C-band accelerator tubes, SLED, RFQ, magnets ...
  - SRF cavities (spoke and elliptical) and high power input couplers
- Cavity fabrication facilities:




**Press Machine** 



CNC Turning Center



Vertical Machining Center





**CMM Machine** 



Vacuum Furnace

**EBW Machine** 

### **Cavity Fabrication**


- Optimized manufacturing process, welding parameters and structures
- Accurate frequency, shape and length control; careful surface cleaning
- More cavities to further improve the welding quality, simplify the manufacturing process, and reduce cost for mass-production

100000001

NOX.

+00000000+

10000000 +



#### IHEP 1.3 GHz Cavity R&D

9-cell TESLA, fine2016 grain cavity with HOM, by High-Energy Racing



9-cell TESLA-like, fine2014 grain cavity with HOM, 16.8 MV/m by EP





9-cell Low Loss, large2012 grain cavity with HOM, 20 MV/m by EP




9-cell low-loss, large2010 grain cavity without HOM, 20 MV/m by CP





2008 single cell low-loss and fine cavity, max. 40 MV/m by CP












#### IHEP03@KEK (2016.02.22~2016.04.30)

(IHEP-KEK ILC 1.3GHz TESLA-like 9cell Cavity Collaboration)

- 1. Frequency and field flatness measurement
- 2. Inspection of inner surface by Kyoto-camera
- 3. Local grinding around defect area
- 4. Pre-EP (5 um) & EP-I (100 um)
- 5. Annealing
- 6. Inspection of inner surface by Kyoto-camera
- 7. Pretuning
- 8. EP-II (10 um), HPR
- 9. Clean room assembly, baking
- 10. Set-up of VT system with T-map
- 11. Vertical Test
- 12. Frequency and Field flatness measurement
- 13. Inspection of inner surface by Kyoto-camera after VT






### **EP** Preparations



Ultrasonic cleaning

#### **π**-mode Field Flatness after pre-tuning



 $\pi$ -mode (1303.167MHz) Field Flatness = 92.95%

## Cavity assembly, Baking




leak test

Baking(48h)

# IHEP-03 Vertical Test Result


CBP(80 μm@IHEP), Pre-EP(5 μm),EP-I(100 μm), Annealing(750 °C,3h) EP-II(20 μm), HPR(1.5h+3.5h),baking(140 °C,48h)



# Cell Gradient by Passband Modes Test

MV / m	Cell 1& 9	Cell 2 & 8	Cell 3 & 7	Cell 4 & 6	Cell 5	<b>Quench Location/Comments</b>
π(initial)	16.85	16.85	16.85	16.85	16.85	Heat @ 1-cell equator 120º X-Ray
π(final)	16.64	16.64	16.64	16.64	16.64	Heat @ 1-cell equator 120º X-Ray
2π/9	8.10	19.44	22.28	14.90		Heat @ 3&7-cell equator X-Ray
5π/9	18.85	12.82	22.24	3.77	23.94	Heat @ 1-cell equator 120º X-Ray
4π/9	13.00	17.03	7.41	18.85		Heat @ 6-cell equator 240°~270° X-Ray
3π/9	12.32	24.64	12.32	12.32	>24.64	Heat @ 2-cell equator 300° X-Ray
Eacc, max	18.85	24.64	22.28	18.95	24.64	Ave. Eacc,max=21.54

Cell3 >22MV/m, Cell4 >19MV/m, Cell8>24.6MV/m,Cell9 >16.85MV/m



# Acknowledgement

*Eiji Kako,* Kensei Umemori, Mineyuki Asano, Motoaki Sawabe, Kouichi Nakamura, Fumihiko Tukada, Jun Sakai, Taisuke Yanagimachi, Shinichi Imada, Hiroki Yamada.....

# **IHEP T-mapping System**

- T-mapping is the most common diagnostic tool for SRF cavities
- We will develop a fixed T-mapping systems
- With Carbon Resistor (200 AB sensor at first step)
- Sampling time: < 100ms
- Data logger: Not determined
- Labview

### **T-mapping : Resistors**






Temperature sensor

#### Vertical test of 1.3GHz cavity N-doped

- 1.3 GHz single-cell cavities were N-doped after Nb sample experiments.
- Several vertical tests were finished, but Q Value didn't increase. Key reason: **NO EP**, just received BCP. Other reasons are also under research.






Magnetic shielding around cavity

#### **IHEP EP Schedule**

2016					2017											2018							
Jun.	Jul.	Aug.	Sept. Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	Apr.	May	Jun.	Jul.	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	Apr.	May	Jun.
		Desig																					
				Revie	ew and	Admini	stritiv	ze pro	cess f	or choc	sing c	ompany	-										
						Engin	eering	Desig	n and	Review													
								Fabri	cation	n and P	urchas	e of c	ritica	l unit	Ċ.								
																Assem	bly						
																		Commi	ssioni	ng and	Acce	ptanc	в


Key Time Points:

- Oct. 2016: Finish the Conceptual Design
- Dec. 2016: Finish Review and Administrative process for choosing company
- Feb. 2017: Finish Engineering Design and Review
- Oct. 2017: Finish Critical Units fabrication or Purchase
- Dec. 2017: Finish Assembly
- Apr. 2018: Finish Commissioning and Acceptance




Layout of Critical Units for Electropolishing facility

### Slotted cavity development time line



# Slotted Cavity HOMs' Damping Comparison

	Mea	Calculated Value					
F (GHz, with covers)	$Q_L$ (with covers)	Q <sub>L</sub> (≈Q <sub>e</sub> , without covers)	F (GHz, without covers)	Q <sub>e</sub> (without covers)	F (GHz)		
1.524	560	Х	Х	5.2	1.525		
1.5312	714	х	Х	-	-		
1.5926	624	х	Х	-	-		
1.5979	606	100	1.599	2.17	1.599(TE <sub>111</sub> )		
1.677	1037	Х	Х	5.74	1.676		
1.68	995	Х	Х	-	-		
1.713	94	Х	Х	-	-		
1.7526	1192	Х	Х	-	-		
1.7492	1280	Х	Х	20.4/8.8	1.754/1.747		
1.794	1312	Х	Х	-	-		
1.8405	2047	344	1.842	446	1.855(TM <sub>110</sub> )		
1.9	445	Х	Х	-	-		
1.973	714	Х	Х	15.9	1.973		
2.052	470	Х	Х	5.43	2.043		
2.086	615	Х	Х	15.2	2.093		
2.184	531	172	2.173	14.2	2.175		
2.1985	321	Х	Х	-	-		
2.254	1450	Х	Х	20.7	2.252		
2.324	1990	2136	2.324	185961	2.326 *		
2.365	1224	Х	х	-	-		
2.4	1071	630	2.4	-	-		
2.437	800	667	2.437	105.1	2.439 *		




\*Notes on TABLE III: Many HOMs disappeared in the network analyzer when opening the waveguide port as the Q<sub>L</sub> of these mode decreased below 10 or so. These modes are depicted by "x". Since there are several calculated modes around the measured frequency or the frequency shift between measured frequency and calculated frequency is large, we use "-" to depict. \* depicts quadruple mode.





# Vertical test

- First test: 4.2K vertical test, limited by power, the accelerating gradient of the cavity reached 2.4MV/m  $(Q_0=1.4x10^8)$ .
- Second & third test: 2K vertical test, the  $Q_0$  of slotted cavity were limited by the coupler flange (stainless steel). Maximum  $Q_0$  is  $1 \times 10^8$ .  $\pi$  mode gradient is 1.4MV/m. Maximum  $B_{pk}$  of  $2/3\pi$ mode(with a lower field in beam pipe) is 24.5mT. It is equal to the  $B_{pk}$  of  $\pi$  mode with a gradient of 4.3MV/m.
- A longer Nb beam pipe is needed to increase Q<sub>0</sub>. Next step, we will add the beam pipe length.




# Contents

- Japan
- China
- Korea
- India




#### **Fabrication of Low-Q IP-BPM**

- Made by Aluminum (2kg for double block)
- Precise surface machining within 4um.
- IPBPM A & B are fabricated together in same block.
- IPBPM C was fabricated to single block.






#### **Installation of IP-BPM system**






#### IP-BPM resolution test in KEK-ATF2 (Mar. 2016): position resolution of 8nm



### **Current Accelerator Activities in Korea (2016)**





Rare Isotope Science Project



Synchrotron for Carbon Therapy

KOMAC,100-MeV Proton Linac


### **Status of Accelerator R&D in Korea**


- PAL-XFEL (10 GeV): Commissioning is under progress smoothly. SASE Lasing was achieved officially on June 27. 2016
- Construction of RISP (Rare Isotope Science Project) & KHIMA (Carbon Therapy) Project are on-going as planned.
- PLS-II (3.0 GeV light source) and KOMAC (100 MeV proton linac) are in users' service.

### PAL-XFEL Tunnel




### First Lasing at 0.5 nm on 14 June, 2016






### DCM Energy Scan



shots/point

# The brightest 0.5-nm FEL (Achieved on June 27. 2016)



# Contents

- Japan
- China
- Korea
- India



#### **Development for SCRF Cavity at RRCAT**

### Raja Ramanna Centre for Advanced Technology

### **Machining facility**



Machined half cells of five- cell SCRF cavity



Dumbell Machining fixture development



Machining of dumbells on precision lathe




Inspection of machined components


### **SCRF Cavity Inspection Facility**


#### Laser Scanning Confocal Microscope

Imaging Method	3-D Laser Scanning	
	Confocal system	
Z - Resolution	1 nm	
(Depth)		
Z - Measurement	12 nm	
repeatability		
X-Y Resolution	0.12 μm	









	No.	Result	Width[µm]	Height[µm]	Length[µm]
1	1		1806.831	252.657	1824.410
1	2		1689.145	212.954	1702.516

#### Confocal image of replica

#### Measurement of bead profile

### **Cavity Processing Facility**

#### Centrifugal Barrel Polishing (single Cell)

#### **Main features of CBP machine**

- Turret and Barrel rotate in opposite direction
- Turret speed 0 200 rpm (variable)
- Barrel speed 0 200 rpm (variable)
- Barrel size 320 X 320 X 500 mm





**Barrel Polishing Machine** 

### **Cavity Processing Facility**

#### Electro-polishing setup for 1.3 GHz & 650 MHz Cavities



EP bench for 1.3 GHz Cavities



EP bench for 650 MHz Cavities

### **Cavity Processing Facility**

#### **High Pressure Rinsing Setup**



#### **Ultra Pure Water Plant**



### Low Temperature Baking & Pilot Cleanroom Facilities



Low temperature baking facility for 650 MHz




**Pilot clean room facility** 

#### EBW Machine Installed at RRCAT, INDORE



### **Development of 1.3 GHz Five-cell cavity**


A five-cell 1.3 GHz SCRF cavity was Fabricated with IUAC. The cavity was sent to Fermilab for processing under IIFC. The cavity was tested in October 2014.




The cavity achieved the accelerating gradient (Eacc) of 20.3 MV/m at 2 K and 42 MV/m at 1.5-1.7 K with  $Q_0$  of 2 x  $10^{10}$ 

## 1.3 GHz 5-Cell Cavity










First multi-cell niobium cavity built in India



Result of the cold test performed at Fermilab. The cavity reached 20.3 MV/m @ 2 K, and 42 MV/m @ 1.5-1.7 K.

### 2K Vertical Test Stand Facility




Cryostat & Cavity Insert Assembly




**Transfer of liquid helium** 


**RF testing in progress** 



The 2K cryostat & electronics was developed in collaboration with Fermilab under IIFC

#### **Niobium Cavity development at TRIUMF**





Cavities for VECC will come from TRIUMF



#### 1-cell cavity cold tests



9-cell cavity inspection

# Conclusions

Asian countries continue to work and collaborate on ILC related tecnologies in 2016

- Japan: KEK continue to work on SCRF and Nanobeam technology for ILC with 41nm achieved at ATF2
- China: IHEP continue its effort on 1.3GHz SCRF technologies with great progress with the first IHEP Factory made 1.3GHz 9cell TESLA cavity completed and collaborate actively with KEK on ILC SCRF and positron source. Financial support for ILC ATF2 and positron source collaboration with ILC has been quaranteed in the nex five years.
- Korea: Korea University collaborate actively on ATF2 BPM and home accelerator projects goes well with PAL-XFEL SASE laseing on June 27, 2016.
- India: BARC progresses well on 1.3GHz SC technology and laboratory deveoplments.

Thanks go to Profs. S. Michizono, A. Yamamoto, W. Namkung, E.S. Kim and D. Datta for their providing progress information fron their countries.