


# FNAL Cavities: QA/QC, qualification, work flow

Alex Melnychuk, Anna Grassellino, Chuck Grimm, Sebastian Aderhold, Damon Bice

September 13, 2016




# Outline

---


- Cavity “Prep and Test” scope of work
- Organization, manpower, workflow
- Subareas work examples, procedures, schedule, infrastructure:
  - QA/QC
  - Vertical Test
  - Re-processing
  - Horizontal Test
- Safety
- Travelers, DRs

# Scope of work, organization

- Cavity prep and test covers all cavity qualification/performance assessment activities from the moment cavities arrive to “ready for string assembly”
- Main goal is qualification of **8 cavities a month** (from cavity arrival moment to delivery for string assembly) to keep CM assembly needed pace/supply
- All cavities undergo QA/QC and VTS qualification
- Assumption for reprocessing (HPR) is ~ 30%, small % can be lightly EP'd if needed
- Only 1 cavity in 16 (every two cryomodules) goes to HTS for couplers, tuners etc verification purposes



# Work Flow, timeline of activities



- With work proceeding in parallel, can assess 12 cavities a month, and qualify 8 cavities a month with ~ 30% reprocessing rate



---

**QA/QC**

# Steps of Incoming Inspection for LCLS-II cavities

---

- **Visual incoming inspection**
  - Check for visible damage
  - Check presence of all components (screws, washers, feedthroughs,...)
  - Recording serial numbers of all parts in circulation
- **Leak check of Helium space**
  - Only Helium space of the Helium vessel is checked, no connection made to (clean) cavity vacuum
- **RF incoming inspection**
  - Measurement of cavity fundamental and HOM frequency spectrum
  - Measurement of external Q of all antennas
- **CMM measurement**
  - Check certain critical dimensions
  - Only performed on each cavity during early production
  - Might be fully waived or only extended to subset of cavities if no deviations from measurements at vendors are found

# Cavity in IB4, incoming inspection



# Incoming inspection documentation and results

---

- **All inspection steps guided by traveler**
- **Results of inspections documented in traveler**
- **No show-stoppers for qualifying cavities / no severe deviations from specifications found in any of the inspections so far**

# Incoming Inspections of the First Eight RI Cavities

---

- **Delivered RI Cavities**


- CAV0003
- CAV0006
- CAV0007
- CAV0008
- CAV0011
- CAV0013
- CAV0015
- CAV0016

- **Shock Log Data**

- All cavity data analyzed and at acceptable levels
- CAV0003 example – Data captured in Incoming Inspection Traveler 464305

# CMM Measurements




- CMM Measurement Map





# CMM Measurements

- CMM Measurement CAV0008
  - All dimensions good, #4 is 60 microns (.002") out-of-tolerance but still acceptable
  - FNAL data reveals the same slight deviation

test number	test object	serial number	test instruct	test location	company na	inspector na	inspection d	remarks	result summary		
Y		100		Bergisch GlöRI		M. Friedrichs	#####	See NCR:			
  											
Dimension record											
Dimensions [mm]											
	1	2	3	4	5	6	7	8	9	10	11
Max value	650.80	650.80	342.00	342.00	272.00	300.5	0.5	24.0	24	24.0	24
Min value	649.20	649.20	341.70	341.70	271.70	299.5	0	23.7	23.7	23.7	23.7
Measured value	650.31	650.15	341.80	341.64	271.70	299.84	0.49	23.87	23.88	23.88	23.86
Result	good	good	good	-0.06	good	good	good	good	good	good	good
Dimensions [mm]											
	12	13	14	15	16	17	18				
Max value	0.25	0.25	24	24.0	0.25	0.1	40				
Min value	0.00	0.0	23.7	23.7	0	0.0	38				
Measured value	0.06	0.07	23.84	23.84	0.33	0.03	36.99				
Result	good	good	good	good	good	good	good				
Remarks											
See NCR 3456-NCR-19-Q10502-0											
Dimension numbers see attachment to Y_M02											
Inspection 7/1/2016 M. Friedrichs											
Description / Notes Date Name											
Cavity in Helium Tank CAV_HT0008											
Serial-No.											

RI CMM Data


MM	FRONT_DATUM_RING_OFFSET_FROM_END_FLANGE_AXIS - DATUM_RING
AX	NOMINAL MEAS
X	0.000 0.087
Z	0.000 -0.285
MM	DIM_1 - PNT1 TO PNT3 (YAXIS)
AX	NOMINAL +TOL -TOL MEAS DEV OUTTOL
M	650.000 1.000 1.000 650.050 0.050 0.000
MM	DIM_2 - PNT5 TO PNT7 (YAXIS)
AX	NOMINAL +TOL -TOL MEAS DEV OUTTOL
M	650.000 1.000 1.000 650.307 0.307 0.000
MM	DIM_3 - PNT5 TO PNT4 (ZAXIS)
AX	NOMINAL +TOL -TOL MEAS DEV OUTTOL
M	342.000 0.000 0.300 341.628 -0.372 0.072
MM	DIM_4 - PNT5 TO PNT2 (ZAXIS)
AX	NOMINAL +TOL -TOL MEAS DEV OUTTOL
M	342.000 0.000 0.300 341.818 -0.182 0.000
MM	DIM_6_RIGHT - Circle0 TO DATUM_A_B
AX	NOMINAL +TOL -TOL MEAS DEV OUTTOL
M	300.000 1.000 1.000 299.245 -0.755 0.000
MM	DIH_6_LEFT - Circle1 TO DATUM_A_B
AX	NOMINAL +TOL -TOL MEAS DEV OUTTOL
M	300.000 1.000 1.000 299.368 -0.632 0.000

FNAL CMM Data

MM	FRONT_DATUM_RING_OFFSET_FROM_END_FLANGE_AXIS - DATUM_RING
AX	NOMINAL +TOL -TOL MEAS DEV OUTTOL MAX MIN
M	24.000 0.000 0.300 23.856 -0.144 0.000 23.860 23.853
AX	NOMINAL +TOL -TOL MEAS DEV OUTTOL MAX MIN
M	24.000 0.000 0.300 23.863 -0.137 0.000 23.893 23.850
AX	NOMINAL +TOL -TOL MEAS DEV OUTTOL MAX MIN
M	24.000 0.000 0.300 23.850 -0.150 0.000 23.864 23.845
AX	NOMINAL +TOL -TOL MEAS DEV OUTTOL MAX MIN
M	24.000 0.000 0.300 23.859 -0.141 0.000 23.866 23.853
MM <td>PLN_A_BOTTOM</td>	PLN_A_BOTTOM
Feature	MEAS OUTTOL
PLN_A_BOTTOM	0.031 0.000
MM <td>PLN_B_BOTTOM</td>	PLN_B_BOTTOM
Feature	MEAS OUTTOL
PLN_B_BOTTOM	0.030 0.000
MM <td>PLN_C_BOTTOM</td>	PLN_C_BOTTOM
Feature	MEAS OUTTOL
PLN_C_BOTTOM	0.085 0.000
MM <td>DATUM_D</td>	DATUM_D
Feature	MEAS OUTTOL
DATUM_D	0.103 0.000
DEG <td>18_REAR - LIN1 TO DATUM_D</td>	18_REAR - LIN1 TO DATUM_D
AX	NOMINAL +TOL -TOL MEAS DEV OUTTOL
A	39.000 1.000 1.000 39.246 0.246 0.000
DEG <td>18_FRONT - LIN2 TO DATUM_D</td>	18_FRONT - LIN2 TO DATUM_D
AX	NOMINAL +TOL -TOL MEAS DEV OUTTOL
A	39.000 1.000 1.000 39.125 0.125 0.000

# Shock Log Data


- CAV0003






# Shock Log Data

- CAV0003 Shock Data




# Shock Log Data

- CAV0003 Shock Data



# Shock Log Data

- **CAV0003 Shock Data**
  - Z axis is the up/down loads, the GP1 Accelerometer understands gravity, which is why the vertical axis starts at 1g




# Minor Issues

---

- **Minor deviations found**
  - absence of plastic caps on RF connectors
  - absence of drilled holes on RF connectors in some of the cavities
  - QA mark placed on the support lug in an undesirable place/surface
  - Input coupler antenna too long (RF inspection indicated that  $Q1*Q2$  was lower than expected, confirmed at VTS)
  - absence of VCR connector on RAV
  - All these were addressed, future cavities are not expected to have them
- **All these were addressed, future cavities are not expected to have these issues**

# Minor Issue Example

---



---

## **Vertical Test**




# IB1 Vertical Test Facility

- Three vertical test dewars for SRF cavities measurements
- Using two dewars VTS-2 and VTS-3 for LCLS-II Production (cavities do not fit in VT1), each dewar can safely host 2 LCLS-2 cavities simultaneously
- Cryogenics shared among several different programs – magnets and SRF testing
- Capability of adjusting cool-down rates, test T from 4.2K down to 1.4K
- Remnant magnetic fields < 5 mGauss (passive shielding), and < 2 mGauss (active compensation via coils)
- No active pumping – cavities will either be tested as received in static vacuum or after re-evacuation in clean room (half of cavities have been tested as received 1e-4Torr and half after re-evacuation 1e-6 Torr, no noticeable performance difference)



# Standard LCLSII VTS Production Testing Schedule (VTS test 12 cavities per month)

- **Need to qualify 8 cavities per month**
- **Assume 30% re-HPR rate (based on XFEL experience)**
  - four more cavities to VTS-test per month
- **Test two cavities in one cryocycle**



<b>Week 1:</b>	<b>2 cryocycles × 2 cavities</b>	<b>= 4</b>
<b>Week 2:</b>	<b>2 cryocycles × 2 cavities</b>	<b>= 4</b>
<b>Week 3:</b>	<b>1 cryocycle × 2 cavities</b>	<b>= 2</b>
<b>Week 4:</b>	<b>1 cryocycle × 2 cavities</b>	<b>= 2</b>
		<b>12</b>

- **This scheme utilizes highest priority that LCLSII receives at lab level and still allows to run other programs (but at lower rate)**
- **Weekly prioritization of VTS test schedule done via SRF program/cavity coordinator (A. Grassellino) in accordance to lab and scientific priorities**
- **In case of schedule conflicts SRF/magnets TD Division Head (S.Belomestnykh) resolves conflicts determining priorities**



# LCLSII VTS Schedule Risk Mitigation (VTS test 16 cavities/month)

- **Need to qualify 8 cavities per month**
- **Assume 30% re-HPR rate (based on XFEL experience)**
  - four more cavities to VTS-test per month
- **Test two cavities in one cryocycle**







Figure 1. Projection for total number of test days (at cryogenic temperature ~2K), versus fiscal year. Dashed line indicates maximum number of days available at cryogenic temperature.



Week 1:	2 cryocycles × 2 cavities	= 4
Week 2:	2 cryocycles × 2 cavities	= 4
Week 3:	<del>2</del> cryocycles × 2 cavities	= <del>2</del>
Week 4:	<del>2</del> cryocycles × 2 cavities	= <del>2</del>
		<b>16 1/2</b>

-- such scheme could be accommodated if needed (but impacting other projects)  
 -- increasing test rate beyond 16 cavities per month may be possible but will essentially delay/stop other programs/projects

# Cavity Instrumentation in VTS Test




- Each Top Plate is instrumented with 4 or 8 T sensors and 5 or 6 fluxgates for careful monitoring (and active compensation) of fields and cooldown parameters, as it is crucial part of cavity qualification (Q)


# Field Emission Detection

top detector (on the top plate)

VTS test pit floor level



Energy Response Curve



bottom detector  
(bottom of  
construction pit)

construction pit floor level



- Top detector Canberra GP110
- Bottom detector very similar but smaller size to fit in the available space at the bottom of the dewar: Canberra GP100M
- Installation and commissioning of bottom detector is on schedule

# Vertical Test sequence and acceptance

Cavity acceptance criteria, LCLSII-4.5-EN-0590-R0

Parameters	Numbers	Unit
Min Gradient	19	MV/m
$Q_0$	2.5e10	
HOM Qext, operating mode	>2.7e11	
HOM power, at 16 MV/m	<1.0	W
Field emission Onset	> 17.5	MV/m
Field Emission at onset	<1	nA
Cavity center frequency	1.300	GHz
Cavity frequency range, tuned	+/- 20	kHz
$Q_{ext2}$ (field probe)	2.5-7e11	

- Warm RF checks, instrumentation and HOMs tuning
- Fast cooldown from 300K to 4.2K
- Active compensation of magnetic fields during cooldown
- No Q-disease test, overnight at 4.2K
- 2K pumping in the morning, Q vs E curve
- Administrative limit at 24 MV/m, or if excessive radiation observed
- Low T ~ 1.4K curve taken only in cases where Q assessment is needed
- If cavity meets specs proceeds to string assembly, if not DR is generated and disposed of (re-processing, etc)



Magnetic fields at vessel during cooldown, example of fast cooldown

# Performance summary nine cells –RI, pre-production series

## 5 cavities ready for string assembly, 3 awaiting re-HPR/test

Cavity S/ N	Dewar N.	Qo at 16 MV/m @ 2K	Qo at 19 MV/m @ 2K	Max Gradient [MV/m]	Reason for Gradient Limit	FE onset at baseline test [MV/m]	FE onset after HPR test	STATUS
CAV003	3	2.22E+10	2.20E+10	>24	Admin	8 (14)	NONE	Qualified*
CAV007	2	2.40E+10	2.38E+10	>24	Admin	9 (9.6)	NONE	Qualified*
CAV008	2	2.46E+10	2.46E+10	>24	Admin	18 (12)	NONE	Qualified
CAV015	2	2.52E+10	2.5e10	>26	Admin	15 (11)	NONE (x-rays present in MP band, cleared)	Qualified
CAV006	2	2.4E+10	2.4E+10	>24	Admin	19 (11)	NONE	Qualified*
CAV011	2	2.27E+10	2.20E+10	>21	Admin (FE)	14 (12)		re-HPR/retest by Fri 16
CAV013	3	--- (issues with 2K pumping)	---	---	Admin (FE)	8		re-HPR/retest by Fri 16
CAV016	3	--- (issues with 2K pumping)	---	---	Admin (FE)	14		re-HPR/retest by Tue 20
Average		2.38E+10	2.36E+10	>24				

test today

- 8 cavities out of 8 required DR, reprocessing (re-HPR) and re-testing, which resulted in some schedule delays despite highest priority given (100% re-work)

---

# Re-processing



# Re-processing methodology

---

- If cavity does not meet FE requirements:
  - Re-HPR at FNAL or ANL facilities
  - If still FE present after two re-rinses then consider light EP (light EP ~ 5-7 microns of dressed cavities has already been successfully implemented on several pCM cavities)
- If cavity does not meet gradient spec
  - Consider on case by case
  - If quench field very low, may open and optically inspect for potential major issue (eg scratches etc)
  - Consider light EP in some cases
- If cavity does not meet Q spec
  - Examine cooldown and magnetic field data
  - Decide on case by case basis

# High Pressure Rinsing Facilities

Two facilities in use by FNAL for High Pressure Rinsing

## SCSPF

- Superconducting **C**avity **S**urface **P**rocessing **F**acility
- Built as part of the joint ANL / SCSPF facility
- Utilizes self contained apparatus
- Located in Class 10 Cleanroom

## CPL

- **C**avity **P**rocessing **L**ab
- Tool isolated from room by doors
- Located in Class 10 Cleanroom
  
- Both Facilities use identical recipes for LCLS-II Cavities
- Both Facilities are severely overbooked and represent the bottleneck in cavity processing
- 30% reprocessing rate planned, anything larger requires re-prioritization and impacts severely other projects/programs, and can result in schedule delays for LCLS-2
- By-Weekly scheduling/prioritization of tool usage done via SRF Program/Facilities meeting



# Facility Tools

SCSPF HPR TOOL



CPL HPR Tool



# LCLS-2 High Pressure rinse recipes

## Two Recipes Have Been Used for Re-Processing

- **Complete Disassembly (~ 5 days)**
  - All cavity peripherals are removed
  - Cavity receives 1 pass of HPR
    - Rinsing begins with the wand at the top of the cavity and cavity moves in the upward direction
  - Both HOM Feedthroughs, field probe, beamline flange blank, and fundamental power coupler are installed
  - Cavity receives 3 more passes of HPR
    - Rinsing begins with the wand at the top of the cavity, cavity moves in the upward direction, cavity then moves downward for the 2<sup>nd</sup> pass, and completes with the cavity moving upward with the wand ending in the lower beamtube
- **Field Emission Mitigation (~3.5 days)**
  - Lower beamline flange assembly removed
  - Cavity receives 3 passes of HPR
    - Rinsing begins with the wand at the top of the cavity, cavity moves in the upward direction, cavity then moves downward for the 2<sup>nd</sup> pass, and completes with the cavity moving upward with the wand ending in the lower beamtube.

---

**HTS**

# Scope and goals of HTS testing

---

## 1. Current scope includes ~1 cavity every two cryomodules, to address:

- QA of processes, procedures, and parts
- Are the processes, procedures, tooling, and staffing yielding the required performance of the combined SYSTEM when assembled from qualified individual components
- Are the vendor-supplied components conforming (or still conforming) to required performance specifications when used/operated under conditions similar to those encountered during cryomodule operation (and which cannot be duplicated “on the bench”).
- Investigate critical problems/issues in production, on an as-needed basis
- Detailed (limited scope) investigation of problem and/or mitigation
- Long-term reliability or stability testing (tuners, coupler, LLRF systems)
- **At this level of scope no clear bottlenecks are envisioned**

---

# Travelers

# Incoming inspection Traveller Example

## LCLS-II 1.3 GHz Dressed Cavity Incoming Inspection Traveler (RFCG)

464305 Rev. NONE


by Timothy McKenna

Series	Serial No.	Job No.	Task No.	Released By	Released Date	Status
RFCG	CAV0003-0	584	n/a	Timothy McKenna	7/28/2016 4:57:22 PM	Closed

5.3.10 Check for the presence of caps on helium service pipe (caps made of PE-LD on both ends of the 2-phase pipe).

*Pass*

*Fail*



# Minor Issues

---

- **Minor deviations found**
  - absence of plastic caps on RF connectors
  - absence of drilled holes on RF connectors in some of the cavities
  - QA mark placed on the support lug in an undesirable place/surface
  - Input coupler antenna too long (RF inspection indicated that  $Q1*Q2$  was lower than expected, confirmed at VTS)
  - absence of VCR connector on RAV
  - All these were addressed, future cavities are not expected to have them
- **All these were addressed, future cavities are not expected to have these issues**

# Noting Minor Issue in Incoming inspection Traveller

## LCLS-II 1.3 GHz Dressed Cavity Incoming Inspection Traveler (RFCG)

464305 Rev. NONE


by Timothy McKenna

Series	Serial No.	Job No.	Task No.	Released By	Released Date	Status
RFCG	CAV0003-0	584	n/a	Timothy McKenna	7/28/2016 4:57:22 PM	Closed

5.3.24 Check to make sure there are 6 bolts with washers.

Pass

Fail




Comments: *No Protective cap*




# Cooldown rates (Examples)

VTS-2 filled from VTS-3



VTS-3 filled from cryoplant main storage dewar



# Cooldown rates (Examples)

LCLS-II 1.3 GHz Nine Cell Dressed Cavity 2K VTS Testing (RFCG)  
464170 Rev. A  
by Jan Szal

Series	Serial No.	Job No.	Task No.	Released By	Released Date	Status
<u>RFCG</u>	<u>CAV0003-0</u>	<u>584</u>	n/a	Oleksandr Melnychuk	8/1/2016 4:47:16 PM	Closed

## 5.0 Testing and Results

### 5.1 Test Operator, and Date.

Principal Test Operator: *Oleksandr Melnychuk*

Test Date: *8/2/2016*

### 5.2 Cool down Parameters.

Enter the temperature gradient between top and bottom when bottom transitions trough Tc.

Temperature Gradient *199 K*

# Traveler Status

---

- **Traveler Status**

- **464305 – Incoming Inspection – Passed all travelers closed**
- **464282 – Incoming Leak Check – Passed all travelers closed**
- **464314 – Incoming CMM – Passed all travelers closed**
  - CAV0008 example
- **464224 – Incoming RF Measurements – Passed all travelers closed**
- **464189 – Reprocessing – All closed**
- **464240 - Preparation and Installation of a Cavity in the Vertical Test Stand -- All closed except for re-tests that did not happen yet**
- **464170 - LCLS-II 1.3 GHz Nine Cell Dressed Cavity 2K VTS Testing -- All closed except for re-tests that did not happen yet**

# Vector Traveler Status

All Inspection, Reprocessing, Preparation and VTS testing travelers that should be closed at this point are closed !

Serial Number	464305 - LCLS-II 1.3 GHz Dressed Cavity Incoming Inspection Traveler (RFCG)	464282 - LCLS-II 1.3 GHz Dressed Cavity Incoming Inspection Leak Check Traveler (RFCG)	464224 - LCLS-II 1.3 GHz Dressed Cavity RF Incoming Inspection Traveler (RFCG)	464314 - LCLS-II 1.3 GHz Dressed Cavity Incoming Inspection CMM Traveler (RFCG)	464189 - LCLS-II Vertical Test (VTS) Preparation of 1.3GHz Dressed Cavities	464240 - Preparation and Installation of a Cavity in the Vertical Test Stand (VTS)	464170 - LCLS-II 1.3 GHz Nine Cell Dressed Cavity 2K VTS Testing (RFCG)
CAV0003 - 0	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>
CAV0003 - 1						<a href="#">Closed</a>	<a href="#">Closed</a>
CAV0006 - 0	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>		<a href="#">Closed</a>	<a href="#">Closed</a>
CAV0006 - 1						<a href="#">Closed</a>	<a href="#">Closed</a>
CAV0007 - 0	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>		<a href="#">Closed</a>	<a href="#">Closed</a>
CAV0007 - 1						<a href="#">Closed</a>	<a href="#">Closed</a>
CAV0007 - 2						<a href="#">Closed</a>	<a href="#">Closed</a>
CAV0008 - 0	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>		<a href="#">Closed</a>	<a href="#">Closed</a>
CAV0008 - 1						<a href="#">Closed</a>	<a href="#">Closed</a>
CAV0011 - 0	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>		<a href="#">Closed</a>	Open - <a href="#">63/85</a> (74%) <a href="#">Done</a>
CAV0011 - 1							Open - <a href="#">0/85</a> (0%) <a href="#">Done</a>
CAV0013 - 0	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	Open - <a href="#">59/85</a> (69%) <a href="#">Done</a>
CAV0013 - 1						Open - <a href="#">19/69</a> (27%) <a href="#">Done</a>	Open - <a href="#">0/85</a> (0%) <a href="#">Done</a>
CAV0015 - 0	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>
CAV0015 - 1						<a href="#">Closed</a>	<a href="#">Closed</a>
CAV0016 - 0	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	<a href="#">Closed</a>	Open - <a href="#">59/85</a> (69%) <a href="#">Done</a>
CAV0016 - 1							Open - <a href="#">0/85</a> (0%) <a href="#">Done</a>
TRACCO15							

# Discrepancy Reports (Field Emission in VTS tests)

[Vector Home](#)

[Reports](#)

## Vector - Select Discrepancy Report - Read Only

DR Number	Document	DR Status
<a href="#">10900</a>	CAV0003-0--464170--LCLS-II 1.3 GHz Nine Cell Dressed Cavity 2K VTS Testing (RFCG)	Closed
<a href="#">10901</a>	CAV0006-0--464170--LCLS-II 1.3 GHz Nine Cell Dressed Cavity 2K VTS Testing (RFCG)	Closed
<a href="#">10902</a>	CAV0007-0--464170--LCLS-II 1.3 GHz Nine Cell Dressed Cavity 2K VTS Testing (RFCG)	Closed
<a href="#">10903</a>	CAV0007-1--464170--LCLS-II 1.3 GHz Nine Cell Dressed Cavity 2K VTS Testing (RFCG)	Closed
<a href="#">10904</a>	CAV0008-0--464170--LCLS-II 1.3 GHz Nine Cell Dressed Cavity 2K VTS Testing (RFCG)	Closed
<a href="#">10905</a>	CAV0011-0--464170--LCLS-II 1.3 GHz Nine Cell Dressed Cavity 2K VTS Testing (RFCG) - <b>Awaiting Disposition Verification (Oleksandr Melnychuk)</b>	Dispositioned
<a href="#">10906</a>	CAV0015-0--464170--LCLS-II 1.3 GHz Nine Cell Dressed Cavity 2K VTS Testing (RFCG)	Closed
<a href="#">10912</a>	CAV0013-0--464170--LCLS-II 1.3 GHz Nine Cell Dressed Cavity 2K VTS Testing (RFCG) - <b>Awaiting Disposition Verification (Oleksandr Melnychuk)</b>	Dispositioned
<a href="#">10913</a>	CAV0016-0--464170--LCLS-II 1.3 GHz Nine Cell Dressed Cavity 2K VTS Testing (RFCG) - <b>Awaiting Disposition Verification (Oleksandr Melnychuk)</b>	Dispositioned

# Status Report

## 464170 - 1.3 GHz Cavity VTS Performance and Acceptance Status (JS)

Serial Number	Rework ID	5.6 Qext1 464170 (Rev. B)	5.6 Qext2 464170 (Rev. B)	5.6 Q HOM A 464170 (Rev. B)	5.6 Q HOM B 464170 (Rev. B)	5.7 Eacc at Maximum Q0 464170 (Rev. B)	5.7 At E <sub>acc</sub> of 16MV/m : 464170 (Rev. B)	5.8 Rad <sub>max</sub> : 464170 (Rev. B) - mR/hr	6.1 Qualified 464170 (Rev. B)	6.1 Need reprocessing 464170 (Rev. B)	6.1 Rejected 464170 (Rev. B)
CAV0003	0					10.7	1.98	7400	○	●	○
CAV0003	1	1.7E10	3.55E11	1.5E13	1.3E12	16	2.22	0	●	○	○
CAV0006	0	5.5E9	3.46E11	8.5E12	2.4E12	15	2.42	200	○	●	○
CAV0006	1	5.1E9	4.63E11	4.4E12	1.7E12	18	2.38	0.06	●	○	○
CAV0007	0					11.9	2.13	7210	○	●	○
CAV0007	1		2.27E11			11	2.3	385	○	●	○
CAV0007	2	1.5E10	2.95E11	2.3E13	8.4E11	14	2.4	0	●	○	○
CAV0008	0	5.5E9	2.82E11	1.4E12	6.8E11	16.3	2.46	450	○	●	○
CAV0008	1	5.7E9	4.11E11	9.6E12	7.4E11	16	2.46	0	●	○	○
CAV0011	0	4.2E9	1.58E11	1.3E15	1.2E12	14	2.2	608	○	●	○
CAV0011	1								○	○	○
CAV0013	0	5.4E9	2.76E11	8.3E12	1.1E12			12	○	●	○
CAV0013	1								○	○	○
CAV0015	0	4.3E9	3.36E11	5E12	7E11	12.5	2.23	495	○	●	○
CAV0015	1	1.5E10	3.61E11	8.5E13	9.7E11	16.1	2.52	16.9	●	○	○
CAV0016	0	4.5E10	3.07E11	1.5E12	7.7E11			130	○	●	○
CAV0016	1								○	○	○
CAV0016	2								○	○	○



# **Safety**



# Safety

---

464045 - NONE - Procedure for SRF Cavity Handling in the IB4 CPL Cleanroom Area

464044 - NONE - Procedure to Authorize Personnel to Handle SRF Cavities in the CPL Cleanroom Area

333960 - NONE - Procedures for SRF Cavity Handling at IB4 RF Laboratory

333959 - NONE - Procedure to Authorize Personnel for SRF Cavity Handling at IB4 RF Laboratory

# Safety (IB4, Cont'd)

---

333957 - NONE - Procedures for SRF Cavity Handling at ANL/FNAL SCSPF

333956 - NONE - Procedure to Authorize Personnel for SRF Cavity Handling at ANL/FNAL SCSPF

333955 - NONE - Procedures for SRF Cavity Handling at CAF

333954 - NONE - Procedure to Authorize Personnel for SRF Cavity Handling at CAF

333953 - NONE - Quality and Materials Department Cavity-related Work Authorization Process

333952 - A - Procedure for Inter-Facility Transport of 1.3 GHz Nine-Cell SRF Cavities

333951 - A - Radio Frequency Cavity Handling Guidelines

TD-7050                      Procedures for Working in Industrial Building #4

## Safety Cont'd (VTS specific)

---

- Have been well prepared for LCLSII production testing
- VTS-2 and VTS-3 test stands were granted ORC by Dave Harding on 11/18/2014
- Test stand cryogenic systems were signed off by the cryo safety subcommittee in mid-October 2014
- Developed a method for establishing relief calculations for "new" devices.
- Conducted radiation verification tests before final ORC was granted
- Relevant building safety and cavity handling procedures in place

# Summary

---

- Cavity prep and test has adequate resources to meet the goal of qualifying 8 cavities a month, under the 30% XFEL reprocessing rate experience
- Well qualified teams in place, for processing and testing
- Procedures, travellers in place and successfully implemented on trial run with pre-production series from RI
- Re-work > 30% (re-HPR, re-test) could cause schedule delays due to large number of other project/programs ongoing at FNAL (conflicts for cryo-usage and processing tools)

---


## **Backup slides**

# High Pressure Rinse Water Source

## Ultra Pure Water


- Resistivity monitored for  $\geq 18$  MegaOhm quality

Total Organic Compounds monitored for quality




# High Pressure Rinse Water Delivery

- Lewa Diaphragm Pump
- Electropolished S.S. high pressure delivery manifold
- 1200 p.s.i water delivered from two 45 degree fanjet nozzles
- Each nozzle delivers approximately 2 GPM





# Mechanical Translation




- Wand rotates inside cavity
  - Speed is approximately 3 RPM
- Cavity moves longitudinally
  - Speed is approximately .2” per minute
- Each longitudinal pass takes approximately 4 hours


# CAV008 before – after re-evac

At receipt/Vertical test pressure  $2e-4$  Torr

Cavity was then brought to clean room, re-evacuated overnight to  $\sim 1e-7$  Torr, retested



# FF measurements CAV003



## Optical inspection – CAV003

No major features revealed (no scratches, etc)

But very strange surface appearance – bumpy and wrinkly – not sure why?

