

# Recent Status of J-PARC Neutrino Beam-line

---

T. Nakadaira (KEK)  
for  
J-PARC neutrino experimental facility


# Outline

- \* Overview of J-PARC neutrino beam-line
- \* Beam operation history
- \* Recent status (troubles)
- \* Upgrade plans
- \* Summary


# J-PARC neutrino primary beam-line

Beam monitors are install along the proton beam transport

Profile (19)



Position (21)



Intensity (5)



Beam loss (50)




Primary proton transport line



Super-conducting combined-function magnets



Normal-conducting magnets



Target

Decay Volume


Beam

Extraction points

Optical Transition Radiation (OTR)  
Profile monitor



Target :graphite rod  
f26mm,L=900mm

# J-PARC neutrino secondary beam-line



# Operation history

- \* Beam quality is kept well.
- \* Flux at ND/SK is estimated with  $\sim 10\%$  uncertainty.
- \* 425kW beam operation achieved.  
→  $2.27 \times 10^{14}$  p/pulse
- \* 440kW trial is also performed.
- \* By 2016 May,  $1.510 \times 10^{21}$  POT is supplied for physics data for T2K.
- \*  $\nu$ -mode :  $7.57 \times 10^{20}$  +  $\bar{\nu}$ -mode :  $7.53 \times 10^{20}$
- \* Beam operation for neutrino beam-line is resumed from Oct. 2016




# Big maintenance

- \* For secondary beam-line, it is necessary to open the concrete shields, He vessel by remote operation.
- \* 2011: Inspection after the big earthquake.
- \* 2014: Replacement of all three horns
  - \* Water-leak was happened at horn itself.
- \* 2015: Target cooling He leak.
  - \* Inspection and repair was done.
  - \* OTR system also met the trouble.
- \* 2016: No maintenance in He vessel.
  - \* Inspection of the outside of beam-window.


# 2015 Target He leak problem

- \* Target: ~23kW heat load at 750kW → Cooled by He gas
- \* In May 2015, Pressure of He gas become unstable.
- \*  $\sim 10^{-1}$  Pa m<sup>3</sup>/h (Requirement:  $\sim 10^{-3}$  Pa m<sup>3</sup>/h)

2015 May





2016 Apr, May (Normal)





Target :graphite rod  
 $\phi$ 26mm, L=900mm

# 2015 Target He leak problem


- \* There is no He leak found the He tubes outside TS He vessel, we have decided to open He vessel for further inspection.
- \* There is no leak at the top of horn module → Horn + target is transported to maint. area.



Top view of Target Station





No leak found at top of the horn support.










# Target He-tube inspection at maintenance area

- \* At the maintenance area, the inspection by manipulator is performed.
- \* Air is sampled by hand-pump and checked by handy gas detector.  
→ He leak was found at **ceramic break!**
- \* Fixing the leak by compound was tried.  
→ We have confirmed that there is no other leak point.



# Replacement of the He tube





- \* Improved He tube with ceramic break and the remote exchange tools are prepared by RAL and KEK. The exchange work is done by the corroboration among RAL, TRIUMF and KEK.
- \* Distortion of U-shape part made by cold working may be cause of the trouble → C-shape with miter joint (welding) is adopted.



Replaced by manipulators  
at the maintenance area

# OTR inspection


- \* OTR system: Mirror alignment check
- \* Trouble in the disk rotation: Required torque become large.  
It can not to be rotated by remote controlled motor.  
→ Now we are using 1 Ti foil.





# Beam window inspection

- \* In 2016, we have checked the beam window by removing the upper shields to check what kind of work is necessary for exchanging with spares.
- \* “Pillow seal” used for Vacuum / He-gas requires the very good surface condition. We have to consider the method to clean up, if necessary.

Target Station (TOP View)






In 2016 →





# To achieve 750 kW p-beam operation

- \* Upgrade the beam-line for 1Hz operation.
- \* Horns : 2 PS + 2 old trans. + 3 horns  
→ 3 PS + 3 new trans. + 3 horns.
- \* Currently used pulse transformers are produced for 250kA operation for K2K in '90s.
- \* New pulse transformers for 320kA is under design.  
→ ~10% improvement for  $\nu$  flux / POT is also expected.
- \* DAQ for beam monitors.
- \* Beam interlock system.  
→ The module that issues the fast Inhibit signal using the beam monitor outputs processed by FPGA.



# To achieve 750 kW p-beam operation

- \* Upgrade the beam-line for 1Hz operation.
- \* Horns : 2 PS + 2 old trans. + 3 horns  
→ 3 PS + 3 new trans. + 3 horns.
- \* Currently used pulse transformers are produced for 250kA operation for K2K in '90s.
- \* New pulse transformers for 320kA is under design.  
→ ~10% improvement for  $\nu$  flux / POT is also expected.
- \* DAQ for beam monitors.
- \* Beam interlock system.  
→ The module that issues the fast Inhibit signal using the beam monitor outputs processed by FPGA.




# Future plans

- \* The T2K experiment submitted the proposal of extended data accumulation up to  $2 \times 10^{22}$  POT to J-PARC PAC in June 2016.
- \* PAC recommended the Stage-1 status in July 2016.
  - \* Cf. J-PARC has 2-stage approval.
    - \* Stage-1 status: Physics interest is recognized.
    - \* Stage-2 approval: Green signal for execution.
- \*  $\sim 1.3$  MW beam power is expected.
- \* New short base line experiment E62 (NuPrism) got stage-1 status, too.
- \* The J-PARC upgrade for the future long base-line neutrino experiment using Hyper-K is recognized as KEK Project-implementation-plan (PIP) with high priority.

J-PARC MR-FX beam power upgrade strategy

	Achieved (User beam)		Mid-term plan		Long-term plan
Protons/pulse	$2.2 \times 10^{14}$		$2.2 \times 10^{14}$	→	$3.2 \times 10^{14}$
Repetition cycle	2.48 s	→	1.3 s	→	1.16 s
Beam power	420 kW		800 kW		1.3 MW

↑ Protons / pulse required to achieve original design intensity (750 kW) has been achieved.




# To do list for $>1$ MW beam power

- \* Reinforce the radiation shield of the Target Station.
- \* Enlarge the processing capacity of the radioactive waste (activated cooling water, etc.)
- \* See next slide
- \* Reinforce the cooling capability of target, electromagnetic horns, TS He vessel, Decay Volume, and beam-dump.
- \* Enlarge the aperture of the magnet for upstream part of primary proton transport (if necessary).
- \* Primary beam monitors that cause less beam-loss.
- \* Sophistication of remote maintenance procedure for activated equipment.



# Reinforcement of Radio-activated water treatment

- \* Target station (TS + Upstream of DV) : Plans in JFY2018



- \* NU3 (Downstream of DV + BD) : Started from JFY2015~

- \* Transport activated water to the facility of JAEA with tank track.



# Summary

- \* J-PARC Neutrino beam-line met the troubles in target system in 2015. It was fixed by remote operation.
- \* In 2016 beam time, there is no severe trouble that takes long maintenance period.
- \* No trouble in 440kW trial.
- \* There are several work to achieve  $\sim 1$ Hz operation and  $>1$ MW beam.
- \* We plan to do the upgrade work that requires long shutdown in JFY2018 during the J-PARC MR power supply upgrade as much as possible.