



PIP-II Fermilab R&D Program

Paul Derwent

IIFC Joint R&D Meeting


4 January 2017

The PIP-II R&D Program

- The purpose of the R&D program is to mitigate technical and cost risks, by validating the choices made in the PIP-II facility design and by establishing fabrication methods for major sub-systems and components, including the qualification of suppliers
 - Technical risk: impair the ability to meet fundamental performance goals
 - Cost/Schedule risk: compromise the ability to meet currently understood cost or schedule goals
 - To complete in advance of Department of Energy Approval for project construction

PIP-II Scope

PIP-II Injector Test



Section	Freq	Energy (MeV)	Cav/mag/CM	Type
RFQ	162.5	0.03-2.1		
HWR ($\beta_{opt}=0.11$)	162.5	2.1-10.3	8/8/1	HWR, solenoid
SSR1 ($\beta_{opt}=0.22$)	325	10.3-35	16/8/ 2	SSR, solenoid
SSR2 ($\beta_{opt}=0.47$)	325	35-185	35/21/7	SSR, solenoid
LB 650 ($\beta_{opt}=0.65$)	650	185-500	33/22/11	5-cell elliptical, doublet*
HB 650 ($\beta_{opt}=0.97$)	650	500-800	24/8/4	5-cell elliptical, doublet*

*Warm doublets external to cryomodules

All components CW-capable

PIP-II Injector Test: PIP2IT

- Mission Statement:

The PIP-II Injector Test (PIP2IT) facility replicates the front end of the PIP-II linac through the first SSR1 cryomodule. PIP2IT is intended to serve as a complete systems test that will reduce technical risks associated with the PIP-II linac in both pulsed and CW operating modes. It is anticipated that PIP2IT will be operated for several years beyond the initiation of PIP-II construction, with the eventual relocation of major PIP2IT components and systems into the PIP-II linac enclosure, where they will serve as part of the PIP-II front end. The construction and operating period of PIP2IT splits naturally into two phases.


- Phase 1 (R&D plan):

- retirement of risks associated with operation of the PIP-II linac in pulsed mode as required for neutrino operations and described in the CDR (1% duty factor).

- Phase 2 (post-CD-3):

- retirement of risks associated with CW operations, in particular as related to utilization of the PIP-II linac for a second generation Mu2e experiment
- important for future scientific opportunities with PIP-II linac

PIP2IT: Phase 1 Deliverables




Phase 1 (R&D plan): retirement of risks associated with operation of the PIP-II linac in pulsed mode as required for neutrino operations and described in the CDR (1% duty factor). The primary risks to be retired during this period include:

- Achievement of required beam characteristics from the ion source through the SSR1 cryomodule.
- Demonstration of MEBT chopper operations at a level required for Booster injection
- Demonstration of the operation of the HWR cryomodule, with beam, in close proximity to the MEBT beam absorber
- Demonstration of stable beam acceleration in the SSR1 cryomodule, under the full control of prototype RF control systems, including resonance control within the cavities

Collaborators	
ANL:	HWR
LBNL:	LEBT, RFQ
SNS:	LEBT
BARC:	MEBT, RF
IUAC:	SSR1



PIP2IT: MEBT

- The MEBT primary technical deliverables:
 - Beam Chopping
 - Forms the bunch structure required Booster injection
 - Testing Prototype kickers in FY17
 - Testing Prototype absorber in FY17
 - Vacuum Management
 - absorber upstream of SRF Cryomodule
 - Progress Dependent on delivery of BARC quadrupoles
 - Ready for Installation ~4 weeks after delivery



Beam size measurements

- The beam transverse size is measured by scrapers
 - Full scans with 10- μs bunch trains; $\sim 2\sigma$ tails for high-power beam
- Quadrupole scans to reconstruct Twiss functions and emittance




Quadrupole current, A

Quadrupole scan and fitting (solid curves). Measured rms sizes are shown by circles (X) and squares (Y). Fitted emittances (rms, n) are 0.19 μm X and 0.20 μm Y.

Long runs

- Several runs at constant beam parameters
 - 9- 24 hours, 2.5 – 0.5 kW of average beam power
 - Ran by operators
 - Beam is reasonably stable
 - Need to improve beam position stability and trip recovery procedures


Example of 24-hours of beam running to the absorber prototype. 10 Hz, 4.5 ms 5 mA beam pulse. RFQ in pulsed mode, 10 Hz, 4.8 ms. Dec 7-8, 2016. Beam was up for 97% of time.



26 hours


MEBT stages

- MEBT is being installed in ~~3~~ 2 main stages, different in the number of focusing elements
 - Full-length MEBT is expected to be installed in 2017



IIFC LLRF Status

- Seven joints FRSs Approved (two more near approval)
 - TRSs in process
- 8-Channel Down-Converters
 - BARC version is in manufacturing process
- 4-Channel Up-Converters
 - FNAL version tested
 - BARC version is in manufacturing process
- FPGA Board
 - In schematic review process
- ADC-DAC FMC Module
 - Ready for manufacturing
- Resonance Control Chassis
 - Leverage from FNAL LCLS-II design and is in progress
- Prototype RF Protection and Interlock System
 - Delivered & Tests on going
 - Software / Executable process an issue
 - Fermilab Engineering Manual requires source code documentation and maintenance under a suitable version control process




SRF

- PIP-II includes
 - 5 different SRF cavity types and cryomodules
 - Half Wave Resonator:
 - 2 Single Spoke Resonators
 - 2 elliptical cavities
 - 3 different frequencies (162.5 MHz, 325 MHz, 650 MHz)
- R&D program:
 - test one complete cryomodule of each frequency to full power
 - HWR & **SSR1** @ PIP-II Injector Test with beam : FY19
 - **HB650** in a test stand with RF power : FY20
 - test LB650 dressed cavities with RF power : FY19
 - test bare SSR2 cavities in vertical test stand : FY19
 - Resonance control of cavities in pulsed mode operation (Lorentz Force Detuning)
 - Combination of High Q_{ext} , pulsed operation
 - Passive means: Mechanical design
 - Developing a piezo-based feed forward and feedback system
 - Application of High Q_0 R&D to PIP-II 650 MHz cavities



SSR1

- Single Spoke Resonator Cryomodule:
 - 8 325 MHz $\beta=0.22$ Single Spoke cavities
 - 4 SC focusing solenoids (& BPM)
 - 11 MeV \rightarrow 25 MeV
- India Institutes Fermilab Collaboration (IIFC)
 - 12 cavities fabricated (10 FNAL, 2 IUAC New Delhi)
 - Fabrication/Assembly 2017




dressed SSR1 cavity in
test cryostat

Lab 2 SRF Cavity & Cryomodule Cleanroom Facility



Introduction to Lab2: design and current status

- ❑ The cleanroom at Lab 2 is ready to receive the SSR1 string assembly
 - ✓ Single pass design was adopted for Lab2 clean room, air is filtered into the clean room and transferred out into the surrounding building
 - ✓ Cleanroom construction completed and qualified
 - ✓ Ultra Pure Water system and ultrasonic cleaners are fully functional
 - ✓ Crane for US area is finalized
 - ✓ Nitrogen gas lines are installed:
 - 900 gal liquid nitrogen dewar installed
 - Line installation completed



Particle free cleanroom assembly for SRF applications

Example: SSR1 Coupler installation procedure



1.

Cavity is placed on a post inside Lab2 class 10 cleanroom and tooling is installed underneath

Tooling is previously cleaned using the standard procedure and then assembled in the cleanroom



2.

Connection to vacuum cart is performed and leak checked, RAV is close



3. Hardware is cleaned using the standard procedure

Cold end tube weldment is cleaned:

- Ultrasonic cleaning for 10 minutes at 25% of the power used for SS in a bath of DI water and simple green.
- Ultrasonic cleaning for 10 minutes at 25% of the power used for SS in a bath of DI water and liquinox

Antenna assy is cleaned :

- Gently wipe with lint free wipes and isopropyl alcohol.

Particle free cleanroom assembly for SRF applications

Example: SSR1 Coupler installation procedure



3.

Vacuum end coupler is assembled and then blow clean with ionized nitrogen and using a particle counter




4.

Cavity is backfilled with ionized nitrogen and the pressure is slightly above atm.

Vacuum end coupler is placed on the tooling

A Teflon cap, held by metal clips, protect the tube from contamination



5.

2 long studs are placed in the cavity flange and used to adjust the tooling and put the vacuum end coupler in the correct position

Once the coupler is aligned all the set screw but the longer ones are removed



6.

Cavity blank is removed and vacuum end coupler is approached to the cavity flange

Once the coupler is secured the tooling is removed and the torquing process begin using the standard procedure but with a maximum torque of 250 in lbs

PIP-II : Resonance Control

W. Schappert

- As cavity gradients rise matched bandwidths narrow
- Minimizing detuning is critical for narrowband machines
- PIP-II presents a unique challenge because of the combination of narrow bandwidths and pulsed operation

			Mode	Gradient	Current	Frequency	Half Bandwidth	LFD	Peak Detuning	Peak Detuning/BW	LFD/BW
				MV/m	mA	MHz	Hz	Hz	Hz		
Wideband CW											
ARIEL	TRIUMF		e- CW	10	10	1300	220				
SPIRAL-II		30 MeV, 5 mA protons -> Heavy Ions	Ion CW	11	0.15-5	88	176				
Wideband Pulsed											
XFEL	DESY	18 GeV electrons – for Xray Free Electron Laser – Pulsed)	e- Pulsed	23.6	5	1300	185	550			3
ESS	Sweden	1 – 2 GeV, 5 MW Neutron Source ESS - pulsed	p Pulsed	21	62.5	704	500	400			1
Narrowband CW											
CEBAF Upgrade	JLAB	Upgrade 6.5 GeV => 12 GeV electrons	e- CW	20	0.47	1497	25		10	0.40	
LCLS-II	SLAC	4 GeV electrons –CW XFEL (Xray Free Electron Laser)	e- CW	16	0.06	1300	16		10	0.63	
FRIB	MSU	500 kW, heavy ion beams for nuclear astrophysics	Ion CW	7.9	0.7	322	15		20	1.33	
cERL	KEK										
Narrowband Pulsed											
PIP-II	Fermilab	High Intensity Proton Linac for Neutrino Beams	p Pulsed	17.8	2	650	30	300	20	0.67	10

http://accelconf.web.cern.ch/AccelConf/IPAC2015/talks/thzms3_talk.pdf

Recent Progress on Active Control



W. Schappert

- Resonance Control has had an extended set of test time at STC while waiting for the next SSR1 cavity to be ready for testing. We estimate 80 working days of testing time, an up time of 60%.
- This extended testing time allowed extensive studies of:
 - Signal qualities/RF circuit
 - Detuning calculation and implementation
 - Feedback/Compensation techniques
- Development of a complementary Self-Excited Loop testing system
- These techniques were developed, coded, and refined first for CW operation, then in pulsed operation.
- This work gives a solid foundation for further testing going forward including different cavity geometries.

Test Conditions

W. Schappert


- PIP-II nominal operating conditions
 - 12.5 MV/m
 - 20 Hz repetition rate
 - 15% duty cycle
 - 0.5ms flattop
- STC operating condition
 - >12.5 MV/m
 - 25 Hz repetition rate
 - 7.5 ms fill
 - 7.5 ms flattop



Preliminary Offline Analysis


W. Schappert

- Within a factor of 2 of PIP-II specs
 - $\sim \pm 2.7\sigma$ within 20 Hz
- Improvements in feedback may help
 - May be possible to automatically extract optimal coefficients from data



SRF: HB650


- Elliptical Cavity Cryomodule:
 - 6 650 MHz $\beta=0.97$ 5 Cell Elliptical cavities
 - Focusing elements are outside the CM



HB650 5 cell cavity

- India Institutes Fermilab Collaboration (IIFC)
 - Cavities of different β at various stages of manufacturing, processing, or testing
 - CM design complete in 2017
 - Test 6 (3 FNAL, 3 RRCAT) dressed cavities in HTS-2

Current status and plans for 650 MHz $\beta = 0.9$ cavities at FNAL




Optical Inspection of 5-cell B=0.9 650 MHz cavity

Total 5 bare cavities of $\beta=0.9$ cavities are at TD → Four AES + One PAVAC

5-cell B=0.9 650 MHz cavity prepared for vertical testing.

HB650 Cavity performance testing



Five-cell $B=0.90$ test results.

*A. M. Rowe, et al, CAVITY PROCESSING AND PREPARATION OF 650 MHz ELLIPTICAL CELL CAVITIES FOR PIP-II, LINAC 2016

Status for Dressing $\beta=0.9$ bare cavities

- Cavity components
 - ❖ Bare cavity → AES-009 qualified as per revised target, others to be processed/ reprocessed
 - ❖ Helium vessel assembly → Initiated procurement
 - ❖ Bellow → Initiated procurement
 - ❖ Ti bellow adapter ring → Procurement to be requested
 - ❖ Ti vessel transition ring → Procurement to be requested
- Tooling and fixtures
 - Insertion tooling or medium berth a → Assembled last week at MP9
 - Cavity rotating fixture → Initiated procurement
 - Glovebox → Modification design prepared, Procurement to be requested
- Weld sample preparation and qualification for each type of joint
 - Samples under preparation at Fermilab
- Leak testing setup preparation → Leak testing cans designed, Procurement to be requested

Planning for cavity dressing

1st Cavity dressing

Rotating fixture → Jan 2017

Bare cavity → Feb 2017

Leak testing cans → Feb 2017

Updating GB for dressing → Feb 2017

Helium vessel → Mar 2017

1st Cavity dressing → April 2017

Testing of dressed cavity in VTS → May 2017

2nd Cavity dressing → June 2017

Testing of dressed cavity in VTS → Aug 2017


3rd Cavity dressing* → Aug 2017

Testing of dressed cavity in VTS → Sept 2017

* Depends on budget availability

650 MHz coupler: Design Review November 2016

New design, structure of 650 MHz coupler



Review: November 22 2016
Slide from Sergey Kazakov

Charge

Charge:

1. Has code adherence and best engineering practices been implemented in this design?
2. Does the prototype coupler design satisfy the Functional Requirement Specification?
3. Have all required specifications and documentation been completed?
4. In carrying out the design for the prototype coupler, were the following important aspects considered: cryomodule integration, RF integration, assembly/alignment challenges, reliability and maintainability?
5. Which of the two design alternatives is most likely to succeed?
6. Is the Testing plan adequate to ensure that the design will be validated? Are there sufficient quantities of prototypes being ordered to validate the design?
7. Is the prototype coupler design ready for procurement? Which design is preferred?


Review: November 22 2016
Slides from Oleg Pronitchev

Motivation for re-design:

Motivation is based on experience with 325 MHz couplers. 325 coupler (one) was destroyed at power level $\sim 50\text{kW}$ (full reflection). 650 MHz has to operate at higher power $\sim 100\text{ kW}$ (PIP-II) and higher (for some application). We think the most weak and limiting factor can be high density of electrical current at place of metal and ceramic brazing at inner conductor. We decided to increase the diameter of inner conductor 2 times ($0.5'' \rightarrow 1''$) and increase of ceramic window outer diameter from $3''$ to $4''$.

Review: November 22 2016
Slide from Sergey Kazakov




HB 650 MHz Main Coupler on the Cryomodule




Review: November 22 2016
Slides from Oleg Pronitchev


3D-model of the 650MHz tuner

Y. Pischalnikov






Electromechanical actuator (Phytron)
(used for LCLS II project)




4 piezo-capsules for fast/fine tuning (PI piezo used for LCLS II project)
Maximal forces on the piezos $\sim 3\text{kN}$...

First prototype tuner assembled on the of the cavity/He vessel mock-up. Ready for tests. Y. Pischalnikov



Electromechanical actuator (Phyton)



Cartridge with 4 piezo-capsules

Plan for Tuner Design Verification Tests (warm) for 2017

- Tests with Tuner assembled on the cavity/He Vessel mock-up:
 - - stiffness of the tuner (kN/mm);
 - - slow tuner range (mm) and sensitivity ($\mu\text{m}/\text{step}$);
 - - fast/fine tuner range (μm) and sensitivity ($\mu\text{m}/\text{V}$).
- Tests with Tuner assembled on the first dressed cavity
 - - slow tuner range (kHz) and sensitivity (Hz/step);
 - - fast/fine tuner range (Hz) and sensitivity (Hz/V)
 - - transfer function (piezo-to-cavity response... mechanical
 - resonances of the cavity system


Existing Fermilab Rings: Scope

- 700 kW -> 1.2 MW:
 - increase pulse intensity
 - Increase pulse frequency


Parameter	700 kW	PIP-II
Booster Injection Energy	400 MeV	800 MeV
Booster Pulse Intensity	4.3e12	6.4e12
Booster Repetition Rate	15 Hz	20 Hz
RR Pulse Intensity	5.2e13	7.7e13
RR RF Duty Factor	60%	50-100%
MI Pulse Intensity	4.9e13	7.5e13
MI Extraction Energy	120 GeV	60-120 GeV
MI Cycle Time	1.33 sec	0.6-1.2 seconds

Conventional Facilities— Overview

S. Dixon







Typical Linac Cross Section



Cryo Plant Requirements

- Developed requirements for building to house the cryo plant;
- Based on known, typical cryo plant information and will be updated when more specific information is available



PIP-II Priorities

- Goal: Complete the R&D Program in advance of Critical Decision 3: Approve Construction
- R&D Goals
 - PIP-II Injector Test
 - Chopper validation
 - HWR and SSR1 Operation with beam
 - SRF/IIFC
 - SSR1 CM (6 US + 2 India)
 - HB650 CM (3 US + 3 India)
 - LB650 + SSR2 Cavities from India (2 + 2)
 - RF systems (8 US + 16 India)
 - Rings
 - 20 Hz: magnet tested, understand control system impact
 - Booster Injection: design and prototype magnet
 - RR/Main Injector RF: PA tested, prototype RR cavity, prototype γ_t magnet
- Critical Decision Goals
 - CD-1 : Approve Alternative and Cost Range
 - Q4FY17
 - CD-2/CD3a : Approve Baseline / Long Lead Procurement
 - FY18/19
 - CD3 : Approve Construction
 - FY20

Progress at Fermilab


- At PIP2IT
 - beam & measurements in the MEBT
 - Awaiting magnets for further expansion
- In SRF
 - Lab 2 progress: assembly of SSR1 cryomodule
 - Resonance control: LFD and active feedback
 - 650 Cavities, Couplers, and Tuners
- Civil
 - Tunnel cross sections
 - Cryo Plant Requirements
- Priorities
 - Completion of MEBT: Chopper prototype tests
 - HWR & SSR1 operation with beam
 - 650 Cavity and Cryomodules

Backups

PIP-II Injector Test: PIP2IT

- Scope:

- A CW H- source delivering 5 mA at 30 keV
- A low energy beam transport (LEBT) with beam pre-chopping
- A CW RFQ operating at 162.5 MHz and delivering 5 mA at 2.1 MeV
- A medium energy beam transport (MEBT) with integrated wide band chopper and beam absorbers capable of generating arbitrary bunch patterns at 162.5 MHz, and disposing of up to 5 mA average beam current




- Low β superconducting cryomodules capable of accelerating 2 mA of beam to 25 MeV
- Associated beam diagnostics
- Beam dump capable of accommodating 2 mA at full beam energy for extended periods.
- Associated utilities and shielding

PIP2IT Deliverables

- FY17
 - Test of Chopper Prototypes & Absorber : Q4
 - Full Length MEBT installed : Q4
- FY18
 - Cryogenic Distribution System Installed : Q4
 - HWR Delivery, installation started : Q3
 - SSR1 Delivery : Q4
 - Note: no beam operation
- FY19
 - SSR1 installation started : Q1
 - Full Length MEBT commissioned : Q3
 - Bunch by bunch chopping demonstrated: Q3
 - HWR / SSR1 RF commissioned : Q4
 - Initial beam to Cryomodules : Q4
- FY20
 - Beam through Cryomodules : Q1
 - Resonance Control Measurements (SSR1) with beam : Q3

650 MHz Main Coupler assembly F10056895

Air inlet with pusher
F10059980



Cold end
Assembly
F10056896

Outer conductor
with bellows
F10058374



Inner conductor
with bellows
F10057202

Review: November 22 2016
Slides from Oleg Pronitchev

Length ~ 1meter, Weight ~ 50kg

Waveguide assembly
with instrumentation box F10059948

Dressed cavity $\beta = 0.9$





Dressed cavity assembly

Dressed cavity consists of following components:-

1. Helium vessel
2. Transition ring MC end
3. Transition ring FP end
4. Bellow assembly
5. Support lugs
6. Lifting lugs
7. Helium inlet (2 nos.)
8. 2-phase pipe assembly
9. Tuner mounting lugs
10. Magnetic shielding (external)

Weld Joint Configuration for cavity dressing:-
Designed in Accordance with Fermilab ES&H Manual 5031.6 (Dressed Niobium SRF Cavity Pressure Safety)



Cavity Dressing Steps for $\beta=0.9$

Step-1 : Bare cavity preparation

Step-2 : Tack welding #1 preparation in medium bertha

Step-3 : Tack welding #2 & 3 preparation in medium bertha



Step-4 : Cavity installation in rotating fixture and 360° rotating trail inside Glovebox

Step-5: Full penetration welding inside GB


Step-1

Bare Cavity Preparation

- Modified joint for TIG welding
- Analysis of dressed cavity with modified joint for LC1 to LC5
- NbTi-Ti weld Sample preparation inside GB
- Testing and qualification of samples





Full weld in GB → Leak testing



Step-2

Preparation of Dressing in insertion fixture (medium berth)

Weld tack #1




Step-3


Preparation of Dressing in insertion fixture (medium berth)

Weld tack #2 & 3 (Bellow tacking)

Weld tack #3




Weld tack #2



Step-4

360° Rotation fixture

→ Tacked cavity and helium vessel assembly is rotated inside GB




Step-5




Cavity Welding in GB

Cavity installation in Rotating Fixture

Full welding similar as sequenced during tack



Status of medium bertha MP9



Assembled in 1st week of Dec. 2016