

SRF technology for future CERN machines

Frank Gerigk, CERN, GARD-SRF Roadmap Workshop
9-10 February 2017, FNAL



Material from:

Sarah Aull, Olivier Brunner, Rama Calaga, Veronica
Del Pozo Romano, Alexey Grudiev, Erk Jensen,
Mikko Karppinen, Guillaume Rosaz, Nikolai
Schwerg, Alban Sublet, Mauro Taborelli, Giovanna
Vandoni, Walter Venturini

Content




01 LHC

02 HL-LHC

03 FCC

04 Summary

LHC cavities



LHC spare cavity program


- **NB-COATED** Cu single cell cavities operating at 4.5 K.
- 400.790 MHz, 2 MV/cavity.
- 2 cryomodules of 4 cavities/beam.
- **1 spare module and one spare dressed cavity available. Many of the "old" experts have retired.**
- **LHC has a physics program until 2035 and we have no experience with ageing of LHC cryomodules.**

The LHC spare cavity program aims at producing 2 spare cavity trains (4 cavities), which may become potentially 2 complete cryomodules.

➔ re-establishment of engineering folder, welding, tuning, assembly, and coating procedures


➔ industrial production of cavities and subsequent coating at CERN

LHC spare cavity program




Practice cavity 1,2

- full cut-off tubes,
- cavity fabrication tools & process,
- rinsing, chemistry
- Nb-coating (magnetron sputtering),
- qualification & cold tests
- several re-coatings
- not intended as spare




Practice cavity 3,5

- half cells by spinning and electro-hydraulic forming (EHF),
- simplified cut-off tubes,
- cold tests in May/July 2017
- not intended as spare



Model cavity

- validation of cavity design & fabrication process
- He-tank updated design,
- cold test expected August 2017
- if successful: the first spare cavity




Series production

- 8 cavities + 2 spares,
- tendering for cut-off tubes early 2017,
- production of half cells (spun or EHF)
- He-tanks tendering in 2017

LHC spares: timeline

2016	2017	2018	2019	2020	
design & analysis					
Practice cavity 1,2					
Practice cavity 3,5					
	Model cavity				
	Market survey, IT, technology transfer				
		spare cavities 1-4			
		spare cavities 5-8			


- Don't change a working system...
- Trying to replicate the original design as good as possible (with very little documentation). Only then do we get derogation from the pressure vessel tests...
- Reverse engineering effort.
- Inside welding no longer feasible, now welding from the outside.
- Calculations on material stresses, which were not possible in the original design stage.
- 40 companies contacted in market survey for cut-off tubes and potentially cavity welding: 2 replied.
- Quality of coating to be re-established.
- Tuning machine corroded in the fields. New machine to be developed.
- Using spinning or electro-hydro-forming (originals were spun).



High-luminosity LHC

the largest HEP accelerator in construction (1.2 km of LHC!)


High Luminosity LHC Project




The SRF part...

2 types of Crab cavities

Double Quarter Wave



RF Dipole









Voltage	3.4 MV/cavity
E_{peak}	40 MV/m
B_{peak}	70 mT
Frequency	400.79 MHz
Q_0	10^{10}
Q_{ext}	5×10^5
Cavity tuning	± 100 kHz
Temperature	2.0 K
RF power	40 kW

- 2 cavities/beam/IP side
- for ATLAS and CMS
- 16 cavities/8 CMs in total

2 types of Crab cavities

Double Quarter Wave


- Vertical crossing for Atlas
- SPS test in 2018



RF Dipole

- Horizontal crossing for CMS
- SPS test in 2021

SPS test stand layout



- Moving table can move the cavity in/out of the SPS beam in ~10 min.
- Test stand is foreseen for DQW and RFD.
- In Nov 2015 CERN in-sourced the DQW production
- Test stand will remain as a unique SRF test stand with proton beams at CERN.

Crab cavities: timeline


installation slots

2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026
	EYETS		EYETS							
Run 2			LS2		Run 3			LS3		Run 4
CM1 construction & SPS preparation		SPS test CM1	CM2 construction		SPS test CM2					
LHC pre-series (2 industrial dressed cavities)										
				LHC series production & installation (8 CMs)						

Last test opportunity before launch of series:


- ➔ First operation of crab cavities in high-current and high-energy proton machine. Mandatory test before LHC installation!
- ➔ Injection/capture/acceleration with crabs, can the cavities be made invincible for the beam (counter-phasing)?
- ➔ Precision control of voltage and phase for preservation of beam quality.
- ➔ Trip rate must not impact LHC availability.
- ➔ Emittance growth, machine protection, RF non-linearities, instabilities,

Final weld on DQW #1



Recent progress

Power coupler test box




Frequency tuning successful



He-tank thermal shock test



- Bulk 400 MHz Nb crab cavities & their cryomodules.
- Power couplers, HOM couplers, cavity control, operation with high-energy proton beam.
- Low trip rate mandatory!
- Industrialisation for small series (8 cavities intended from the US, 8 to be tendered by CERN).



Future Circular Collider Study

- CDR until 2019,
- In 2020 assessment by the European Strategy Group on the future physics roadmap.
- FCC-ee as potential first step
- FCC-he as option
- FCC-hh 100 TeV pp in 100 km
- Potential construction: 2025-2035

FCC options

parameter	FCC-ee				FCC-hh	
physics	Z	W	H	t	hh	
energy/beam [GeV]	45.6		80	120	175	50000
bunches/beam	30180	91500	5260	780	81	
bunch spacing [ns]	7.5	2.5	50	400	4000	25
bunch population [10^{11}]	1.0	0.33	0.6	0.8	1.7	1
beam current [mA]	1450	1450	152	30	6.6	500
luminosity [$10^{34}\text{cm}^{-2}\text{s}^{-1}$]	210	90	19	5.1	1.3	5-30
energy loss/turn [GeV]	0.03	0.03	0.33	1.67	7.55	
RF voltage [GV]	0.4	0.2	0.8	3.0	10	0.032

timeline:



FCC options

"high current" machine

parameter	FCC-ee					FCC-hh
	z	w	H	t	hh	
physics	z	w	H	t	hh	
energy/beam [GeV]	45.6	80	120	175	50000	
bunches/beam	30180	91500	5260	780	81	
bunch spacing [ns]	7.5	2.5	50	400	4000	
bunch population [10^{11}]	1.0	0.33	0.6	0.8	1.7	
beam current [mA]	1450	1450	152	30	6.6	
luminosity [$10^{34}\text{cm}^{-2}\text{s}^{-1}$]	210	90	19	5.1	1.3	
energy loss/turn [GeV]	0.03	0.03	0.33	1.67	7.55	
RF voltage [GV]	0.4	0.2	0.8	3.0	10	
					0.032	

timeline:



"high gradient" machine

cavity options (per beam)

parameter	FCC-ee								FCC-hh
	z		w	H		t		hh	
RF voltage [GV]	0.4	0.2	0.8	3.0		10		0.32	
Energy loss/turn [GeV]	0.03		0.33	1.67		7.5			
beam current [mA]	1450		152	30		6.6		500	
cavity technology	Nb/Cu		Nb/Cu	Nb	Nb/Cu	Nb	Nb/Cu	Nb	Nb/Cu
E_{acc} [MV/m]	10		10	20	10	20	10	20	10
frequency [MHz]	400		400	800	400	800	400	800	400
temperature [K]	4.5	4.5	4.5	2.0	4.5	2.0	4.5	2.0	4.5
Nb cavities	107	54	107	107	200	200	667	667	32
cells/cavity	1	1	2	2	4	4	4	4	1
P_{cavity}	462	924	470	470	251	251	75	75	<500

same cryomodule

both beams in same cavities

cavity options II

two different sets of cavities will be needed to cover all scenarios

“high current”
machine




- lower frequency, low N_{cells} , low R_s
- 400 MHz, Nb/Cu, < 100 cavities
- FPC: aim at 1 MW/cavity (movable for hh, fixed for ee)
- HOM power < 1.5 kW/cavity
- 1 RF source/cavity (e.g. high efficiency klystrons)
- CM design to accommodate 1-cell (W) and 2-cell cavities (Z, hh)

“high gradient”
machine




- optimise power consumption, multi-cell, high R_s
- 400 MHz (Nb/Cu) or 800 MHz (Nb), > 1000 cavities
- transverse impedance favours low frequency
- N_{cells} defined by beam-cavity interaction, for now assume 4/5
- 1 RF source/cavity: SSPA, IOT


SRF R&D for FCC



optimize cell shapes




beam dynamics studies




Q-slope mitigation




material & manufacturing




assembly & cost optimisation



ancillaries:
1 MW CW coupler!



efficient RF production



coated crab cavities

FCC

Thin film R&D


Overview

Coating methods



- **Diode coating** with bias for HIE-ISOLDE
- **Direct Current Magnetron Sputtering (DCMS)** for LHC cavities.
- Improved method: **Biased High Power Impulse Magnetron Sputtering (HiPIMS)**, more R&D needed.
- HiPIMS coating: 10 single cell 1.3 GHz cavities (from LNL) are being prepared to test coatings with different HiPIMS parameters.
- R&D on new coating cathodes (400 and 800 MHz).

Coatings types




- Crucial: R&D on **surface preparation** of Cu and Nb surfaces.
- Full **EP** of substrates, upgrade existing facility for 400 and 800 MHz Cu. 704 MHz multi-cell Nb was already done in a vertical set-up.
- > 30 coatings on seamless 6 GHz cavities with a few for application at 800 MHz (INFN, Italy).
- Microscopic and surface characterisation of samples at STFC (UK)
- Longer term effort: **A15 coatings**: Nb₃Sn at high-temperature (600-700 deg), annealed Cu, V₃Si
- More details in session 1 & 2 by Sarah Aull.
- 800 MHz bulk Nb used as state of the art comparison (JLAB collaboration).
- Collaboration agreement with FNAL in preparation on prospects of Nb₃Sn and nitrogen doping for bulk Nb 400-800 MHz cavities.

**Thin film
R&D**

Quadrupole resonator

Our tool to qualify SRF surfaces

Principle



- 4 rod transmission line half-wave resonator
- resonant frequencies: 400/800/1200 MHz
- pole shoes focus magnetic field on the sample
- thermally decoupled sample
- high-resolution calorimetric measurement of surface resistance

Activity

- Original QPR was built 20 years ago to measure samples for the LHC cavities.
- Since then it became a work-horse for CERN's coating qualification.
- HZB Berlin recently optimised and re-built the QPR (Niowave) and achieved 120 mT on the sample surface (see SRF 2015) for 433, 867, and 1300 MHz.
- CERN has further optimised the pole shoes and is building another device for 400, 800, and 1200.
- Machining starts early 2017, first tests foreseen in 2018.

FCC

Next generation Crab Cavity

Wide Open Waveguide cavity (WOW)

Why a Nb/Cu crab cavity?



- No thermal run-away (“natural” quench protection).
- Crab cavity power needs are driven by off-axis beam and not by surface losses.
- Lower cavity impedance (mandatory for FCC).
- No magnetic shield (cost, simplicity).
- Power coupler and HOM dampers can be outside of the helium tank (no feedthroughs).
- Cheaper base material (Cu), easier welds,
- Operation at 4.5 K.
- Mechanical stability (lower microphonics, easier RF stabilisation).
- Structure can be cascaded.

Wide Open Waveguide cavity


Basic parameters

electric

magnetic



Voltage	2.7 MV/cavity	80% of bulk Nb CC
E_{peak}	40.5 MV/m	same as bulk Nb CC
B_{peak}	70 mT	same as bulk Nb CC
Frequency	400.79 MHz	
Temperature	4.5 K	
P_{diss}	< 50 W	for LHC quality coating




electric

magnetic


Mechanical construction

Geometry optimised for coating



brazing
welding

- machined out of seamless tubes
- then welded & coated




welding

Status & timeline

- Copper is at CERN and qualified, welding tests done, handling and tooling concept is defined.
- Mechanical drawings ready, machining of prototype 1 is starting.
- Preliminary coupler design for vertical testing.
- LHC-style coating set-up (coating electrodes inserted in cavity) was chosen. Small modifications on existing set-up is needed.

2016				2017				2018				2019		
material procurement, drawings				fabrication 1st prototype										
							fabrication 2nd prototype							
				coating design & construction				coating, cold testing, re-coating						

Active power coupler R&D




HIE ISOLDE

- 4 CM with 5 low-beta QWR in each. 6 MV/m, $Q_{0,nom}=5 \times 10^8$
- Crisis in 2015, no one understood why linear indications (“microcracks”) appeared on the cavities and spoiled the performance.
- Strategy: i) shrink-fit and weld at CERN, ii) work on the welding parameters (already succeeded), iii) seamless cavities (under test).
- CM3 needs 70 W instead of 50 W, and there are good hopes that CM4 will be at nominal, allowing full-spec operation!
- In-situ helium processing works and provides a mechanism to save declining (dirty) cavities.
- First 2 physics runs successful.




in-situ Helium processing

CM1 CAV1



CM1 CAV5



Summary

- HIE ISOLDE low-beta QWR: 3 modules installed, 1 more to come. Potential to replace NC front-end with SC cavities in HIE-ISOLDE phase 3 (not funded/agreed today).
- LHC spare cavities.
- Crab cavities for HL-LHC.
- Focus on coated Cu cavities (not many alternatives for ≤ 400 MHz): Extensive Nb on Cu R&D program towards FCC, 400/800 MHz with modest gradients.
- Coated crab cavity for FCC.
- Short to medium term: focus on HIPIMS Nb/Cu. Construction of new QPR.
- Long term: A15 coatings on Cu.
- Bulk Nb: crab cavities for HL-LHC, modest effort on 704 MHz 4-cavity (5-cell) CM, 800 MHz for FCC (but also trials with Nb/Cu at 800 MHz). Reference for comparison coated cavities.
- Improved power couplers, aiming at 1 MW CW.

