What is the timeline and milestone path to a machine with films technology with E_{acc} >16 MV/m, and Q>1.5e¹⁰?

A perspective on Nb films on Cu cavities

- Basic material processes exist
 - proof-of-principle demonstrations for modest field applications
- Principal present challenges
 - Establish adequate process controls
 - Address technical challenges with scale-up
 - Though not fundamental, these require serious resource investment to establish "industrial" capability.
 - Half-hearted effort not worth doing, won't reach the goal. Resources drive the timeline.
- So, tool-up for the big cavities and refine process parameters in parallel on smaller scales.
- Done right, also a reasonable stepping stone to truly "engineered surface", with all the benefits of high Q, high field, low cost, and high reliability systems.



What is the timeline and milestone path to a machine with films technology with E_{acc} >16 MV/m, and Q>1.5e¹⁰?

Scale of efforts required for aggressive timeline for production readiness

- Build a dedicated UHV cavity coating system based on Nb Energetic condensation technology
- Coat cavities (1- & multi-cells):
 - > 1st cavity coated by end of 2018
 - Coating rate: 1.5 2 cavities/wk depending on frequency 100-150 coated cavity cycles
 - Tight coordination between substrate preparation, coating cycle and RF measurement (RF feedback needs to be timely, within 1 wk)
 - Specs [with E_{acc} >16 MV/m, and Q>1.5e¹⁰] consistently achieved by end of 2020
- Develop Cu cavity electropolishing facility in parallel with deposition system
- Film material analyses in parallel for process parameter guidance

Assumes personnel has EC Nb film coating , cavity coating & UHV proficient skills on day 1 Assumes prior investments in utilities & infrastructures already in place:


- ✓ RF testing facility (dewar, RF power...) able to accommodate up to 4-cell 400 MHz cavities
- Cooling water and power in coating facility
- HPWR and cleanroom infrastructures

Personnel:	5FTEs /yr. involving 7-8 scientists & professionals				
Graduate students:	2 FTEs/yr				
Dedicated cavity deposition system & ancillaries (portable cleanroom/substrate inspection): 470-570 K\$					
Cu cavity substrates (cost dependent on frequency) :	120 to 240 K\$				
Other direct expenses (supplies, machine shop, mate	erial analyses): 285 k\$				
Project duration 40 Mos.	Direct costs				




Focused Timeline

Assumes Nb film, cavity coating and UHV proficient skills available on day 1 Assumes adequate funding on day 1 for personnel and procurements



Alternate Timeline

Assumes Nb film, cavity coating and UHV proficient skills available on day 1 Half manpower & same procurements



A-M Valente-Feliciano, C Reece

Why energetic condensation?

interface


Enable excellent crystal structure for optimum RF performance


Interface Film nucleation

Sequential phases for film growth

- Growth of appropriate template for subsequent deposition
- Deposition of final surface optimized for minimum defect density.


Full control over final SRF performance with strict process protocols







Control over nucleation & subsequent growth, thus structure

Flux Penetration comparable to H_{c1} for bulk Nb





Why energetic condensation?




Existing Infrastructure

Location reserved for scale-up cavity deposition system

Present cavity HiPIMS system with LSF Cu cavity – Matt Burton's PhD thesis work

Timeline & Budget for Nb/Cu cavity development (based on 400 MHz)




400 MHZ cavity coating development : 40 Mos.	TOTAL		YEAR 1		YEAR 2		YEAR 3		YEAR 4	
SENIOR PERSONNEL	CAL		CAL		CAL		CAL		CAL	
Scientists	90.0	\$691,080	24.0	\$177,962	24.0	\$182,411	24.0	\$186,972	18.0	\$143,735
Senior Scientists	31.0	\$389,618	10.0	\$122,394	10.0	\$125,454	10.0	\$128,590	1.0	\$13,180
(3) TOTAL SENIOR PERSONNEL	121.0	\$1,080,698	34.0	\$300,356	34.0	\$307,865	34.0	\$315,562	19.0	\$156,915
OTHER PERSONNEL										
2 OTHER PROFESSIONAL (TECHNICIAN, DESIGNER, ETC.)	90.0	\$449,203	28.0	\$134,028	24.0	\$132,169	26.0	\$118,669	12.0	\$64,337
2 GRADUATE STUDENTS	96.00	\$216,000		\$54,000		\$54,000		\$54,000		\$54,000
TOTAL SALARIES AND WAGES (A+B)		\$1,745,901		\$488,385		\$494,034		\$488,230		\$275,252
FRINGE BENEFITS (IF CHARGED AS DIRECT COSTS)		\$914,881		\$259,762		\$263,141		\$259,670		\$132,309
TOTAL SALARIES, WAGES AND FRINGE BENEFITS	307.0	\$2,660,782		\$748,147		\$757,175		\$747,900		\$407,560
Cavity coating system		\$450,000		\$450,000						
Portable cleanroom		\$50,000		\$50,000						
Substrate Inspection		\$70,000		\$70,000						
400 MHz cav		\$240,000				\$240,000				
TOTAL PERMANENT EQUIPMENT		\$850,000		\$570,000		\$240,000		\$40,000		
TRAVEL		\$50,000		\$5,000		\$8,000		\$12,000		\$15,000
OTHER DIRECT COSTS										
MATERIALS AND SUPPLIES		\$100,000		\$50,000		\$20,000		\$20,000		\$10,000
CONSULTANT SERVICES		\$95,000		\$30,000		\$30,000		\$20,000		\$15,000
MACHINESHOP		\$90,000		\$50,000		\$10,000		\$15,000		\$15,000
TOTAL OTHER DIRECT COSTS		\$285,000		\$130,000		\$60,000		\$55,000		\$40,000
TOTAL DIRECT COSTS		\$3,845,782		\$1,453,147		\$1,065,175		\$854,900		\$462,560
TOTAL INDIRECT COSTS (~60%)		\$2,150,683		\$779,166		\$588,371		\$492,152		\$285,481
TOTAL COST OF PROJECT		\$5,996,465		\$2,232,312		\$1,653,546		\$1,347,052		\$748,041

A-M Valente-Feliciano, C Reece

Existing Infrastructure



ECR cavity deposition system Under design



A-M Valente-Feliciano, C Reece