

# Phase-I Upgrade of the CIVS pixel detector

Mia Liu Fermilab AEM Feb 20, 2017












- •
- **Crucial in tracking and vertex reconstruction**  $\bullet$
- instantaneous luminosity of 10<sup>^</sup>34 cm<sup>-2</sup> s<sup>-1</sup>






## The new phase 1 pixel detector

- Installation during extended year-end technical stop 2016/17 in Feb/March 2017.
- Compared to the current detector:
  - Similar sensor design, pixel size, module design concept.
    - Change from analog readout chip to digital readout chip (ROC) —> reduced buffer overflow and inefficiency, increase data transmission speed
  - Added layers, channels doubled, closer to beam
    - 3 to 4-hit coverage —> increase track finding efficiency
    - $\cdot$  Closer to the beam -> improve vertex reconstruction
  - Single-phase fluorocarbon (C6F14) to evaporative, bi-phase CO2 cooling: lower mass.






## Building the forward pixel detector at Fermilab(S











# Arrival at CERN



## Fermilab CERN

- **Detector re-assembled after** ullettransportation at CERN main site.
- **Detector tested/calibrated post-**● <sub>6</sub>transportation.



### • Very Tight schedule.

- First half cylinder arrived at CERN last September.
- All four half cylinders tested within three months.—> allow for repairs after Christmas.
- Checkout procedure shortened to less than one week.
- Lots of work getting the detector to function properly •

  - Exercised more advanced calibrations needed to have uniform response from all pixels.

## "PixelAlive" for One module, 16 Readout chips

Detector Checkout : Timing scan, adjust light level in optical fibers, adjust settings on the readout chip etc...

70

60

50

20

10



# Getting ready for collisions

## • Status as of today:

- All four half cylinders have been tested at CERN main site.
  - They were thoroughly tested at Fermilab before transported to CERN.
  - Three transported to CMS site, tested, ready for installation.
- Barrel part transported to CMS site, half of the barrel tested.
- More than 99% working channels •
- Installation in ~2 weeks! •
  - **Commissioning& calibration will follow** •
  - Need smooth transition from installation to physics data taking. •
- Expecting LHC proton-proton beam for physics in June.
  - New detector is getting ready to see tracks for the first time!