

# ProtoDUNE-SP Construction Status

Gina Rameika  
LBNC Meeting  
March 23 – 25, 2017

# Outline

- Detector Overview
- Design and Construction Status
- Time Projection Chamber
  - Cathode/Field Cage /High Voltage
  - Anode Plane Assemblies
  - Front-end Amplifiers and Digitization
- Photon Detectors and Readout
- Prototyping and Installation Planning
  - High Voltage testing at PC4 (35-ton)
  - Full scale integration testing at Ash River
  - Electronics test stations at FNAL and BNL
- Summary

Watch my expression



Under control



New, unknown



Concern



# Major Milestones

**Q3/2016:** design reviews for ProtoDUNE-SP  (complete Q4/2016)

**Q3/2016:** TDR for ProtoDUNE-SP 

BNL Cold Electronics Integration Test-stand Operational : 3/8/17 

Submission of Production FEMB Fabrication : 4/19/17 on track

35ton HV Test (Phase 1) Complete : 5/3/17 on track

First 10 PD modules ready to ship to CERN : 5/9/17 will be @ CERN when needed

Ship APA#1 Electronics to CERN : 5/24/17

Ash River Trial Assembly Complete : 6/9/17 on track

**PSL APA #1 Arrives @ CERN : 6/9/17 pushing very hard to keep to this date**

PSL APA #2 Arrives @ CERN : 9/8/17

UK APA#1 Arrives @ CERN : 9/18/17

Decision to fabricate APA #7 : 8/18/17

35ton HV Test (Phase 2) Complete : 8/24/17

PSL APA #3 Arrives @ CERN: 11/9/17


UK APA #2 Arrives @ CERN : 11/27/17

UK APA #3 Arrives @ CERN : 1/19/18

# Main Goals of ProtoDUNE-SP

- In progress
- Engineering validation of the full-scale DUNE detector components
  - Develop the construction and quality control process
  - Validate the interfaces between the detector elements and identify any revisions needed in the final design
- Validate the detector operation using cosmic rays
  - Study the detector response to known charged particles
  - Improve event reconstruction and detector response models

DUNE Dimensions




# PD-SP Detector Overview

Main Detector Elements include :  
Time Projection Chamber (TPC) ,  
Front-end and digitizing electronics, a  
Photon Detector System (PDS) and  
Data Acquisition (DAQ)

Prototype of the single phase DUNE far detector. Full scale modules, but only half height of DUNE FD (single layer of APAs).

TPC has 6 units of anode wire planes (APAs), a high voltage cathode plane (18 “units”), 28 field cage modules, 15K readout channels

Dimensions - W: 3.6m (x2), H: 6m,  
L (along beam direction) : 7m ; 300  
ton active mass



# Detector Elements – a modular approach

Table 2.1: TPC detection components, dimensions and quantities

| Detection Element  | Approx Dimensions            | Quantity                                                       |
|--------------------|------------------------------|----------------------------------------------------------------|
| APA                | 6 m H by 2.4 m W             | 3 per anode plane, 6 total                                     |
| CPA module         | 2 m H by 1.2 m W             | 3 per CPA column,<br>18 total in cathode plane                 |
| Top FC module      | 2.4 m W by 3.6 m along drift | 3 per top FC assembly, 6 total                                 |
| Bottom FC module   | 2.4 m W by 3.6 m along drift | 3 per bottom FC assembly, 6 total                              |
| End-wall FC module | 1.5 m H by 3.6 m along drift | 4 per end-wall assembly (vertical drift volume edge), 16 total |
| PD module          | 2.2 m × 86 mm × 6 mm         | 10 per APA, 60 total                                           |

From ProtoDUNE Technical Design Report

This modular approach to detector construction enables the construction of detector elements to take place in parallel and at multiple sites.

This will be an essential approach for the DUNE Far Detector.



# Design Evolution from previous LArTPC Field Cages




“Racetrack” Field Cage with metallic cathode

- not easily scalable
- tremendous stored energy




New design

# HV Bus distribution to cathode plane



A HV bus cable to distributes the cathode voltage to all of the cathode panels






## Two new elements of the TPC design

### Resistive Cathode CERN, BNL

- At full voltage (180kV) there is almost 100J of energy stored in the cathode plane
- In the event of a discharge from a cathode edge to the cryostat wall, there is a risk of physical damage to either the cathode or the membrane wall; the voltage on the an all metal cathode will collapse very quickly, injecting high current into the cold electronics, through the APA wires, risking damage to the front end ASICs
- To mitigate this risk a new all resistive cathode has been developed using a commercial resistive film
- Several types of resistive surfaces have been investigated and the preferred solution is Dupont Kapton film laminated on FR4 substrate

### Modular Field Cage

- A new design of a modular field cage using extruded, open aluminum profiles held together by pultruded fiberglass beams has been developed
  - Panels are of manageable size and weight
  - Each panel has its own resistor chain to degrade the voltage and is electrically insulated from the adjacent panels which will minimize the peak energy dump in case of sparks



Stony Brook,  
Louisiana State,  
William & Mary,  
CERN



# Cathode Plane (CPA)

Argonne National Lab,  
BNL, CERN



18 individual “panels” assembled into units of 3 and assemblies of 2 panels; 3 total panels needed







# Field Cage Module Construction

## Top and Bottom

Stony Brook University



Need 12 of these  
6-top, 6-bottom



58 profiles in each module;  
Profiles being procured by CERN and  
will be installed at CERN in the summer;


CERN, William & Mary

## Endwalls

Louisiana State University



Need 16 of these  
8 upstream  
8 downstream  
(1 us has the beam plug)







# Field Cage Resistor Divider Boards

Create the field gradient (500V/cm nominal)  
from the cathode to the anode plane

Louisiana State University



3 varistors  
2 1GOhm resistors  
per connection

RD: SM104FE-1000M, MOV: ERZ-V14D182

One board connects 8 field cage profiles  
Need 7 of these per field cage module -> 196 total boards needed  
Will be installed on the field cage profiles at CERN



## Ground Planes



CERN

The purpose of the ground plane above the field cage is to shield the fringe field created by the CPA/FC from entering the gas ullage and cause breakdown


The ground planes are stamped from 1 mm thick stainless steel

The ground plane on each T/B field cage panel is composed of 5 panels.

Since the top and bottom field cages are designed to be symmetric, there is a ground plane by default on the bottom.



# CPA-FC Assemblies



Each composed of a

- CPA (2 columns, 6 units)
- 4 Field Cage Modules (w Ground Planes)
  - Beam Right
    - Top and Bottom
  - Beam Left
    - Top and Bottom

Units are assemble outside of the cryostat and moved into the cryostat through the TCO


Need 3 Assembled Units :

- Upstream
- Midstream
- Downstream





# Anode Plane Assemblies (APA)



PD-SP will have 6 APAs

Each APA : 960 X, 800 V, 800 U,  
960 G (un-instrumented) wires

10 Photon Detectors are  
installed into each APA frame

# APA Construction at UW-PSL and Daresbury, UK




UW - PSL  
X-plane wires  
complete;  
U-plane  
wire winding in  
progress

US APAs (1-3)  
UW-PSL – Lead Lab  
QA/QC support from  
Syracuse  
UT-Arlington  
Yale



schedule





U.K. winder under  
construction at  
Daresbury

1<sup>st</sup> frame under  
construction


UK APAs (4–6)  
Daresbury  
Manchester,  
Lancaster,  
Sheffield,  
Liverpool

# TPC Readout – Cold Electronics with a warm interface

Integral  
APA+CE  
Concept





Keep eye on  
schedule for  
delivery and  
testing of  
ASICs and  
FEMBs



*ProtoDUNE-SP*

Cold electronics module and its  
attachment to the APA frame



- BNL - lead
- UC Davis
- Boston
- Michigan State
- U Penn
- LSU
- U of Florida
- Fermilab

10/12/2016

H. Chen - Cold Electronics Review



23

# Detector Support Structure




Design,  
schedule

Looks simple, but is a complicated structure which needs to support and enable positioning of the components during installation as well as in final position



Only three bridge beams are shown. Five will be used for installation.



Custom trolley design to enable positioning the elements



# Full Scale Trial Assembly at Ash River



New,  
Not exactly  
same as CERN



1/6 mock-up of PD  
Learn how to deploy field cages  
Latch into place  
Develop installation procedures –  
including ES&H + QC










# Developing installation tooling and procedures



Note – lifting devices and fixtures NEED TO BE REMOVED after construction is complete



# High Voltage System






CERN, FNAL, BNL, Kansas State,  
U of Houston, UC Davis



# Photon Detection System

Indiana, FNAL, MIT, Northern Illinois,  
Caltech, Colorado State, ANL, UNICAMP

10 Photon Detector bars per  
APA -> 60 total bars needed  
3 types of “bars” being  
tested and fabricated







# SiPM Readout

Each bar read out by an array of 12 SiPMs -> 720 SiPMs needed




- Signals go into a 12 channel waveform digitizer with a 14-bit 150MSPS ADC




## I-V curves warm and cold



## Mounting machine at CSU



But indications that they are generally OK when properly mounted





Recent damage on a new batch  
Not rated for cryogenic operation; but OK experience up until now

# Small field cage test

CERN

Designed to fit in the ICARUS 50 liter cryostat  
Roll-formed Al and SS profiles with UHMW PE caps  
All profiles a same potential  
Applied -100kV without discharge




# CPA/FC/HV test setup

Fermilab, ANL, BNL, William & Mary, Kansas State, LSU,  
UC Davis, University of Houston



- This setup will be able to test the following features at full scale for E field purpose:
  - CPA lifting fixture
  - Ground plane
  - Ground plane overhang
  - Field cage support structure
  - CPA edges
  - **Field cage profiles**
  - Profile caps
  - End wall FC box beams
  - HV cup

In the 35 ton facility at FNAL




- **Aluminum profiles with conductive coating have now mounted in the Field Cage panels:**

37




# High Voltage Test at the 35t



Instrumented with cameras and PMTs  
Monitoring current draw as voltage is ramped up  
Have ramped to 40kV in air with no sign of breakdown

Status :  
Cool down  
Filling  
Ramp to voltage  
Purify  
Ramp to voltage





# Electronics Testing – FNAL and BNL





## FNAL

- RF Shielded room with isolation transformer
- Warm test
- Will test full electronics chain (with small APA)


## BNL

- Cold test (LN2)
- Also tests full chain with “40%” APA





# What we need to accomplish this year



# Risk Updates

- Held a PD-SP Risk Workshop in early February
- Re-evaluated risks to protoDUNE-SP
  - 13 in Construction phase
  - 10 in Installation phase
  - 6 in Operations phase
  - 1 in Analysis phase
- Highest ranked risks
  - Schedule
    - APA delivery
    - Cold Electronics delivery
  - High Voltage
- Update :
  - closed 1 (FC production sites are ready)
  - realized 2 (APA behind schedule, SiPM yield unknown)

# Response to LBNC Recommendations

| Review Date | Item Description                                                                                                                                                                                 | Due Date  | Status     | Actions                                                                                                                 |
|-------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|------------|-------------------------------------------------------------------------------------------------------------------------|
| 12-Jun-16   | Work with the funding agencies, including DOE, to make sure support for operations and the hiring of key personnel is realized in a timely fashion                                               | 1-Jun-17  | in process | This has been highlighted at visits DOE in Germantown. Discussions with DOE continue. Fermilab have provided key hires. |
| 23-Oct-16   | The collaboration should review the goals of the test beam run taking into account the trade-off between meeting the current schedule versus the risk of the detector not performing as required | 19-May-17 | in process | A list of deliverables was provided to the DOE IPR March 1, 2017.                                                       |
| 23-Oct-16   | At the next LBNC, present the response plan from the Final Design Reviews and their outcomes                                                                                                     | 23-Mar-17 | in process | Yes. We will. (Need high level response based on individual L3 responses)                                               |
| 23-Oct-16   | Investigation of the variable high frequency noise problem should continue to be pursued with high priority to understand the root cause, which may not reside in the LV power supply.           | 22-Jun-17 | in process | This is ongoing at both the FNAL screen room facility and the BNL cold 40% APA test stand.                              |

# Summary

- All detector elements are either in production or nearly ready to start (final versions of 1<sup>st</sup> elements)
- Most significant issue is meeting the schedule
  - Currently we have challenges in delivery of DSS, APAs and Cold Electronics
  - All equipment delivered to CERN needs to have acceptance reviews for safety before it can be installed
- Significant effort is going into the trial assembly so that the installation phase at CERN is efficient