

ANALYSIS AND OPERATIONAL FEEDBACK ON THE CURRENT HIGH ENERGY BEAM DUMP IN THE CERN SPS

Antonio Perillo-Marcone

On behalf of the TIDVG#4 team



ENGINEERING
DEPARTMENT


7th High Power Targetry Workshop
June 4-8, 2018

Contents

- Introduction of the SPS beam dump (TIDVG)
- Design
- Material selection
- Assembly and installation
- Operational feedback
- Conclusions

Introduction of the SPS beam dump

CERN's Accelerator Complex





Two beam dumps in the SPS:

- **TIDH** (Target Internal Dump Horizontal): <28 GeV
- **TIDVG** (Target Internal Dump Vertical Graphite): 105-450 GeV
 - Total length 4.3 m, 30 cm core diameter
 - Internal dump (in UHV)

Beam dilution on dump

- In order to avoid damaging the absorbing material, the beam is diluted over $\sim 7.2 \mu\text{s}$ (for LHC beams)
- Asymmetry in the energy deposition in the dump induced by the position of the device with respect to the injected beam



Injected beam Circulating beam



Current SPS beam dump – TIDVG#4

Installed in March 2017


Cast iron blocks (EN-GJL-200)
with embedded stainless steel
tubes



Cooling circuit of the
upper half yoke

Cooling circuit of the
bottom half yoke

Dump inside vacuum chamber
(SS 316L seamless tube)




Absorbing blocks

Tungsten block (40 cm)

CuCr1Zr block (40 cm)


C18150

Graphite blocks (350 cm)



CuCr1Zr block integrated
into core. A perfect
thermal conductivity is
achieved (no interface)

Copper core cooling system:




OUTLET

INPUT

2xSS tubes
in the upper
Cu half

2xSS tubes
in the bottom
Cu half



- Limited time window:
 - Faster manufacturer
 - Use of known technologies. No R&D

- T sensors on all the parts (18 in total)
- T sensors for the water +1 flow meter
- Copper core made of CuCr1Zr

Material selection for TIDVG#4

General material requirements for the SPS beam dump design

- **Good thermal and mechanical properties**
 - High power to be dissipated and high stresses due to the beam impact
- Materials available in needed quantities, sizes and easy to machine + delivery
- **UHV compatibility**
- **Avoid Al as absorbing block** (molten in previous design)

Component	CERN specifications	Additional treatments applied
Graphite	Isotropic properties Grade with proven high thermal shock resistance	Machined without lubricants Purified in Ar @ $T > 2000^{\circ}\text{C}$ Vacuum fired @ 950°C at CERN
Tungsten alloy	Density, mechanical properties, machinability	Degreased at CERN Vacuum fired @ 950°C at CERN
CuCrZr	Homogeneity / 3D forged	Degreased at CERN
Tube for vacuum chamber	Homogeneity + small grain size 3D forged 316L as per CERN spec. Seamless	Degreased at CERN

Current SPS beam dump – TIDVG#4

Forging of SS vacuum chamber



SS vacuum chamber




Vacuum firing of the Gr blocks

Tungsten alloy



CuCrZr core



Current SPS beam dump – TIDVG#4


Graphite inside the
CuCrZr core



Medium/high-Z absorber



TIDVG#4 core fully assembled and
ready for insertion in the vacuum
tube




TIDVG#4 core being pulled
into the vacuum chamber




TIDVG#4 core fully
inserted (upstream)

Final leak detection
(upstream/ water manifolds)




Current TIDVG#4 Installation

Installation during EYETS 2017 (March)



Operational feedback for TIDVG#4

Performance monitoring



P-VACUUM-VGHB11860 (mbar)	7.00e-8
P-VACUUM-VGHB11879 (mbar)	1.90e-7
P-VACUUM-VGHB11931 (mbar)	1.10e-8

P-VACUUM-VGHB11936 (mbar)	1.60e-9
P-VACUUM-VGHB11952 (mbar)	6.00e-9
P-VACUUM-VGHB11959 (mbar)	1.80e-8


Beam intensity: 7.63e+11 charges

Beam energy: 4.00e+2 GeV

Average beam power over last 10 mins: 4.27e+1 kW

Average beam power over last 10 SC: 4.83e+1 kW


Average beam power over last hour: 1.88e+1 kW



Gr583-RD


14 PT100 installed in the dump core
(2 PT100 were damaged during assembly)

Operational feedback for TIDVG#4



4 PT100 on the SS vacuum chamber
2 PT100 on the shielding

Operational feedback for TIDVG#4



Sensors located in the water:

- 2 flow-switches
- 4 PT100 in the water
- 1 water flow sensor (water flow and outlet T)

Operational feedback for TIDVG#4


Beam Type	p GeV/c	Bunch Intensity (protons)	# Bunches	Total Intensity (protons)	Continuous beam dump	Average power (kW)
LHC	440	$1.10 \cdot 10^{11}$	48	$5.3 \cdot 10^{12}$	2h30	9
LHC	440	$1.25 \cdot 10^{11}$	72	$9.0 \cdot 10^{12}$	4h00	16
LHC	440	$1.10 \cdot 10^{11}$	144	$1.6 \cdot 10^{13}$	3h00	27
LHC	440	$1.10 \cdot 10^{11}$	288	$3.2 \cdot 10^{13}$	1h30	55

- Dedicated **commissioning beams** have been requested in order to validate the performances of the dump (simulation cross-check) as well as to condition graphite
- TIDVG4 can operate safely under continuous average beam power of **~60 kW**

Operational feedback for TIDVG#4





Behavior under 48b beam

TIDVG.11892:TEMP_C1519_LD TIDVG.11892:TEMP_C1519_RD TIDVG.11892:TEMP_C1619_RU TIDVG.11892:TEMP_CU3699_LD TIDVG.11892:TEMP_CU3699_RD TIDVG.11892:TEMP_GR1749_RD TIDVG.11892:TEMP_GR2915_LD
TIDVG.11892:TEMP_GR2915_RD TIDVG.11892:TEMP_GR583_LD TIDVG.11892:TEMP_GR583_RD TIDVG.11892:TEMP_SS1000_D TIDVG.11892:TEMP_SS1000_U TIDVG.11892:TEMP_SS2500_D TIDVG.11892:TEMP_SS2500_U
TIDVG.11892:TEMP_W4100_LD TIDVG.11892:TEMP_W4100_RD





2h30 hours of continuous dumping



Operational feedback for TIDVG#4



Operational feedback for TIDVG#4




Good agreement (within ~25%)




Operational feedback for TIDVG#4


~Steady state at **144 bunches** (27 kW deposited)




Simulation for **27 kW**
 (144 bunches x $1.1 \cdot 10^{11}$)
 $I_{\text{total}} = 1.6 \cdot 10^{13}$



288 bunches (1h30– 55 kW deposited)



Simulation for **56 kW**
 (288 bunches x $1.1 \cdot 10^{11}$)



Conclusions

- The SPS beam dump (TIDVG) is a critical component of the CERN's accelerator complex
- TIDVG#4 successfully installed and operational according to the project schedule
- Good vacuum performance with a fast conditioning observed
- Good thermal performance (tested for high power beams)
- Longitudinal welds along the core were avoided (using a seamless vacuum chamber)
- Design features tested in TIDVG#4 to be implemented in TIDVG#5, to be installed in 2020 (details in poster presented here)
- Numerical model validated and able to predict dump performance
- No significant degradation observed after 1 year of operation



ENGINEERING
DEPARTMENT

Thank you for your attention.

Do you have any questions?

Acknowledgements: J. A. Briz, K. Cornelis, M. Calviani, R. Esposito, S. Gilardoni, B. Goddard, J.L. Grenard, D. Grenier, M. Grieco, J. Humbert, V. Kain, F. Leaux, S. De Man, C. Pasquino, J. R. Poujol, P. Rios-Rodriguez, S. Sgobba, D. Steyaert, F. M. Velotti, V. Vlachoudis