


Update on Radioactive Sources in DUNE

Juergen Reichenbacher & Jason Stock




**DUNE Calibration Task Force
Phone Meeting, 19-Oct-2017**

Re-iterate 16 Penetration Positions in Alternate Scheme



- A ^{58}Ni - ^{252}Cf source will emit 8-9 MeV gammas which are in the right range for calibration the energy response in the SN region. As absolute energy calibrations would otherwise be difficult this capacity should be foreseen.
 - A Ni source will probably need $\sim 100\text{mm}$ space including N moderator.
- Dynamic T-gradient monitors should also be foreseen at the detector ends and it is reasonable to combine these functions in single larger penetrations. Assume a 250 mm crossing tube.
- 16 penetrations total. 8 roughly centered in each TPC drift and 8 at the ends of the detector. The penetrations at the ends should not be more than 0.5m from the field cage but sufficiently far away not to risk the field.
 - Need to check rate when a natural position is determined.

External radioactive source deployments



TRI-PP-96-7
Apr 1996

A 7-9 MeV isotopic gamma ray source for detector testing


Joel G. Rogers^a, Mark S. Andreaco^b, and Christian Moisan^{*}

^aTRIUMF, 4004 Wesbrook Mall, Vancouver, B.C., Canada V6T 2A9

^bCTI, 810 Innovation Drive, Knoxville, TN 37932, U.S.A.



smaller design with Cf-252



0 10cm
scale

Table 1 - Thermal (n,γ) Rates from natural Ni taken from ref. [3]


Gamma Energy (MeV)	Rate (photons/100 captures)
8.997	26
8.532	11
8.119	2.5
7.817	6
7.528	4
7.22	0.4
7.05	0.6
6.839	9
6.58	2
6.34	1
6.10	1.3
5.99	0.4
5.82	3
5.70	0.6
5.31	1.3

[3] E. Troubetzkoy and H. Goldstein, "A compilation of information on gamma ray spectra resulting from thermal neutron capture", USAEC Report, ORNL-2904 Oak Ridge National Laboratory, 1960.


Using Cf-252 (or even better AmLi) would significantly reduce size of source, such that it would fit a 20 cm diameter feedthru

Safety distance of deployed radioactive source wrt. FC

$$318.66 \text{ mm} - (250 \text{ mm diameter} / 2) + \sim 80 \text{ mm shrinkage} = 273.66 \text{ mm}$$



Double Chooz Calibration Deployment System inside Glove Box:



**Automated fishline system
for target deployments:**


+/-2 mm precision over 7 m

**-> 2 systems available
in Jan 2018**


radioactive source





Blue Laser



UV Laser



UV Laser w/ hat



Oct 19, 2017

J. Reichenbacher (SDSM&T)


Simulation of 9 MeV gamma's in LAr

charge


Source at half-drift

light


Charge Collected (8.997MeV γ X2000)




PEs Detected (8.997MeV γ X2000)




Single event







Single event



Single event




Simulation of 9 MeV gamma's in LAr











About 10% of vertices in outliers

Drift velocity vs E-field




Do we really achieve our HV goal and e-lifetime?

Scenarios



Feedthru Options

Main question: How to arrange the 4 or 6 ports in the central region?





Laser has a lot on the flange, so this could mean

- So, we maybe looking at using cameras/radioactive source during commissioning as needed
- Then Laser takes over these shared ports after that? (except for the ones outside the FC)

Is this reasonable?

Feedthru Options

Main question: How to arrange the 4 or 6 ports in the central region?



Laser has a lot on the flange, so this could mean

- So, we maybe looking at using cameras/radioactive source during commissioning as needed
- Then Laser takes over these shared ports after that? (except for the ones outside the FC)

Is this reasonable?

More reasonable with only 4 FTs in central columns but all at half-drift?

Deployment Plan

1. Dummy source deployment (within 2 months of the commissioning)
2. Present to TB on the dummy source deployment and get sign off/green light for the real source deployment (1 to 2 weeks)
3. First real source deployment (within 3-4 months of the commissioning)
4. Second real source deployment (within 6 months of the commissioning)
5. Assuming things will be reasonably stable, radioactive source will be deployed every half a year. Ideally, a deployment before a run period and after the run period are desired so you have at least two data points for calibration. This is important since you need to know if the state of the system has changed before and after the physics data run.
6. If stability fluctuates due to electronics changes at a particular location, one would want to deploy the source at that location once a month or more often depending on how bad the stability is.

In terms of how long it takes to deploy:

1. few hours (e.g. 8 hours -> one work day u/g) for one FT position
2. parallel deployment (one port to another) takes 2 days or so.
3. Full calibration campaign (with only one shared system) — at least a week.