


Managed by Fermi Research Alliance, LLC for the U.S. Department of Energy Office of Science

# Fundamental Couplers for PIP-II, design and operation experience.

Sergey Kazakov, Cryomodule Workshop September 7, 2018, BARC, Mumbai, India

#### **PIP-II project:**

Perfomance Parameter	Value	Unit
Paticle species	H	
Linac Beam Energy	800	MeV
Linac Beam Current	2	mA
Linac Pulse Length	0.55 - CW	ms
Linac Pulse Repetition Rate	20 - CW	Hz



9/2/2018

- Room temperature cavities:
  - RFQ.
  - Bunching cavities (4 pc).
- 5 types of superconductive cavities:
  - Half Wave Resonators, HWR (8 pc).
  - Superconductive Spoke Resonator 1, SSR1 (16 pc).
  - Superconductive Spoke Resonator 2, SSR2 (35 pc).
  - Low Beta 650 MHz Cavity, LB 650 (33 pc).
  - High Beta 650 MHz Cavity, HB 650 (24 pc).

#### Total number of couplers: 122.

#### Requirements to couplers:

(Requirements meets <u>CW</u> version of PIP-II with <u>5 mA</u> current. Requirements are revised now for 2 mA version.)

#### **RFQ coupler:**

Frequency162.5 MHzPower75 kW, CW

#### **Bunching coupler:**

Frequency162.5 MHzPower3 kW, CW

#### HWR coupler:

Frequency 162.5 MHz Power 10 kW, CW

#### SSR1 & SSR2 coupler:

Frequency 325 MHz Power 30 kW, CW

#### LB & HB 650 coupler:


Frequency650 MHzPower110 kW, CW

🛟 Fermilab

9/2/2018

# All couplers were designed and all, except 650 MHz couplers, were built and tested.

#### Power consumption of the cavities at 2 mA in the nominal regime.




# **Principles of design:**


- Simplicity of vacuum part of coupler: no moving parts, no bellows. simple configuration – more reliable, easy to clean, less expansive.
- Air cooling of antennas (no water) Not so severe consequences in case of leak.
- Ability to apply high voltage bias to suppress a multipactor.
- Avoid a copper coating of stainless steel.



### 162.5 MHz RFQ coupler, logic of configuration



# 162.5 MHz RFQ coupler




8 S. Kazakov | Fundsmental couplers for PIP-II. BARC, Mumbai.

9/2/2018

**‡** Fermilab

#### 162.5 MHz RFQ coupler




Two coupler and four windows unit were produced.

Two windows failed after ~ 500 h work in CW mode.



Windows with replaceable ceramic and Viton O-rings were designed.



Diameter of ceramics was increased up to 6".

In case of broken window (broken ceramics), the ceramics can be replace easily (and one order less expensive).


We have 8 spare ceramic disk on the shelf.



#### 162.5 MHz RFQ coupler











11 S. Kazakov | Fundsmental couplers for PIP-II. BARC, Mumbai. 9/2/2018

We hope we solved the problem with RFQ couplers. Ceramics is large, stresses are small. Multipactor is suppressed by HV bias.


#### **Couplers works already more then 8 months in CW mode.**



Design power: 30 kW, CW, full reflection

#### **RF Window:**

Single, room temperature, alumina, OD 73mm (2.87"), ID 12.7mm (0.5"), thick. 6mm (.236")



Antenna: Copper 0.5", air cooled, HV bias.

#### Outer conductor:

SS, ID 73mm (2.78"), 0.4mm wall thickness, no Cu coating.

# Thermal properties of coupler (without thermal radiation of antenna):

P, kW	"2K ", W	"5K", W	"70K", W
0	0.07	0.35	1.9
10	0.20	0.62	4.6
20	0.33	0.89	5.7




#### **Current** status

- Couplers were successfully tested up to 30 kW, CW, full reflection, 90 dgr. step reflection phase.
- Couplers were tested up to failure. Window was destroyed at 47 KW, CW, full reflection.
- 11 antenna with windows were produced by CPI.
- 1 antenna with windows was produced by CoorsTek, 4 are under production
- 6 cavity were qualified with couplers (ready to be installed to cryomodule).
  Additional 2 cavity will be qualified soon.




#### Each ceramic disk is measured before to be brazed.





#### **CoorsTek ceramic measurements, F ~ 2.7 GHz**



#### Some times ceramics is extremely good: loss tangent ~ 1.5E-5 at 2.7 GHZ


🛟 Fermilab


9/2/2018



#### Antenna made by CPI







S. Kazakov | Fundsmental couplers for PIP-II. BARC, Mumbai.


9/2/2018

17

#### **Coupler qualification:**

Each couplers (each pair of couplers) is qualified at test stand.

Qualification: running coupler at full reflection mode, CW, at qualification power level for ~ 2 hours at each reflecting phase point. It is 4 phase point with 90 dgr. steps. Total time ~ 8 hours. Qualification power depends on operating power. It is still debated how much it shall be. Qualification is not conditioning. After qualification the couplers are re-cleaned and installed to cavity without conditioning. Really, the couplers do not require a conditioning. HV bias suppresses any activity.



🛛 🛟 Fermilab

#### 18 S. Kazakov | Fundsmental couplers for PIP-II. BARC, Mumbai.


9/2/2018

#### **Problem and issues with current design:**

 Wall thickness of vacuum outer conductor is rather small, 0.4 mm. It is causes difficulties for handling. The wall thickness is increased up to 0.8 mm.



#### LB & HB coupler, new design




Fermilab

9/2/2018




# LB & HB coupler, backup design





#### Vacuum part of coupler, new design



9/2/2018

# Thermal properties of 650 MHz couplers

	2K, W	5K, W	70K, W	293K, W
New, 0 kW	0.15	0.6	3.3	-2.7
New, 100 kW	0.55	0.93	6.2	21
Bckp, 0 kW	0.41	1.46	3.0	-3.1
Bckp, 100 kW	0.97	4.1	11.4	20

#### 100 kW:

New = 0.55\*960 + 0.93\*220 + 6.2\*20 = 857 W of cryo-plant Bckp = 0.97\*960 + 4.1\*220 + 11.4\*20 = 2061 W of cryo-plant

New design requires ~ 2.4 times less power of cryo-plant.

🛟 Fermilab

9/2/2018

#### **Current** status

- Two coupler prototypes with four vacuum parts are under production.
- Four vacuum parts are already made by CPI.
- Test infrastructure is under constriction.











24 S. Kazakov | Fundsmental couplers for PIP-II. BARC, Mumbai.

9/2/2018


### **Couplers test bench.**





Couplers will be tested in resonance mode with full reflected power. It will allow to increase the level of testing power more then 100 kW using 30 kW RF source.





**‡** Fermilab

9/2/2018

After the test couplers will be re-cleaned.

Current status.

Two vacuum parts of new design and two vacuum parts of backup design are produced by CPI.

Air parts of couplers are under production.

Test facility is under development.

First high power run is planned to be performed on December 2018.




#### Good news:

We verified the approach (with electromagnetic shields) at 1.3 GHz coupler prototype. 1.3 GHz coupler with configuration similar to 650 MHz coupler (scaled) was successfully tested,



#### **1.3 GHz prototype coupler was successfully tested in last week.**



#### Design is similar to 650 MHz coupler design.

29 S. Kazakov | Fundsmental couplers for PIP-II. BARC, Mumbai.

# Coupler at test stand Matched load

**RF vacuum window** 

Coupler

Test results:

Coupler was tested in pulse and CW modes. + 3kV bias was applied in all tests.

- In pulse mode the coupler was tested up to 15 kW/ 10ms only.
  RF source (IOT) was not stable in pulse mode.
- There was no sign of any vacuum activity (no evidences of multipactor) during the pulse mode test. Vacuum level was ~ 2E-8 Torr.

Other test were in CW mode.

- Maximum power 27 kW, CW, TW was reached.
- Power level was limited by RF source (IOT).
- Time was limited by temperature (vacuum level) of waveguide RF window. Window became hot and vacuum level reached upper limit 1E-6 Torr.




Power	Time
27 kW	~ 14min
20 kW	~ 1 hour
15 kW	~ ∞

#### **Conclusion:**

New configuration works:

- No multipactor in slots, no multipactor in SS chambers.
- No other vacuum activities.





MP is suppressed by HV bias

33 S. Kazakov | Fundsmental couplers for PIP-II. BARC, Mumbai.

9/2/2018

**‡**Fermilab