DAQ and Slow Control Commissioning

Angela Fava (FNAL), Wes Ketchum (FNAL), <u>Yun-Tse Tsai</u> (<u>SLAC</u>) ICARUS Collaboration Meeting September 19th, 2018

DAQ and Slow Control



The Overall Guidance

- May 2019: ICARUS ready to fill LAr
 - DAQ has to be capable of measuring noise level
 - Slow control hardware interface ready
- Fall 2019: ICARUS ready for beam neutrino data
 - Full DAQ operation
 - Full slow control and monitors operation
- Aim to have full DAQ and slow control system commissioned in summer 2019

Milestone December 2018

• Servers:

- All EVB (event building) computers will be ready
- One or two servers for TPC data will be ready
- Readout: Run TPC+PMT DAQ with one crate at ICARUS building
 - Plan B: Run TPC+PMT DAQ at the test stand
- Trigger: Inject external triggers
- Logging: Identify specifications of the event-by-event database

Milestone March 2019

- Readout: Demonstrate readout, synchronization, and event building at the detector scale
- Trigger: Specify the interface between DAQ and trigger
- Monitoring/Control:
 - Operational and slow control monitors set up
 - Initiate implementation of online data quality monitoring
 - Complete the development of ICARUS-specific slow control hardware interfaces
 - CSS infrastructure (slow control GUI) ready

Milestone March 2019

- Logging:
 - Implement event-by-event database and test performance
 - Initiate implementation of configuration database
 - Update DAQ process management tools and logging
 - Slow control archiver ready
- Data management: Initiate implementation (data transfer) and test
- Management: Define people and tasks required for commissioning

Milestone June 2019

- Readout: Full-scale detector tests
- Trigger: Full trigger implementation
- Monitor/Control:
 - White rabbit and timing (GPS) monitoring tools available
 - Initial version of a stable run control ready
- Logging: Offline archive of DAQ configuration database
- Data management: Throughput tests
- Management: Commissioning documentation ready

Data Acquisition

8

DAQ Goal



CRT readout

Develop the ICARUS-specific DAQ system based on the existing (and evolving) generic artdaq framework

DAQ server





Data management

Readout Components

• TPC

- Multithreaded readout being tested
- Plan to test with compressed data
- PMT
 - Multithreaded readout tested
 - Output to trigger boards tested
- CRT: to be delivered beyond summer 2019
 - Two systems of electronics (Bern/CAEN and Double Chooz) to be integrated
- Plan to test with more readout boards

DAQ Integration/Trigger

• Future work on integrating all the components

- Calculate the timing for each fragment
- Synchronize all the fragments
- Stress test
- Future work on trigger
 - Integrate trigger data in the software DAQ system
 - Establish and exercise mechanisms interfacing trigger and various sub-systems

Monitoring/Control

- Plans on DAQ performance monitoring
 - Develop and exercise operational readout/DAQ performance monitors based on the existing hooks
- Plans on online data quality monitoring
 - Develop online data quality monitors based on the existing framework
- Plans on run control
 - Develop GUI run control interfacing DAQ, run configuration database and catalog, and logs for shifters



- Plans on event-by-event database
 - Identify the specifications
 - Implement and test the performance
- Plans on run configuration database
 - Develop and implement
- Offline archive of the databases

Teststand

- Currently have
 - TPC boards
 - PMT readout cards
 - CRT boards
 - White rabbit timing system
 - DAQ servers
- Plan on
 - Build and assemble a TPC crate
 - Possibly a vertical slice of the integrated DAQ
 - Maintain and perform tests

Data Management

- Initiate a dedicated group in charge of
 - Transferring data collected by the online DAQ system to permanent storage
 - Cataloguing the data
 - Providing collaborators with the access to the data

Summary



- Plenty of work to do you are more than welcome to join!
- Regular DAQ group meetings at 10:30am CDT on Mondays tri-weekly (next on on Oct. 1st)
 - Mailing list: <u>ICARUS-DAQ@fnal.gov</u>
- Slow control group mailing list (common SBN): <u>sbnd-dcs@fnal.gov</u>

Backup

17

DAQ Roles

• TPC

- PMT
- CRT
- Trigger interface
- Teststand
- Run control
- Monitoring metrics/database
- Data management