

J-PARC Horn Operational Status and Upgrade Plan

T. Sekiguchi








2019. 10. 22



- **Introduction**
- **Operational experience**
- **Horn upgrade**
 - **Electrical system upgrade**
 - **Cooling upgrade**
- **Summary**



- **Introduction**
- **Operational experience**
- **Horn upgrade**
 - **Electrical system upgrade**
 - **Cooling upgrade**
- **Summary**



Target and magnetic horns are located inside He vessel at Target Station



Horn1



- **Aluminum coaxial conductor by A6061-T6**


- 3mm(10mm)-thick inner (outer) conductor
- Fatigue: 310 MPa \rightarrow 68.9 MPa after 2×10^8 cycle at 97.5% C.L.
- Corrosion: Strength reduction $\times \sim 0.43$
- Allowable stress: **29.6 MPa**

- **320kA pulsed current (design)**

- Toroidal magnetic field: 2.1 T (max.)
- Pulse width: 2~3 ms
- Cycle: 2.48 s \rightarrow **1.3 s** \rightarrow **1.16 s**

- **Water cooling**

- Heat deposit: 32.8 kJ/pulse (1.3 MW)
- **Spray water onto inner conductor**



- **Aluminum coaxial conductor by A6061-T6**


- 3mm(10mm)-thick inner (outer) conductor
- Fatigue: 310 MPa \rightarrow 68.9 MPa after 2×10^8 cycle at 97.5% C.L.
- Corrosion: Strength reduction $\times \sim 0.43$
- Allowable stress: **29.6 MPa**

- **320kA pulsed current (design)**

- Toroidal magnetic field: 2.1 T (max.)
- Pulse width: 2~3 ms
- Cycle: 2.48 s \rightarrow **1.3 s** \rightarrow **1.16 s**

- **Water cooling**


- Heat deposit: 32.8 kJ/pulse (1.3 MW)
- **Spray water onto inner conductor**



Horn1




Horn2




Horn3





- Current flow
 - Power supply $\xrightarrow{25\text{ kA}}$ Transformer $\xrightarrow{250\text{ kA}}$ Horn
- **250 kA** operation since beginning of T2K physics run
 - K2K PS (250 kA rated) reused for T2K at day1
 - **Several PS-related problems limited horn current to 250 kA**


- **Water cooling of horn conductors**
 - Water spray onto IC \Rightarrow collected in drain tank \Rightarrow pump up
- **Two independent pumps for water circulation**
 - Water supply pump
 - Water suction pump @ 7~8 m above horns
 - **Supply and suction flow rates are balanced manually**




- Introduction
- **Operational experience**
- Horn upgrade
 - Electrical system upgrade
 - Cooling upgrade
- Summary




Horn Operation History



- **Water level decreased during beam operation since March 2018**
 - **~5 L/day** (\Leftrightarrow 10 L/day in 2012)
 - Dropped water immediately evaporated and condensed after He compressor, then collected at its drain tank



- **Investigation performed after beam operation**
 - **Before opening He vessel**
 - One-by-one horn operation and water circulation
 - Check water level → **Horn1 caused water drop**
 - **In-situ investigation after He vessel opened**
 - **Remote camera inspection during horn operation**
 - Special visual inspection tool lowered through $\phi 65\text{mm}$ through-hole
 - **Observed actual water drop from upstream of horn1**



• Expected reasons of the drop

① Corrosion at the upstream seal

- A step structure at the upstream flange created a water pocket
- If water stays at a tiny gap, a gap corrosion occurs

② Beam heating caused thermal expansion of bolts

- Contact pressure at seal reduced


③ Higher pressure inside horn than before

- Outlet pressure of new He blower is higher by ~4 kPa than before (~115kPa@Horn1)


• Countermeasures

- Don't stop water circulation during long shutdowns
- Change He flow direction to reduce He pressure
 - Horn1(**115kPa**)→Horn2(105kPa)→Horn3(101kPa)
 - Horn3(115kPa)→Horn2(105kPa)→Horn1(**101kPa**)
- Larger drain tank for He vessel drain (30L→250L)


• Current horn1 will be replaced in FY2021



1st/2nd generation horn1






3rd generation horn1




- Al knife-edge seal → **Helicoflex seal** ⇒ **Countermeasure for thermal expansion**
- **Remove step structure** ⇒ **Avoid corrosion**
- Al bolts ⇒ **Ti bolts** ⇒ **Countermeasure for thermal expansion**

- **Introduction**
- **Operational experience**
- **Horn upgrade**
 - **Electrical system upgrade**
 - **Cooling upgrade**
- **Summary**

- **320 kA & 1 Hz operation** \Rightarrow **10%** neutrino flux gain
 - 3 power supply configuration
 - Need new PS, Transformer, striplines
- **Cooling improvement**
 - Horn2 stripline cooling : He gas cooling (~ 750 kW) \Rightarrow water cooling (1.3 MW)
 - **Development of water-pipe embedded striplines (only for Horn2)**
 - Additional cooling for upstream part of Horn2 outer conductor
 - Cooling capacity improvement
 - H₂ removal system for safe operation




- **New power supplies** with energy recovery
 - Operation voltage < 6 kV at 320 kA
 - Charging time < 1 sec
- **New low impedance striplines**
 - $L \sim -40\%$, $R \sim -30\%$
 - Wider and thicker stripline plates
 - Stronger against Lorentz force
- **New transformers** for 320 kA operation
 - High mechanical strength
 - High magnetic field tolerance
 - High cooling performance




Parameter	horn1	horn2	horn3
Operation current	323 kA	323 kA	323 kA
Operation voltage	<u>5.85 kV</u>	<u>5.72 kV</u>	<u>5.91 kV</u>
Returned voltage	4.60 kV	4.78 kV	5.00 kV
Voltage recovery rate	78.6 %	83.6 %	84.6 %
Pulse width	2.00 ms	2.01 ms	2.08 ms
Charging time	<u>0.71 s</u>	<u>0.54 s</u>	<u>0.52 s</u>

- Three transformers should be placed in the existing space
 - Available space for transformers is very limited \Rightarrow **compact design needed**




- Three transformers should be placed in the existing space
 - Available space for transformers is very limited \Rightarrow **compact design needed**



Staged Upgrade Scenario

Current




1st upgrade in FY2021


for 1 Hz operation @ 250 kA

- New transformer
- Capacitor upgrade

After FY2021




Current




1st upgrade in FY2021
for 1 Hz operation @ 250 kA

- New transformer
- Capacitor upgrade

After FY2021






After FY2023



2nd upgrade in FY2021
for 320 kA operation

- New power supply
- New transformer
- Striplines outside He vessel



Item	Horn1	Horn2	Horn3
Instantaneous temp. rise (°C)	16.3	3.6	1.0
Steady state temp. rise (°C)	19.1	22.1	5.8
Coolant water temp. (°C)	25.0	25.0	25.0
Max. temp. (°C)	60.4	55.3	31.8

- **Expected max temperature ~ 60.4°C < 80 °C (allowable temp.)**
 - Cooling performance is sufficient for 1.3 MW
 - Monitor temperature at several non-energized parts (water, frames, etc)
- **Cooling capacity**
 - Currently ~1 MW acceptable ⇒ cooling capacity improvement
 - Replacing pump and heat exchangers needed

Summary of upgrade from ver.2 to ver.3

Item	Horn1	Horn2	Horn3
Conductors	Improved upstream sealing	Improved inner conductor	No change
Cooling	No change	Forced cooling of upstream plate and flange	No change
Striplines	No change	Water-cooled striplines	No change



- **Heat deposit at Horn2**

- Heat deposit by single shot 3.2×10^{14} ppp beam
 - Higher heat deposit at upstream thick plate and flange

- **Horn2 OC cooling**



- No forced cooling, but bottom running water has cooling effect
- Water vapor inside the horn conductors can help for cooling

Heat deposit at Horn2 by PHITS 3.11 (in unit of Gy)




- Cooling simulation**

- 1 kW/m²/K (bottom) and 100 W/m²/K (others) assumed
- Expected temperature to be **45°C** (barrel) and **75°C** (upstream flange)
 - High temperature causes **1mm deformation**
- **Water cooling for upstream parts**
 - Water-pipe embedded as same as water-cooled striplines
 - **Upstream part successfully cooled down to 35°C**




- **Heat deposit at striplines**
 - **Largest at horn2** due to defocused particles
- **Forced He flow inside stripline ducts**
 - Current flow rate for Horn2 → **750 kW** acceptable
- **Water-cooled striplines development for 1.3 MW**








Heat flux per stripline plate (J/m²) @ 1.3 MW


	Horn1	Horn2	Horn3
Total (Beam + Joule)	214	1066	141
Acceptable beam power (MW)	2.10	0.75	2.04





- **Water cooled striplines**
 - **Stainless pipe embedded** in 15mm-thick plate by **Friction Stir Wending (FSW)**
 - Cooling test with small test piece → **$> 3 \text{ kW/m}^2/\text{K}$ achieved.**
 - **Max temp. @ 1.3 MW = 61.6°C ($<$ allowable temp. 80°C)**
 - 0.75 MW (by He cooling) → **2.1 MW acceptable**



- **With water-cooled OC flange**
 - 3/8 inch stainless pipe embedded
 - Effective heat transfer coefficient = 5 kW/m²/K
 - Heat transfer coefficient of 1kW/m²/K at stripline connection
 - Max temp. @ connection can be reduced to ~ 45°C






















- **First mockup produced in FY2016**
 - Producibility check for real size
 - Water circulation test
- **Further mockup tests**
 - **Current test** with spare horn1 (ongoing now)
 - Vibration measurement
 - ⇒ No difference compared to normal one
 - **Check vibration tolerance** of water inlet/outlet
 - **Current test** in FY2020
 - Final mockup to be tested
 - Spare horn2 not ready, test with striplines only
 - The final mockup can be installed if no further modification needed
- **Installation** to Horn2 in FY2021





Upgrade Schedule


Item	FY2019	FY2020	FY2021	FY2022	FY2023
Power supply (existing)			Install 		
Capacitor		Production 			
Transformer #2		Production 	Install 		
Power supply (new)				Production 	Install 
Transformer #3				Production 	Install 
Horn operation		Horn1 320 kA? 		 1.3 s 	All horn 320 kA 
Horn1 ver.3			Install 	Horn1 320 kA 	
Horn2 ver.3	Production 		Test  Install 		
Water-cooled stripline	Production 	Test 			

Summary

- **Magnetic horns to focus secondary pions**
 - Currently 250kA @ 2.5 s
 - Water-cooled horn conductors
- **Operation status**
 - Operating second-generation horns since 2014 \Rightarrow 17 million pulses
 - Water drop problem at horn1
- **Upgrade for 1.3 MW beam**
 - Horn current increase to 320 kA @ 1Hz
 - New PS, transformer, striplines developed
 - Staged upgrade
 - For 1Hz operation in FY2021
 - For 320 kA operation in FY2023
 - Cooling improvement
 - Horn2 upstream cooling
 - Horn2 striplines with water cooling

Backup

January 2014



- Drop rate : **>10 L/day**
- Dropped water **ran the bottom**
- **Significant corrosion** of iron surface
- **Condensation** at horn surface

December 2018



- Drop rate : **~5 L/day**
- Dropped water was **evaporated**
- **No** additional significant **corrosion**
- Horn surface is still **clean** (shinny)

- **Power supply**

- 1 Hz operation cycle \Rightarrow charging time < 1 sec.
- Rated peak current : 32 kA at PS output
- 2 ms pulse width \Leftarrow can be widened up to 3ms since lower heat load at Horn3
- Design lifetime $> 2 \times 10^8$ pulses ($\Delta C/C < 5\%$ at 2×10^8 pulses)
- Remote control from external system (via EPICS)

- **Transformer**

- Turn ratio = 10 : 1 (32 kA \rightarrow 320 kA)
- Rated peak current : 320 kA
- Compact size
- Water cooled


Electrical Parameters

Inductance and resistance

Components	New configuration					
	horn1		horn2		horn3	
	L (μH)	R ($\text{m}\Omega$)	L (μH)	R ($\text{m}\Omega$)	L (μH)	R ($\text{m}\Omega$)
Horn	0.47	0.100	0.46	0.035	0.53	0.023
Striplines	0.15	0.056	0.17	0.060	0.18	0.065
Transformer	0.25	0.025	0.25	0.025	0.25	0.025
Total	0.87	0.181	0.88	0.120	0.96	0.113


PS circuit parameters

Item	Value
Rated operation voltage	7 kV
Rated charging current	7 A
Charging unit	50 kW
Rated operation cycle	1 Hz
Total capacitance	4 mF
Capacitor bank configuration	
(original design)	2S16P (0.5 mF \times 32)
(modified)	2S24P (0.335 mF \times 48)
Pulse width	2 ms
Rated output current	32 kA
Stored energy	98 kJ




Transformer Drawing



Iron core cross section : $0.5\text{m} \times 0.5\text{m} = 0.25\text{m}^2$






- Horn current and pulse width reduced during Run8
- Capacitance measurement
 - Decrease by **5~10%@1.3x10⁷** \Leftrightarrow Spec : $\Delta C/C < 5\%$ @ 2×10^8 pulses
- Inspection by manufacturing company
 - Electro-corrosion on Al metallized electrode
 - Resulting in capacitance drop
 - Caused by **100% alternating voltage operation**
- Measures
 - Same phenomenon at CERN Booster magnet PS
 - CERN already has a solution for this problem
 - **Al+Zn metallization** \Rightarrow no electro-corrosion
 - rf. <https://doi.org/10.1109/EPE.2015.7309424>
 - **All capacitors to be replaced with modified ones**



- **New PS developed for 320kA&1Hz operation**
 - Two PSs in service since 2014 ($\sim 1.75 \times 10^7$ pulses) \Rightarrow **5~10% capacitance drop** observed
 - Found that alternating voltage usage caused electro-corrosion
- **New capacitors with countermeasures already developed**
 - **Replacement of all capacitors needed**
 - New capacitors have 50% larger in volume with same capacitance (0.5mF)
 - To keep the size, capacitance $0.5 \rightarrow 0.335\text{mF} (\times 2/3)$ and # of capacitors increased ($\times 3/2$)
 - **Additional PS chassis is needed**




- For horn1, all upgrade were completed
- 320kA test operation performed
 - Charging voltage : 6.05 kV as expected (\Leftrightarrow 5.8 kV, rated 7kV)
 - Pulse width : 1.98 ms as expected (\Leftrightarrow 2 ms)
 - Short-term (24 hours) continuous operation performed
 - No problem observed \Rightarrow ready for 320 kA



- **1.3s operation w/ current setup**
 - If no budget, we must use current setup for high rep. rate operation ==> Is it feasible or not?
 - A concern on temperature at epoxy insulator < ~60°C
 - 4 hour operation at 1.3 s cycle
 - Measured temp. at various points
 - ~60°C @ copper busbar
 - ~50°C @ nearby epoxy insulator
 - 1.3 s cycle operation is feasible but new transformer should be prepared for a safe and stable operation



	Horn1	Horn2&3
Primary busbar	<50°C	<50°C
Primary epoxy	<50°C	40°C
Secondary busbar	48 °C	60 °C
Secondary epoxy	38°C	48°C
Iron core	<50°C	<50°C
Aluminum busbar	35°C	34°C




- **Large displacement@Horn2 \Rightarrow $\sim 1\text{mm}@320\text{ kA}$**



- Inner conductor was modified to reduce displacement.
 - Adding ribs on both upstream and downstream ends
- Transient stress analysis for Lorentz force and Joule heating
 - Done by RAL team (P. Loveridge)



Outer conductor:
Al-Alloy



Inner conductor:
Al-Alloy



Time-history for Joule Loss and Magnetic Pressure loads corresponding to $I_{max}=320\text{kA}$

FEM results

- Displacement reduced from 0.93mm to **0.25mm**
- Stress at endplate also reduced from 45MPa to **24MPa**
- Design modification and outer conductor production to be done

Transient Analysis: Displacement Results (320 kA)

Transient Analysis: Stress Results (320 kA)

