




Managed by Fermi Research Alliance, LLC for the U.S. Department of Energy Office of Science

ICARUS CRT

Minerba Betancourt and Umut Kose on behalf of the CRT group

September 12, 2019

Overview of the ICARUS CRT




Bottom CRT planes: installed and tested
Setting the DAQ interface →



Modules at the West and East Sides

- Working on getting support structures installed
- Remaining side CRT is going to be installed after the cold commissioning is completed




Supports



Drawing courtesy of Cat

Schematic

- Preparing the utility rack, several components on site Fermilab (FEB, optical readout, timing distribution and servers)
- Power supplied is scheduled for delivery in a couple of weeks
- Testing the power distribution




We received 40 FEBs from Marzio for the side CRT

Power Distribution

- Design criteria:
 - Minimal line & circuit power drop
 - Full power supply sensing compensation
 - Ripple/noise reduction
 - Minimal voltage spread
 - To keep all the FEBs within the working voltage (5.1 V)
 - Reliability
 - Long term operation
 - Safety
 - Easy access and troubleshooting
 - Uniform distribution
 - Balanced load
 - Easy replacement
 - Note: since the top CRT will have maximum load (12 FeBs/line, twice the side system) the layout was optimized accordingly. Using the same cabling for the side is straightforward, since derivations are similar for CRT pairs or single

Power distribution box, PDB, will be prepared both for side and top CRT systems


Single power line layout



- Power distribution line and box are designed and materials identified
- A simple simulation with SPICE has been performed.
- Voltage drop test has been performed: all the measured voltage drops found to be within estimated range.
- Couples of power distribution box in preparation for final test.

Cable Mapping for the side CRT

- We have all the cable mapping for the side CRT ready for installation
 - Cables for servers, T0 and T1



Details about all the cable mapping at SBN-doc-13486

Top CRT grouping



- 11 lines (+ 1 spare)
- max 12 CRT/line
- shortest cables for the chains of 12
- small load spread ($9 \times 11 + 2 \times 12$), compensated by the cables
- relatively straight cable paths

Mihai Iliescu, Umut Kose, CERN, July 2019

2


Test Stand at Fermilab

Chris, Tyler, et al.


- Setup a test stand at Fermilab to test the optical readouts and efficiency measurements



- Setup contains six FEBs





- Test stand at Fermilab has three modules in a stack, with one ORM at each end (North/South) connected to its own Front-End Board (FEB)



- Two ORMs are tested at a time on the middle module, top and bottom modules have the same form ORMs on them for all runs
- Two tests are run: one to obtain ADC/PE conversion, as well as check for spurious noise, another to obtain light yield at 4 meter along the module

Setup


- Using daisy chain scheme for distribution of two timing signals: PPS (T0) and hodoscope (T1)
 - Testing the setup we are going to use in the detector




Production Numbers

- Produced a total of 361 ORMs at CSU
- After QC checks done on site at CSU, 344 were identified as shippable and 340 were sent to Fermilab
- Testing at Fermilab identified a further 13 ORMs as unviable, leaving a total of 327 viable ORMs for use in the detector
- Need a total of 268 for full coverage of side CRT modules, (22% spares for installation)

North Bottom Reference ORM Light Yield Stability




North Mid ORM Light Yield Stability




Cutting the modules

- Modules for the south wall have been cut at Wideband
 - We have a few modules that needed to be sealed and tested
- The last layers of the modules for the north wall needed to be cut to avoid interference with the cryo piping
 - Modules have been cut at ICARUS building. We will need to seal and test them







North Wall



South Wall



Top CRT assembly steps: (Frascati, Italy)



Transporting to CERN then Fermilab with 40inch container

Status

- Top CRT module assembly is on going
- Assembled modules tested for light tightness and efficiency
 - Efficiency found $\geq 94\%$
- Approved modules stored on the rack
- First container is ready to be transported to CERN
 - Due to custom's clearance complexity (from Italy to Switzerland) shipping being delayed!
- Once custom problem resolved, couple of CRT module will be transported to Fermilab
- The rest of modules to be shipped to Fermilab on February 2020
- All modules will be tested again at Fermilab before installation. Space will be needed in the ICARUS hall, preferable a closest area to the truck door

CRT Database at CERN

- We set up a database (MySQL) at CERN to store the history and information of CRT modules.
- Barcode system used for FEBs, Scintillators and CRT modules, Id numbers for SiPMs.



- Will be merged to the database at Fermilab

ICARUS TOP COSMIC RAY TAGGER PRODUCTIONS

We are planning to put Barcode stick on the module in order to trace the history, and link the scintillators (producer, batch number, quality check results), fibers, SiPMs (Batch number, Breaking Voltage, Dark Count), Front-end-Board (SiPM connected channels) etc.

We would need to create Barcode, read them by scanner and fill the proper tables:

[Scintillator productions and quality checks \[obsolete\]](#)

Fibers polishing and aluminization

[SiPM Database](#)

[Front-end-Board Database](#) → PHP interfaces for Database communications

[Scintillator Database \(New!!\)](#)

[CRT Module Construction](#)

[CITIROC_SC_SN files](#) → CITIROC configuration files

[Goto ELOG](#)

We set up Slack workspace for communication: topcrtteam.slack.com please register if you have not done it yet.

Useful documents:

All the Front-end-Board have to be configured before attaching to the CRT module. High voltage (58 Volts) with help of trimmers, MAC Address (serial number -100), and barcode. Please follow the steps given in [the instruction](#) document.

For each single CRT module, [check list document](#) has to be printed and the steps followed carefully.

Copies of CRT barcodes numbered as: [CRTxxxx](#)

Copies of FEB barcodes numbered as: [FEBxxxxx](#)

How to access database and elog: [DB and ELOG](#)

How to prepare CITIROC configuration files: [CITIROC_SC_SNxxx](#)

CRT DAQ Activities

In case of any problem or help, please contact [Dmitri Kozlov](#)

Checklist document

ICARUS Cosmic Ray Tagger - Modules

[ADD NEW ENTRIES...](#)

[Return to the main menu](#)

100

Connected to MySQL DATABASE

Example SQL table

CRT Barcode	CRT Assembly date [YYYY-MM-DD]	FEB Barcode	Barcode of Scintillator	Barcode of SiPMs	FEB Channel numbers	Electronics Functionality	Pedestal Scan	Calibration Scan	Cosmic Muon	Efficiency	Name	DB Update	Citiroc Config
1	CRT00001	FEB00001	10216Scin	15827 15830	0 1	YES	NO	NO	NO	94	Laura	Update Module	Citiroc_SC
			10212Scin	16675 16648	2 3								
			10215Scin	15801 15841	4 5								
			10226Scin	16591 16590	6 7								
			10171Scin	15842 15803	8 9								
			10188Scin	15813 15857	10 11								
			10164Scin	16572 16568	12 13								
			10165Scin	16584 16583	14 15								
			11270Scin	13840 13815	16 17								
			11272Scin	14053 14052	18 19								
			11256Scin	14121 14136	20 21								
			11264Scin	13834 13833	22 23								
			11271Scin	13801 13805	24 25								
			11275Scin	14064 14058	26 27								
			11101Scin	13747 13742	29 29								
			11117Scin	13767 13766	30 31								
			10018Scin	14075 14074	0 1								
			10020Scin	13754 14101	2 3								
			10003Scin	14088 14092	4 5								
			10004Scin	14085 14082	6 7								


Next Steps

- Reseal and test the modules for the north and south wall
- Install the FEB support
- Install the support for the rolling side CRT
- Install the modules at the rolling side CRT
- Test the power distribution at the Fermilab and Frascati test stand
- Test the DAQ at Fermilab and Frascati test stand
- Finalize the utility and server racks for both systems
- Install the electronics
- Commissioning of the bottom, side CRT and two modules from the top CRT

Back Slides

Front-end-boards

- All FEBs received from CAEN.
- Firmware upgraded with new functionalities.
- We have found a bug “stuck event/spikes” on T0 timing reference. Fixing the bug and testing in progress.




- After bug fix, timing resolution measurements will be performed once more again.

Bottom CRT

- Double Chooz veto modules installed, including the PMT readout
- Readout has been tested
- Ongoing work: setting the artDAQ interface



Setup



Using daisychain scheme for distribution of 2 timing signals: PPS (T0) and hodoscope (T1)

Route TOUT signal from each FEB to coincidence unit at the rack

