
# SLAC Proposal for PX L-band Couplers

Chris Adolphsen



# **TTF-3 Coupler Design**


Design complicated by need for tunablity (Qext), dual vacuum windows and bellows for thermal expansion.




**Coaxial Power Coupler** 

# Baseline and Alternative Coupler Designs

|  |          | Cold Window     | Bias-able | Variable Qext | Cold Coax Dia. | # Fabricated |
|--|----------|-----------------|-----------|---------------|----------------|--------------|
|  | TTF-3    | Cylindrical     | yes       | yes           | 40 mm          | 62           |
|  | — КЕК2   | Capacitive Disk | no        | no            | 40 mm          | 3            |
|  | KEK1     | Tristan Disk    | no        | no            | 60 mm          | 4            |
|  | LAL TW60 | Disk            | possible  | possible      | 62 mm          | 2            |
|  | LAL TTF5 | Cylindrical     | possible  | possible      | 62 mm          | 2            |



# Achieving Uniform Gradient Along the Bunch Train in Each Cavity



Relative Gradient = Actual Cavity Gradient (due to TTF and Field Limits) / Nominal Gradient for RF Unit (roughly the average)

Assume all cavities in RF Unit run at the same rf phase

SLAC Coupler Facilities and Capabilities

# SLAC Cleanroom Dedicated to Coupler Assembly

- Building 006 High Bay before cleanroom (left picture)
- Building 006 High Bay after cleanroom (right picture)



- Class 10 cleanroom 24 ULPA Filters (99.999% @ 0.12)
- Cleanroom size is 16' x 12'





#### Ultra Pure Rinse Station in class 10 area



- Class 100 cleanroom 10 HEPA Filters (99.97% @ 0.3)
- Cleanroom size is 12' x 12'



#### Ultrasonic Wash Station in Class 100 area




- Air Shower
  - All material and personnel will go through the Air Shower to remove particulates prior to entering into the cleanroom.






Power Coupler Sub-Assemblies and RF Processing Stand (4 MW Peak Power)






Processing of First Pair after 150  $^{\circ}$ C Bake: Power (MW) -vs- Time for Pulse Widths of 50,100, 200, 400, 800, 1000  $\mu$ s



# **SLAC Connection Cavity**



average dissipated power (stainless) =  $0.23\% \times 1.3$  MW  $\times 1.5$  ms  $\times 5$  Hz = -22.3 W


integrated field from antenna tip =  $\frac{-28.76 \text{ kV}}{-28.76 \text{ kV}}$ 

## **Current L-Band Test Stand in ESB**










## Multipacting in 40 mm Diameter SS Coaxial Line after Initial Processing



# **Coupler Fabrication**

### 12 Couplers Ordered from CPI by FNAL have been Inspected – 4 warm and 3 cold sections being repaired



#### **TTF3 Coupler Metrology Report**

|                   | Inspection of Cold Part 3964328/A.000   |                      |                     |          |       |                        |   |  |  |
|-------------------|---|----------------------|---------------------|----------|-------|------------------------|---|--|--|
| Serial<br>Number: |   | Inspector:           | Keith Caban (CMM)   |          | Date: | 11/9/2007              |   |  |  |
| Serial<br>Number: | CP3C41  | Inspector:           | Tom Nakashima Video |          | Date: | 11/14/2007             | * |  |  |
|                   |   |                      |                     |          |       |                        |   |  |  |
| Item              | Inspection Criteria   | DESY Print<br>Number | LAL Print<br>Number | Findings | Pass  |                        |   |  |  |
| 1                 | Visual: Nicks, scratches, proper edge chamfers  | 3964328/A.003        | 165-3D-1250         |          | х     |                        |   |  |  |
| 2                 | Visual: Weld form, size, and porosity   | 3964328/A.000        | 165-2E-1200         |          | x     | and all and the second |   |  |  |
|                   | Visual: Brazing: irregularities, centering of groove , buildup<br>Ceramic: metailization borderline,coverage, chamfer | 3964328/A 200        | 165-35-1260         |          | x     |                        |   |  |  |
| I                 | I   |                      | I                   | I I      |       | THE PARA               |   |  |  |

# **Coupler Inspection Results**

Failed inspection: Warm inner conductor with extensive oxidation.



# **Coupler Inspection Results**

Failed Inspection: Here the part has copper plating on the ceramic. The ceramic has to be free of metallization.



## DESY/Orsay Developing Other Vendors (ACCEL, Thales and Toshiba)



#### ACCEL






## SLAC Klystron Group is Building a Cold Section using TIG Welding instead of E-beam Welding



Parts from an Orsay sponsored study of TIG Welding





# Elements of a PX Coupler R&D Program

- Study power and multipactor limits of TTF3 coupler using coupler processing stand and coupler component test stand at SLAC
- Continue program of building coupler cold parts without e-beam weld to allow more vendors and lower cost
- Build and test 60 mm diameter cold section to see if it is more robust at higher power
- Re-examine design of the warm section e.g., may want to eliminate the HV bias option to reduce cost