



Roger Kalt on behalf of the LLRF team :: Paul Scherrer Institut

Lab Talk: LLRF Status and Activities at PSI

LLRF Workshop 2019, Chicago

30.09.2019 - Presented at LLRF Workshop 2019 (LLRF2019, arXiv:1909.06754)

Table of Contents

4 Accelerator Facilities

- ☐ SwissFEL (Swiss Free Electron Laser)
- ☐ SLS (Swiss Light Source)
- ☐ HIPA (High Intensity Proton Accelerator)
- ☐ Proscan (Proton Cancer Therapy)



SLS

HIPA

Proscan

4 Mandates of the LLRF team

- | | |
|--|---|
| <input type="checkbox"/> Operation & Maintenance | <input type="checkbox"/> Planning |
| <input type="checkbox"/> All | <input type="checkbox"/> HIPA injector Cyclotron RF upgrade |
| <input type="checkbox"/> Realization & Commissioning | <input type="checkbox"/> Upgrade |
| <input type="checkbox"/> SwissFEL-Athos Beamline | <input type="checkbox"/> SLS 2.0 storage ring upgrade |

RF systems in operation

Facility:	HIPHA	SLS	Proscan	SwissFEL
LLRF operated since	1980's	2000	2005 (1980's)	2015
System Type	Analog	Analog	Analog	Digital
RF Op. Type	CW	Pulsed 3 Hz + CW	CW	Pulsed 100 Hz
Hardware	Own design	External institute	Internal HIPA + Ext.company	COTS (Controls HW) + own RF
Controls integration	Analog interface	Analog interface	Analog interface	Full remote access

Table: LLRF systems in operation:

SwissFEL: 6 x 3 GHz ; 2 x 12 GHz; 28 x 5.7 GHz (*2 types*) \Rightarrow **36 RF Stations**

(today with test facility and Athos)

HIPHA: 8 x 50 MHz (*3 types*); 4 x 150 MHz (*3 types*); 1 x 500 MHz \Rightarrow **13 RF Stations**

(today situation with test facility)

SLS: 7 x 500 MHz (*3 types*); 2x 3 GHz; 1x1.5 GHz SC passive \Rightarrow **10 RF Stations**

(today with test facility)

Proscan: 1 x 72.8 MHz \Rightarrow **1 RF Station**

total 60 RF Stations



SwissFEL

SwissFEL
RF Teststand

- ☐ Main Beamline Aramis:
- ☐ 2nd Beamline Athos:
- ☐ RF Teststand:


Operation & Maintenance
Realization & Commissioning
Installation of C-band RF system

SwissFEL Project Summary & Outlook

Status (as of Sept. 2019)

1x X-band LLRF FE devel.,
modulator in-house devel.

1x C-band LLRF installed,
modulator commissioning...



All 34 RF systems are installed and in operation

Schedule

	2019	2020	2021
Aramis	User operation	replace X-band LLRF FE	
Athos			
- dual bunch operation	Establish permanent dual bunch		
- RF systems installation & commissioning	LLRF FE & mod. development	Commissioning	
- user operation			User operation

RF- and Beam-Stability Analysis

- ☐ LLRF system fulfills stability requirements
- ☐ Model-based prediction of RF vs. beam jitter
- ☐ Identify critical RF stations, then jitter contributing subsystems like:
 - HV modulator Different issues, e.g. loose conn.
 - Pre-amplifier Broken units – repair program
 - Klystron multipactor Different for each klystron
 - BOC multipactor A problem below 40 MW input power



LLRF Tuning for Dual Bunch Operation

- ☐ Keep basic low-level RF functionalities on lower-layer as is
- ☐ High-level setup and automation tools for **independent** tuning of both bunches created.



RF Systems Availability Analysis

- ☐ Implemented dedicated RF systems fault events database


Low-Level RF Hardware

❑ Fuse broken, PS broken, cable loose


- Check & tighten all cables 1x / year

❑ Commercial LO amplifiers have production problems: Results in sudden phase jumps up to 1.5 deg.

- In-house development of low-noise narrow-band LO amplifier



Jumps of the LO amp result in phase jumps in all Rx channels.
Example 4 days.



Blue: Reference phase meas.
Orange: LO Amp RF level

Low Level RF Software / Algorithms

❑ Sudden software crash or stall, ~10-20 events / year

- Reboot, have a proper configuration parameters restore mechanism.

❑ Gun recovery from RF trip takes ~20min

- Instead of pickups implement virtual probe based on FOR/REF dir. coupler sig.

❑ Race conditions of LLRF trigger vs. RF phase reference

- FPGA based race detection and automatic correction


❑ BOC detuning over LLRF phase measurement stuck

- Control room alarms on the ACC voltage: Expected vs. measurement

❑ Klystron output RF amplitude setting procedure is not robust enough for all use cases

- Klystron LUT, forbidden multipactor areas, HV feedback, operation pt. det. algorithm

Example C-band station





HIP

- ☐ Operation & Maintenance of old RF stations
- ☐ Implementation & Commissioning for Injector Cyclotron RF upgrade

HIPA Injector Cyclotron RF Upgrade Project



Old analog LLRF



Dig. LLRF (installation partly completed)

RF Upgrade Project General Scope

- ☐ Exchange of two 150 MHz resonators with 50 Mhz
- ☐ Complete renewal of RF systems of all resonators

Status LLRF Upgrade

- ☐ Low-power tests with cavity + tuner plungers done
- ☐ Fw/Sw implementation on-going
 - Generic re-usable code open-sourced on [GitHub.com/psi_fgpa_all](https://github.com/psi_fgpa_all)
- ☐ RF frontend HW prototypes [filters, selectable attenuators] produced & characterized (pizza box style)
- ☐ HW installations & cabling partly completed

RF Upgrade Project Roadmap

- ☐ Solve cavity tuner plungers and hot-spot problems at the 50 MHz RF test stand
- ☐ Amplifier chain RF-commissioning stand-alone
- ☐ Amplifier chain connection to the already installed cavity

LLRF Upgrade Roadmap

- ☐ System integration & exception handling tests (e.g. startup)
- ☐ Handle >90dB dynamic range for cavity tuning





- ☐ Operation & Maintenance
- ☐ Planning for SLS 2.0 Upgrade

SLS → SLS 2.0 upgrade preparatory phase

Goal: Upgrade storage ring to provide factor >30 improved brightness + harder X-rays

For all subsystems such as RF/LLRF: Upgrade to ensure other 20+ years operation, to optimize operation + maintenance cost, optimize perf. ...

→ Upgrade analog to digital 500 MHz LLRF / tuning system.

Schedule (simplified)

	2019	2020	2021	2022	2023	2024
SLS-2 preparatory phase						
financing period						
procurement/testing/pre-assembly						
maximum "dark" period						

Status

1. Decision for SSA's in Aug-2019, but some klystrons may stay
2. Internally with other groups next **processing platform options** evaluated: **CompactPCI-Serial** or **internal platform** developed for BPM's.
3. Upgrade of Linac RF stations (currently with feed-forward only) with the SwissFEL type digital LLRF (exact fit: pulsed 3 Hz @ S-band)



SwissFEL

☐ LLRF System weak points known – most of them are in software / algorithms.

- Replacement of the commercial LO amplifiers with in-house development.
- Consolidation of the RF amplitude setting procedure

☐ Studies like RF vs. beam jitter to be continued → Talk

- Identified weak RF stations and subcomponents
- LLRF is not the limiting subcomponent for the critical RF stations such as injector S- and X-band.

☐ Operation:

- Establish dual bunch operation as default
- Beam-rate: Go up to 100 Hz
- Training of other colleagues for operation procedures and problem handling.

HIPAC Injector Cyclotron Upgrade

☐ LLRF upgrade to new digital LLRF on-going, first RF station in operation 2020.

SLS 2.0 Upgrade

☐ Next processing platform selection process almost completed.

☐ Implementation of prototype 500 MHz prototype LLRF for RF test stand 2020

My thanks go to

- All team members
- All colleagues for their contributions to the workshop

