

COMMISSIONING THE LCLS-II LLRF SYSTEM IN THE LERF CRYMODULE TEST FACILITY

Curt Hovater, Ramakrishna Bachimanchi, Tomasz Plawski, Michael Drury, Larry Farrish,
Wesley Moore, Clyde Mounts, Anna Solopova, JLAB, Newport News, VA 23696, USA
Larry Doolittle, Gang Huang, Sergio Paiagua, Carlos Serrano,
LBNL, Berkeley, CA 94720, USA
Andrew Benwell, Jorge Diaz-Cruz, Sonya Hoobler, Janice Nelson, Alessandro Ratti,
Benjamin Ripman, Lisa Zacarias, SLAC, Stanford, CA 94309, USA
Brian Chase, FNAL, Batavia IL, USA




Abstract

The JLAB Low Energy Recirculating Facility, LERF, has been modified to support concurrent testing of two LCLS-II cryomodules. The cryomodules are installed in a similar fashion as they would be in the L1 section of the LCLS-II linac, using all of the LCLS-II hardware and controls for cryomodule cryogenics, vacuum, and RF (SSA and LLRF). From the start, it was intended to use LCLS-II electronics and EPICS software controls for cryomodule testing. In effect the LERF test facility becomes the first opportunity to commission and operate the LCLS-II LINAC hardware and software controls. Specifically it is an excellent facility to test the performance and commission all facets of the LLRF system. This poster presents the trials, tribulations and successes of the LLRF system as it was commissioned and used for cryomodule tests.

CRYMODULE, RF AMPLIFIERS, & LLRF RACK



RF SYSTEM



LCLS-II RF System Block Diagram

Features

The LERF replicates the RF system in the L1 section of the LCLS-II Linac

High Power RF

- 16 four kW solid state amplifiers tested to 4 kW
- 50 dB dual directional couplers
- Isolator with load tested to 4 kW

Low Level RF

- Each rack controls four cavities
- Single LLRF System/cavity
- Resonance
 - Coarse: Stepper motor
 - Fine: Piezo Tuner
- Cavity Interlocks
- Cavities tested and operated in SEL and SELAP (GDR)

Mode


Description

SEL (Self Excited Loop)	RF system tracks the cavity frequency in open loop, no phase or amplitude regulation
SELA (Amplitude)	RF system tracks the cavity frequency while maintaining cavity amplitude with feedback loop parameters
SELAP (Phase)	RF system runs at nominal frequency while maintaining cavity amplitude and phase. GDR equivalent.
Chirp	Frequency sweep over 100 kHz within one waveform to quickly measure detune over wide range. Used only during characterization
Pulsed	Pulsed RF
Tone	Open loop forward power without tracking frequency. Used for system calibration and testing by experts
Integrator (on)	Piezo tuner feedback loop enabled. Tunes cavity based on RF detune calculation

RF START UP/CALIBRATIONS


RF Start Up Calibrations

- SSA Calibration
- Frequency Chirp
 - Determines cavity frequency
- Pulsed SEL Calibration
 - Loaded Q
 - Cavity scale factor (gradient)
- Ramp to Target Gradient in SEL Mode
- 8pi/9 Frequency




LLRF EPICS Waveform Screen Showing a Gradient Calibration from the Emitted Power


“OUT-OF-LOOP” RF SYSTEM PERFORMANCE




Phase noise plot of the cavity field signal in GDR. RMS. Phase error is 0.013°. Phase noise was limited by the LO source.



Amplitude error of the cavity field signal in GDR. RMS. Error is 0.016%.




Solid State Amplifier Gain Curve



LLRF Experts Assisting with Cryomodule Commissioning

RF INTERLOCKS

- All fault information embedded into firmware
- Enables fast response and fault waveform capture
 - Quench detection
 - SSA permits
 - IOC watchdogs
 - Stepper tuner temperatures
 - Limit switch status
 - Coupler temperatures
 - Vacuum status
 - Cryo-system summary




Cavity Quench Fault Waveforms


RESONANCE CONTROLS

Features

- Coarse Control: Stepper motor
- Fine Control: Piezo Tuner
 - Simple integrator ~ 1Hz
 - Easily tracks out the He drifts
 - +/-50 V with 2000 Hz dynamic range
- Resonance control implemented a simple “I” controller to compensate for He drifts




Waveforms showing cavity active detuning while in SELAP (GDR)



Resonance control screen for stepper motors and piezo control

Resonance system is Active
Resonance Control (ARC) ready. This has been tested at FNAL.



This work was supported by the LCLS-II Project and the U.S. Department of Energy, Contract DE-AC02-76SF00515