

# Primary Beamline Low Conductivity Water (LCW) Preliminary Design Review

Technical Design Aspects

131.01.03.03.02.04.02 Primary Water LCW System

131.01.03.03.02.04.03 Electrical Bus


Noah Curfman

October 31, 2019

---



# System Operational Scope



# Summary of Major System Updates

- Re-arrangement of service building
  - MVA staging area merged with service building
  - Re-arrangement of dipole power supplies
    - Significant changes to pipe and bus routing
- Minor magnet lattice re-arrangements
- LBNF LCW fill system from MI added
- System now uses one primary pump with one hot spare

# System Operational Scope

- Provide LCW cooling
  - LBNF magnets downstream of Q203
  - LBNF magnet power supplies in LBNF – 5
  - Horn power supplies in LBNF – 20
  - Water cooled bus
- Manage dipole bus routing and hydraulics
  - System does not include cable-connected magnets
  - System does not include bus-to-magnet connections (flags)
  - Includes pump room bus shielding
- Provide LCW makeup for RAW room

# System Design Requirements

- Meet previously described operational goals
- Require minimal unscheduled interventions
- Meet established lab practices for flow and capacity
- Operate over a range of elevations determined by CF
- Use pond water for cooling and MI LCW for fill
- Conform to ASME B31.3 and FESHM 5031.1

<b>Fluid</b>	<b>Low Conductivity Water</b>
<b>Resistivity</b>	<b>9M<math>\Omega</math>·cm or better</b>
<b>Nominal Temperature</b>	<b>95°F</b>
<b>Radioactivity</b>	<b>&lt; 1900 pCi/ml</b>
<b>MAWP</b>	<b>200 psig</b>


# Component Summary

- 41 water cooled magnets – 502 GPM, 477 kW
  - 2 QQU - Q60 Quadrupoles
  - 15 QQB - 3Q120 Quadrupoles
  - 12 IDA Dipoles
  - 12 IDD Dipoles
- 24 power supplies – 228 GPM, 178 kW
  - 15 quadrupole power supplies
  - 7 dipole power supplies
  - 2 horn power supplies
- 4,612 feet of 2"x2" dipole bus – 95 GPM, 193 kW
  - 5 pairs of bus

# Flow Requirements

- Sum of est. flows: 895 GPM
- With 5% contingency: 940 GPM
  - Horn PS flow may be over-estimated
- Fathom model: 124 BHP
  - 135 HP motor req. at 92% Efficiency
- 150 HP 900 GPM Flowserve Pump
  - 72% efficiency @ 908 GPM
  - 109.3% of BEP
  - 37.4 ft. NPSHA, 24.1 ft NPSHR


	Flow Required
<b>Magnets</b>	502 GPM
<b>Magnet Power Supplies</b>	128 GPM
<b>Dipole Bus</b>	95 GPM
<b>Horn Power Supplies</b>	100 GPM
<b>Filtration Allowance</b>	50 GPM
<b>RAW Room Fill</b>	20 GPM
<b>5% Contingency</b>	45 GPM
<b>Estimated System Flow</b>	<b>940 GPM</b>



# Flow Requirements

- All magnets 100 psi dP or higher
- Using full dipole flows
  - Only 2/3 may be required

Magnet Type	Required flow
QQB - 3Q120 Quad	6 GPM
QQU - 3Q60 Quad	8 GPM
IDA Dipole	15 GPM
IDD Dipole	18 GPM



Detail view of magnets after beamline crest from "PDF of Fathom Model Indicating Fluid Flows" in DUNE DocDB Doc. #16706

**PIPE UNITS**  
P Max= psig

**COLORS**  
Volumetric Flow Rate (gal/min)

- $\geq 50$
- $\geq 35$
- $\geq 24$
- $\geq 18$
- $\geq 15$
- $\geq 8$
- $\geq 6$
- $> 0$



# Fluid Velocity

Pump Outlet	5.3 ft/s
Vehicle Access Headers	6.4 ft/s
Upstream Supply Header	8.4 - 3.8 ft/s
Downstream Supply Header	5.9 - 2.3 ft/s
Upstream RR Header	5.9 ft/s
Downstream RR Header	8.4 ft/s


**PIPE UNITS**

P Max= psia  
V= feet/sec  
Q= gal/min

**COLORS**


Velocity (feet/sec)

- > 10
- > 8
- > 7
- > 6
- > 5
- > 4
- > 3
- > 2
- > 1
- > 0



Detail view of LCW supply piping at tunnel alcove from "PDF of Fathom Model Indicating Fluid Velocities" in DUNE DocDB Doc. #16706

# System Pressures



**PIPE UNITS**

P Max= psia  
V= feet/sec  
Q= gal/min

**COLORS**

Pressure Static Maximum (psia)

- > 200
- > 180
- > 160
- > 140
- > 120
- > 100
- > 80
- > 60
- > 40
- > 20

<b>MAWP</b>	<b>200 psig</b>
<b>Expansion Tank</b>	15 psig (N <sub>2</sub> )
<b>Pump Inlet</b>	2 psig
<b>Pump Outlet</b>	170 psig
<b>Max Pressure</b>	178 psig

<b>Magnet dP</b>	109-140 psi
<b>Magnet PS dP</b>	60 psi
<b>Horn PS dP</b>	50 psi

Detail view of LCW supply piping at upstream end of tunnel from "PDF of Fathom Model Indicating Fluid Pressures" in DUNE DocDB Doc. #16706

# Heat Dissipation


- **Nominal fluid temp: 95 °F**
- Heat exchanger  $\Delta T$ : 9.1°F
- Magnets  $\Delta T$ : 1.4°F – 11.5°F
- Power supplies  $\Delta T$ : 0.9°F – 9.1°F
- Dipole bus  $\Delta T$ : 7°F – 22.8°F
- **Max fluid temp: 118°F**
  - Occurs in longest bus run
  - Does not account for air cooling

	Dissipated Power
Magnets	477 kW
Magnet Power Supplies	103 kW
Dipole Bus	193 kW
Horn Power Supplies	60 kW
10% Contingency	83 kW
Pump BkW to LCW	97 kW
<b>Total kW Dissipated:</b>	<b>1,013 kW</b>
<b>Selected HX Size</b>	<b>1,200 kW</b>

Pump Motor Heat Dissipation	
Pump Motor Horsepower:	150
Pump Motor Power in kW:	111.9
Pump Motor Efficiency:	90%
Heat Loss into Room (kW):	11.2
VFD Heat Dissipation	
Pump Motor VFD Horsepower:	150
Pump Motor VFD Power in kW:	111.9
Pump Motor VFD Efficiency:	93%
Heat Loss into Room (kW):	7.8
<b>Total Heat Loss into Pump Room:</b>	<b>19 kW</b>

# System Capacities

		Fluid Volume
1	Service Building & Pipes to Tunnel	2,721 Gal.
2	Magnets Upstream of Service Building	622 Gal.
3	Magnets Downstream of Service Building Before Crest	538 Gal.
4	Magnets Downstream of Service Building After Crest	266 Gal.
5	Target Hall and Piping Leading to Target Hall	195 Gal.
<b>Total System Volume:</b>		<b>4,342 Gal.</b>



# ASME B31.3/FESHM 5031.1 Compliance

- 8" straight pipe @ 200 psig  $t_{\text{required}} = 0.054"$
- 6" curved access corridor pipes @ 200 psig  $t_{\text{required}} = 0.041"$
- 8" sch. 10 304/304L pipe  $t_{\text{actual}} = 0.138"$ , 2.5x thicker than required
- 6" sch. 10 304/304L pipe  $t_{\text{actual}} = 0.134"$ , 3.2x thicker than required
- Only listed tees, junctions, valves, etc. will be used
  - Class 150 Flanges are sufficient

# System Design Requirements

- Meet previously described operational goals
- Require minimal unscheduled interventions
- Meet established lab standards for flow and capacity
- Operate over a range of elevations determined by CF
- Use pond water for cooling and MI LCW for fill
- Conform to ASME B31.3 and FESHM 5031.1

<b>Fluid</b>	<b>Low Conductivity Water</b>
<b>Resistivity</b>	<b>9M<math>\Omega</math>·cm or better</b>
<b>Nominal Temperature</b>	<b>95°F</b>
<b>Radioactivity</b>	<b>&lt; 1900 pCi/ml</b>
<b>MAWP</b>	<b>200 psig</b>