





High-Charged Magnetized Beams at FAST-IOTA [MagBeam]

Northern Illinois University: A. Fetterman*, C.

Marshall*, P. Piot

Fermilab: J. Ruan

Collaborators at JLab: S. Benson, J. Gubeli,

F. Hannon, S. Wang

^{*} Graduate students

funded proposal to DOE NP



- T1: High-charge magnetized beam:
 - Production of high-charge (1.6 and 3.2 nC) magnetized beam
 - characterization of magnetization
 - Transport + manipulation over long beamline including use of locally non-symmetric optics
- T2: Understanding halo
 - Explore halo formation in magnetized beam using a longdynamical range diagnostics (LDRD)
- T3: New merger concept:
 - Tests of merger concept combining RF deflector and magnetic coil proposed by G. Krafft and A. Hutton -augmenting recent test at Cornell.

Some encouraging results produced during run I, but poor data quality for publication

Initially planned for run II now moved to run III


Initially planned for run III now moved to another facility (DOE approved)



Relevance of FAST injector to EIC e- cooling



 Similar beam parameters except for a higher peak current




Parameter	Unit	JLEIC	FAST
Beam Energy	MeV	[20,55]	45
Beam Charge	nC	3.2/1.6	>3.2
cath. spot size	mm	1.1	1
B field on cath.	T	0.05	< 0.09
cyclotron emitt.	μ m	≤ 19	< 5
drift emitt.	μ m	36	37
$\delta p/p$ (uncor.)	-	3.10^{-4}	$< 4.10^{-4}$
$\delta p/p$ (pk-to-pk.)	-	$<6.10^{-4}$	$O(10^{-4})$
bunch length σ_z	cm	2	0.2


Fermilab








- Significantly improved bunch charge:
 - Emission was space-charge-limited
 - Increasing spot size resulted in bunch charge up to 6 nC
- Produced and transported a magnetized beam up to the low energy dump:
 - Characterized magnetization and other beam parameters
- Produced a flat beam:
 - Measured associated emittance (which corresponds to the incoming magnetized beam eigen emittances)
- Limitations:
 - Emittance measurement of eigenemittance could not be performed precisely due to movable slit issues
 - We could not trust the ICT
 - Laser inhomogeneity













Outcomes and Summer Improvements and Summer Improvemen


- Issue with single-slit scan was fixed (Daren, Jinhao) and analysis (Aaron) shows is could be used for emittance measurement
- Improved analysis of data is encouraging

RFTB Eigen-Emittances

Paramters	units	
ε_+	$\mu\mathrm{m}$	$32.5{\pm}2.9$
arepsilon	$\mu\mathrm{m}$	$2.2{\pm}1.9$
ε_u (calc.)	$\mu\mathrm{m}$	8.2±.4
\mathcal{L} (calc.)	$\mu\mathrm{m}$	15.2 ± 1.5


Cathode Magnetization

Paramters	units	
Magnetization	$\mu\mathrm{m}$	13.9 ± 6



X107V In/ vs X107V Out/

(a) Vertical X107 Slits




(c) Vertical X118 Slits


Shearing Magnetization

Paramters	units	Data Set 1	Data Set 2	
Magnetization	$\mu\mathrm{m}$	31.8 ± 4.9	37.8 ± 3.3	
Cathode Magnetization				

Paramters	units	Data Set 1	Data Set 2	
Magnetization	$\mu\mathrm{m}$	$26.3 {\pm} 8.7$	23.8 ± 10.2	



(b) Horizontal X107 slits



(d) Horizontal X118 Slits


(analysis from Aaron Fetterman)

Simulation using realistic experimental conditions reproduce some of the experimental feature (A. Fetterman et al. NAPAC19)

Fermilab

INCREDE TO ACCEPTATOR AND DETECTION DEVELOPMENT

- Optimization done for idealized laser distribution
- Impact of non-ideal distribution is explored via simulation







Proposal (phase I: 4 shifts)


NORTHERN BLUCKS GRIFTS FOR ACCULARIOR RAN BLUCKS OR ACCULARIOR RAN BLUC


- Shift 1: essentially reproduce settings of run 1 (FEB/MAR):
 - Vary solenoid and monitor vacuum (processing)
 - Test all diagnostics and especially all the scanning single slits diagnostics
- Shifts 2-4 (contiguous): 1.6 and 3.2-nC magnetized beam characterization
 - Measure magnetization, eigen emittances,
 - Perform parametric studies for a few cases: several laser-spot radii. Ratio of Bmain and Bbuck
 - Take data to compare the two eigen-emittance measurement methods












Proposal (phase II: 2 shifts)



- Shift 5-6: beam transport to downstream cryomodule (assuming all data of phase I have been collected)
 - Transport through cryomodule (ideally with cryomodule eventually off)
 - Generation of a "skew" flat beam with Q441-3
 - Measure beam magnetization downstream of cryomodule and injector values.
 - If times allows study propagation of magnetized beams in a non-locally but globally symmetric beamline

Flat beam generated using Q441-3 quads and observed in the 450 area



!!! Beam termination: not sure on its way to HE dump (is it acceptable with up to 10 bunches (total Q~50 nC over macropulse?)

Personnel + TODO list



• Shift personnel:

- Shift 1: local people (NIU include A. Fetterman and P. Piot)
- Shift 2, 3, and 4: Jlab personnel will join (list to be finalized once we have possible dates)
- Shift 5, 6: locals only (TBC) will likely include NIU's C. Marshall, A. Fetterman and P. Piot.

Data acquisition/analysis

 Tools are mostly ready and will enable some preliminary on-line analysis to guide experiment

• Hardware:

- Check CCD focus at slit locations [Aaron]
- Deploy/test RCDS algorithm for fast on-line flat beams optimization [Philippe]
- Ability to change the laser spot size between 2 to 4 mm (full radius) if not what is possible?
- Are the ICTs OK?