



121.06 – Requirements Flow Down

S. Dixon, Level 2 Manager

DOE CD-2/3a Independent Project Review

SC4 – Conventional Facilities

January 29, 2020

A Partnership of:

US/DOE

India/DAE

Italy/INFN

UK/UKRI-STFC

France/CEA, CNRS/IN2P3

Poland/WUST



About Me

- PIP-II Level 2 Manager for Conventional Facilities
- Relevant Experience
 - Licensed Architect;
 - Project Management Professional (PMP);
 - LEED Accredited Professional;
 - 27+ years at Fermilab;
 - NOvA Project L2 Manager for Site and Buildings;
 - 2014 CD-4
 - 2015 U.S. DOE Secretary's Award for Excellence
 - General Plant Project Manager for 17+ years
 - Short Baseline Neutrino (SBN) Near Detector Building;
 - Short Baseline Neutrino (SBN) Far Detector Building;
 - Experimental Operations Center;

Outline

- Performance Requirements
- Technical Requirements
- Interfaces
- Space Allocation
- CAD Flow Down to CF
- Summary


1. Does the proposed technical design satisfy the performance requirements? Do the Key Performance Parameters (KPP's) provide a satisfactory indication of the project's completeness?
2. Are the interfaces to the existing accelerator complex identified and defined? Do the planned hardware upgrades to the existing complex fully support the ultimate performance goal of 1.2 MW operation of the complex?
3. Is the resource-loaded schedule complete, consistent and credible so that it can serve as the cost and schedule part of the project's performance baseline? Is it compatible with the funding guidance provided by High Energy Physics? Have the project's risks been fully analyzed and accounted for in the contingency estimate?
4. Is the project team properly staffed with individuals that have the required skills to deliver the proposed technical scope within the baseline budget and schedule?
5. In-kind international contributions are described in bi-lateral agreements called Project Planning Documents (PPD's). Does the project baseline and in-kind scope contributions defined in the PPD's present the complete scope required to meet the KPP's? Are the delivery dates for in-kind scope sufficiently understood to establish the credibility of CD-4 date? Does the Project have a credible plan for managing the deliverables including acceptance, Q/A, and risk management.
6. Does the project have a certified Earned Value Management System and have they demonstrated their ability to utilize it as an effective project management tool?
7. Is the documentation required by DOE Order 413.3B, *Program and Project Management for the Acquisition of Capital Assets* for CD-2 complete and in good order?
8. Are Environment Safety and Health aspects being properly addressed?
9. Has the project responded satisfactorily to the recommendations from the previous independent project review?
10. In regard to CD-3a; is the scope of the 3a package appropriate and justified? Are the associated designs sufficiently mature to support the requested CD-3a cost and schedule? Have the appropriate design reviews been completed?

Performance Requirements

- Requirements flow from the Global Requirements to Physics Requirements to Functional and Technical requirements;
- Requirements are supported by Interfaces and Room Data Sheet;

5 out of 30 L3 FRS's apply to Conventional Facilities (one for each L3 WBS)

104 out of 745 total interfaces involve Conventional Facilities (all interfaces are documented in the PIP-II Master ICD)



Teamcenter documents are located in PIP-II-doc-2492

	Site Preparation	Cryogenics Plant Building	Utility Plant	Linac Complex	Booster Connection
	121.06.02	121.06.03	121.06.04	121.06.05	121.06.06
Functional Requirement Specification	ED0006787	ED0006718	ED0006748	ED0008043	ED0006794
	Complete	Complete	Complete	Complete	Complete
Technical Requirement Specification	ED0006789	ED0006719	ED0006749	ED0010906	ED0006795
	Complete	Complete	To Be Updated	In Progress	To Be Updated

Technical Requirements

Room Data Sheet ^[1]

- Information is collected/organized by Linac Installation and Commissioning subproject (F. G. Garcia, 121.04)
- Organizes Equipment Requirements:
 - Spatial (size, height, quantity)
 - Electrical (type, voltage, UPS)
 - Cooling (LCW, heat load to air)
 - Cabling
 - Communication
 - Safety issues (electrical, X-Rays, ODH)
 - Estimate Uncertainty
- First Signed Off in January 2019
- Updated in September 2019 based on baseline change requests and transferred management to Technical Integration Team

[1] See Teamcenter document ED0009544 and PIP-II-doc-4408

Technical Requirements – Room Data Sheet




Room Data Sheet PIP-II

-> Enter only relevant fields for items that take up floor space, require environmental control, cooling water, AC power, a rack, or networking.

-> If equipment does not extend beyond the rack, it does not need to be included. Including cables will allow us to determine equipment location based on access to power or networking.

-> If multiple cable types run to the same rack, select the least flexible cable type going to the rack and provide the total number of all cables.

-> Columns D/H have a "red triangle" in the right-hand corner - hover the mouse over them to view additional information.



High Bay Building
HBB-lower - WFE

- N/A = Denotes missing information
- These cells are automatically calculated, no input required
- Data cells not applicable

Automatic filled out cells **Start Here** ↓

Identif	VBS Level 2	VBS ID	VBS Name	Building	Space Designation Location	Sub-System	User Defined Sub-System	Component	Description	Quantity	Level of Design	Source of Requirements	Uncertainty Multiplier	Spatial Requirements				Floor Requirements						
														Space Type	Length (in)	Width (in)	Height (in)	Weight (lbs)	Floor Flatness	Vibration	Finishes			
DM-001	121.03	12103.07	Controls	LG	LG-BTL	Computers, Front End		Racks	Networking, permits etc.	3	Preliminary	Off the Shelf	5%	Floor	30	24	60			Sealed concrete	65	-/+		
DM-002	121.03	12103.08	SS	LG	LG-BTL	Interlocks		Racks	ESS Interface	1	Preliminary	Off the Shelf	5%	Floor	30	24	36			Sealed concrete	65	-/+		
DM-003	121.3	1213.06	Controls	F3	BTL-F3 Building	PLC/LCV Controls		Racks, Rittal	Rittal half size cabinet	1	Preliminary	Off the Shelf	5%											
DM-004	121.03	12103.06	Vacuum	F3	BTL-F3 Building	Ion Pump PS System		Racks	Bulk, Ion pump PS, gauge interface,	2	Preliminary	Off the Shelf	5%	Floor	30	24	60			Sealed concrete	65	-/+		
DM-005	121.03	12103.09	Instrumentator	LG	LG-BTL	BPM		Racks	BPM	2	Preliminary	Prototype-Testing	25%	Floor	30	24	60			Sealed concrete	65	-/+		
DM-006	121.03	12103.09	Instrumentator	F3	BTL-F3 Building	BPM		Racks	BPM	1	Preliminary	Prototype-Testing	25%	Floor	30	24	60			Sealed concrete	65	-/+		
DM-007	121.05	12105.04	BTLBAL	LG	LG-BTL	Collimator Controls		Racks	will this be needed??	1	Preliminary	Off the Shelf	5%	Floor	30	24	60			Sealed concrete	65	-/+		
DM-008	121.03	12103.05	Magnets	F3	BTL-F3 Building	Fast Dipole Switch		Racks	Pulse Magnet Power Supply	1	Conceptual	Expert Opinion	50%	Floor	30	24	60			Sealed concrete	65	-/+		
DM-009	121.03	12103.05	Magnets	LG	LG-BTL Power Supply	Fast Dipole Switch		Cables	Fast Dipole Switch	8	Preliminary	Prototype-Testing	25%											
DM-010	121.03	12103.05	Magnets	LG	LG-BTL Power Supply	Fast Dipole Switch		Magnets	Fast Dipole Switch	1	Conceptual	Expert Opinion	50%											
DM-011	121.03	12103.05	Magnets	F3	BTL-F3 Building	Magnets, Dipole		Power Supplies	TeV PS	1	Preliminary	Expert Opinion	50%	Floor	60	24	96	3500			Sealed concrete	65	-/+	
DM-012	121.03	12103.05	Magnets	Booster		Magnets, Dipole		Power Supplies	125kV Spange PS	2	Preliminary	Off the Shelf	5%	Floor	62	44	89	2500			Sealed concrete	65	-/+	
DM-013	121.03	12103.05	Magnets	BTL	BTL-Beamline Tunnel	Magnets, Dipole		Cables	Dipole cables	20	Preliminary	Off the Shelf	5%											
DM-014	121.03	12103.05	Magnets	BTL	BTL-Beamline Tunnel	Magnets, Dipole		Cables	Dipole cables	16	Preliminary	Off the Shelf	5%											
DM-015	121.03	12103.05	Magnets	F3	BTL-F3 Building	Magnets, Regular Quadupole		Racks	Quadupole Power Supplies	3	Preliminary	Off the Shelf	5%	Floor	30	24	90			Sealed concrete	65	-/+		
DM-016	121.03	12103.05	Magnets	BTL	BTL-Beamline Tunnel	Magnets, Regular Quadupole		Cables	Quad Cables	32	Conceptual	Off the Shelf	5%											
DM-017	121.03	12103.05	Magnets	BTL	BTL-Beamline Tunnel	Magnets, Regular Quadupole		Magnets	Magnets	57	Conceptual	Prototype-Testing	25%								Sealed concrete	65	-/+	
DM-018	121.03	12103.05	Magnets	BTL	BTL-Beamline Tunnel	Magnets, Regular Quadupole		Magnets	Booster in C Mag	1	Preliminary	Prototype-Testing	25%								Sealed concrete	65	-/+	
DM-019	121.03	12103.05	Magnets	F3	BTL-F3 Building	Magnets, Dipole Corrector		Racks	CE Dipoles	3	Preliminary	Off the Shelf	5%	Floor	30	24	90			Sealed concrete	65	-/+		
DM-020	121.03	12103.05	Magnets	BTL	BTL-Beamline Tunnel	Magnets, Dipole Corrector		Cables	Cables	56	Preliminary	Off the Shelf	5%								Sealed concrete	65	-/+	
DM-021	121.03	12103.05	Magnets	BTL	BTL-Beamline Tunnel	Magnets, Dipole Corrector		Magnets	Magnets	56	Preliminary	Off the Shelf	5%								Sealed concrete	65	-/+	
DM-022	121.05	12105.04	BTLBAL	BAL Area	BAL-Beam Absorber	RAV Absorber		Pumps	Pumps	1	Preliminary	Prototype-Testing	25%											
DM-023	121.05	12105.04	BTLBAL	BAL Area	BAL-Beam Absorber	RAV Absorber		Racks	Controls	1	Preliminary	Prototype-Testing	25%											
DM-024	N/A	N/A	Upgrades	LG	LG-Upgrade	RF-Sep- HPRF		Power Amplifiers	SCL SS-70kV style	1	Pre-conceptual	Expert Opinion	50%	Floor	96	134	96						40-80	
DM-025	N/A	N/A	Upgrades	LG	LG-Upgrade	RF-Sep-Magnets, Vert. Dip.		Racks	Need 2 vert. dip. corrector (SCL dip.)	1	Pre-conceptual	Expert Opinion	50%	Floor	32	24	96		No				78	-/+
DM-026	N/A	N/A	Upgrades	LG	LG-Upgrade	RF-Sep-Magnets, Vert. Dip.		Power Supplies	Need 2 vert. dip. corrector (SCL dip.)	2	Pre-conceptual	Expert Opinion	50%										78	-/+
DM-027	N/A	N/A	Upgrades	LG	LG-Upgrade	RF-Sep-Magnets, Lambertson		Racks	Need 3 (SCL quad-style PS)	1	Pre-conceptual	Expert Opinion	50%	Floor	32	24	96		No				78	-/+
DM-028	N/A	N/A	Upgrades	LG	LG-Upgrade	RF-Sep-Magnets, Lambertson		Power Supplies	Need 3 (SCL quad-style PS)	3	Pre-conceptual	Expert Opinion	50%										78	-/+
DM-029	N/A	N/A	Upgrades	LG	LG-Upgrade	RF-Sep-Spang		Power Supplies	75kV Spange PS	5	Preliminary	Off the Shelf	5%	Floor	31.5	24	51	645			Sealed concrete	65	-/+	
DM-030	N/A	N/A	Upgrades	LG	LG-Upgrade	RF-Sep-Magnets, BLQuads		Racks	Need 8 Quad PS - SCL quad-style PS	2	Pre-conceptual	Expert Opinion	50%	Floor	32	24	96		No				78	-/+
DM-031	N/A	N/A	Upgrades	LG	LG-Upgrade	RF-Sep-Magnets, BLQuads		Power Supplies	Need 8 Quad PS - SCL quad-style PS	8	Pre-conceptual	Expert Opinion	50%										78	-/+
DM-032	N/A	N/A	Upgrades	LG	LG-Upgrade	RF-Sep-ELVac		Racks	Rack Contains all Ion Pump Controllers,	1	Pre-conceptual	Expert Opinion	50%	Floor	24	32	96						78	-/+
DM-033	N/A	N/A	Upgrades	LG	LG-Upgrade	RF-Sep-ELVac		Power Supplies		1	Final	Off the Shelf	5%	Rack Mounted									78	-/+



Interfaces

Interfaces

Charge #2

- Interfaces are defined and controlled at the following levels:
 - PIP-II to Fermilab Accelerator Complex;
 - L3 to L3;
 - Partner interfaces (Partner to Fermilab, Partner to Partner);
 - Any level at the discretion of the L2M (Design Authority).
- Single database → [Master ICD](#) (MICD) - 746 interfaces;
- All interfaces are managed utilizing Teamcenter® workflow. Integration Coordinator manages the database;
- Periodic Master ICD self-assessment by L3MS is conducted;
- Integration Coordinator releases updates to MICD monthly;
- PIP-II Interface Management Plan is documented
 - Teamcenter® document ED0007942 ([PIP-II-doc-3232](#))



Interfaces



Fermi National Accelerator Laboratory

PIP-II Interface Management Plan

Document number: ED0007942

Document Approval

Signatures Required	Date Approved
Originator: Integration Team	Approved in Teamcenter
Approver: Alex Martinez, Integration Coordinator	Approved in Teamcenter
Approver: Allan Rowe, Project Engineer	Approved in Teamcenter
Approver: Arkadiy Klebaner, Technical Director	Approved in Teamcenter

Revision History

Revision	Date of Release	Description of Change
-	7/12/2019	Initial Release

Note that the Integration Coordinator may determine that the requested interface change exceeds a certain threshold as described in the PIP-II Configuration Management Plan [7] which requires referral to the Design Change Board (DCB) for further action. These are typically changes that impact technical scope across multiple L2 systems, impact cost and/or schedule or exceeds a monetary threshold.




Figure 8-1. Interface Management Flow Chart

8.2. Interface Update

Since an Interface Update consists of a non-critical update to an interface, the update is made directly to the Master ICD document and the change noted on the Revision List. No additional stakeholders need

Interfaces

PIP-II Master Interface Control Document (ICD) List


Warning: This ICD is subject to change. The current version is maintained in Teamcenter (ED0010433).

Search Criteria											
System A WBS	System B WBS	Integrator WBS	749 ←←← Number of entries satisfying this search criteria.								
121.6.05 Cmplx											
	121.6.05 Cmplx										
		121.6.05 Cmplx									
Unique L3-L3 ID	Interface #	Interface ID	Interface Name	Interface Requirements Description	Requirements Clarification	Verification Method	System A WBS	System A Scope	System B WBS	System B Scope	Inte
1764	001	1764-001	HWR CM cryogenic process piping (CPP)	Cryogenic process piping (CPP) shall connect the HWR to the CDS to deliver helium cryogenic cooling to various HWR Cryomodule process circuits as required. CPP also includes insulating vacuum with vacuum barriers, alignment and installation of CPP, and acceptance testing	HSIB shall connect the HWR to the CDS to deliver helium cryogenic cooling to various HWR Cryomodule circuits as required. The interface consists of a cryogenic bayonet connection for each of the cryogenic circuits, pressure gauges and LHe level probes	Inspection; Demonstration; Measurement; Analysis	121.2.02 HWR	HWR shall specify helium operating and design parameter requirements at the interface. CDS and HWR shall define geometry, location, and alignment requirements of connections	121.2.06 CDS	CDS shall provide interconnect U-tubes to HWR Cryomodule bayonets for each process circuit, and supply helium to HWR requirements.	121.
1764	002	1764-002	HWR CM warm helium piping	HWR requires helium vent headers for CM relief devices and purge and mixing helium for helium guard and warm-up	The interface consists of a relief system connected to the HWR.	Inspection; Measurement; Analysis	121.2.02 HWR	HWR shall specify helium purge gas and pressure safety requirements for CM devices, and supply appropriately sized relief piping within the CM and external connections to CDS warm helium headers	121.2.06 CDS	CDS shall size relieving system based on pressure safety requirements specified by HWR, and supply relief devices and headers which mate to the CM external connections	121.
1764	003	1764-003	HWR Cryogenic Controls	The CDS cryogenic control system shall integrate HWR CM devices and provide controls and signal readback for HWR instrumentation and heaters and interface with the global control system		Inspection; Demonstration	121.2.02 HWR	HWR shall specify control devices to be included in the CDS cryogenic control system and requisite details for integration into CDS controls	121.2.06 CDS	CDS shall provide the cryogenic control system	121. 121. 121.
1764	005	1764-005	HWR CM Thermometry	HWR CM Thermometry interface shall include information about		Inspection; Demonstration; Measurement	121.2.02 HWR	HWR shall provide specification of	121.2.06 CDS	CDS shall review and approve specifications	121.

Current version can be found in PIP-II-doc-2492

Space Allocation

Integrated 3-D Model is being utilized



- Automated lattice import implemented;
- Data exchange procedure with lattice and Conventional Facility is documented;
- Coordinated by the Integration Coordinator, Installation L3, and Conv Fac L2 Manager.

31 Jan 28, 2020

Klebaner | Design Status and Technical Integration | Plenary



From A. Klebaner's Plenary talk





Space Allocation


Space Allocation

- Allocation of space within the Linac Complex (tunnel, gallery, support buildings, etc.) requires detailed coordination between the various stakeholders:
 - space requirements;
 - stay clear envelopes;
 - accessibility for egress;
 - Installation and maintenance.


Managed by Integration Coordinator, L3 Installation, and L2M Conv Fac



CAD flowdown to CF




CAD flowdown to CF




Not-to


ata
by FNAL





CAD flowdown to CF



CAD flowdown to CF



Example



Summary

- Room Data Sheets provides the technical requirements
- CAD model integration provides the spatial configuration of technical components
- Interface control manages connections to other systems

- Processes in place for:
 - Configuration control of Room Data Sheets
 - Transfer of CAD model to CF
 - Interface control