


SRF at ANL: Progress and Plans

February 2, 2009

Speaker: Mike Kelly



ANL SRF Activities

ATLAS Upgrade

- 7-cavity upgrade cryomodule nearing completion
- Goal to increase ATLAS voltage by 30% in a single 5-meter module
- Demonstration of technology for next generation linacs for protons and heavy-ions

- Considerable progress on cavity processing since ~Nov. 08
- All essential steps for cavity processing/assembly are operational

HINS/Project X


- ANL participation in ongoing R&D (single spokes SSR1-01,02)
- ANL has strong interest in working with FNAL on the front end for Project X

■ FRIB

- MSU selected as site in Dec. 08
- Level of ANL participation in SRF for FRIB unclear







Facilitates simplified assembly

Top loading box cryomodule

Equally suitable for spokes, half-waves, quarter-waves



HINS: A pair of single spoke cavities processed at ANL




- Performed chemical polishing, high-pressure rinsing in G150 (good results for SSR1-01)
- Basis for a more formal and broad based collaboration to include design, fabrication, assembly and testing



Common need in SRF community for cavity diagnostics: Second sound measurements

Heat pulse

2nd sound signal









- Good signal-to-noise, time resolution in 6" test dewar
- Ready for test with cavities


Germanium detector mounted on a 6 ft dewar insert (Z. Liu)



ILC: Cavity processing at Argonne











Ultrasonic Cleaning




Electropolishing parameters for single cell cavity (TE1ACC002, Jan. 29, 09)







Recent single-cell results (fabricated at AES and Niowave)



Limited by available rf power at 33 MV/m

Limited by quench at 27 MV/m

ANL/FNAL should demonstrate at least a few good single cell results before proceeding with nine cell cavities



Present FY09 manpower for ILC at joint ANL/FNAL Facility

Present ANL Manpower

- 1.25 FTE total (S. Gerbick, M. Kelly @ 50% for remainder FY09)
 - 4 electropolishing procedures so far this year (2 last week)
 - 2 procedures end of Feb/beginning of March
 - 2-3 EP/month through April 09 Sept. 09
 - ~17 total EP procedures for FY09

■ Present FNAL Manpower

- 1.5 FTE
 - FNAL leading the clean room work
 - FNAL personnel are being trained on electropolishing

Manpower is ample for the next couple months

I believe the effort should be expanded to ~2 FTE each at ANL and

FNAL by the end of FY09



Summary/Plan

- ANL will install a SC cavity upgrade cryomodule into ATLAS this March
 - Technological basis for the next generation of proton and heavy ion linacs
- Joint ANL/FNAL processing facility in reasonably good shape to deliver cavities for ILC cold test program
 - No Accidents
 - Should ramp up manpower (2 FTE each lab ~full time)
 - Spares, reserve components should be obtained ASAP in order to sustain full time operations
- HINS/Project X collaboration in single spoke cavities
 - ANL participation should be broad based and go beyond processing
 - ANL has strong interest in the 420 MeV front end; requires a quick start to triple-spoke prototyping
- Work together on cavity diagnostics?

