POSIPOL-2013 workshop in ANL (USA), 2013.09.04

SuperKEKB e⁺ source

design considerations and construction status

Takuya Kamitani (KEK)

SuperKEKB Injector & e+ source



(1) TARGET

target offset & beam hole



- injection e- beam on axis to preserve low emittance
- primary e- beam 2~3 mm off axis
 - (target offset 3.5 mm, FC offset 2.0mm)
 - e+ yield degradation by this offset ~ 10%

target destruction issue

PEDD & Y(e+) vs. e- spot size on target



We enlarge design spot size to 0.7 mm for safety margin of factor 2.

target protection



- beam spoiler to maintain spot size σ_x,σ_y> 0.7 mm on target
 avoid too small beam spot on spoiler & on target, need monitoring spot sizes and focusing magnet settings
- distance D & thickness t should be optimized considering beam line layout
- at a position D = 3.0 (m), t = 0.5 (mm) for AI plate

(2) CAPTURE SECTION

Why we gave up L-band

Iarger transverse/longitudinal acceptance with L-band ?

- overall acceptance predominantly limited by the downstream beam-line acceptance
- Large aperture S-band structure can give comparable acceptance
- satellite particle elimination with co-prime (1298:2856мнz = 5:11) frequency relation ? [satellites make radiation problem at DR injection]
 - S-band high-gradient deceleration can give sufficient satellite elimination
- solenoid gaps for wide L-band wave-guides make deep field dip and significant beam loss
 - Helmholtz-like configuration can avoid field dip, however power consuming

deceleration capture [1]



deceleration capture [2]



deceleration capture [3]



deceleration capture [4]

low-grad. decelaration makes satellite particles in drift space.

in drift space

10 MV/m, Acc. Phase 80 10 MV/m, Dec. Phase 80 14 MV/m, Dec. Phase Kinetic Energy [MeV] z [mm] Animation by F. Miyahara 2nd Acc 1st Acc

satellite fraction vs. field gradient



Deceleration field grad. above 14 MV/m preferred for satellite elimination !

(3) FLUX CONSENTRATOR DEVELOPMENT

Flux Concentrator

- SLAC/IHEP-type spiral-slit FC is fabricated for SuperKEKB
- discharging wire cutting at KEK for slit processing





SLAC/IHEP-type FC	parameters
length	100 mm
outer diameter	100 mm
inner diameter (min.)	7 mm
inner diameter max)	52 mm
peak current (for SKB)	12 kA
pulse width	5 us (half-sine)
peak field	3.9 T
inductance	1.0 uH

POSIPOL workshop in ANL (USA) 2013 September 4,

"SuperKEKB e+ source" by Takuya Kamitani

FC test stand

- FC prototype operation started in 2013 Feb.
- Iow current operation (1.36 kA) in the air for field measurement
- high current operation (~6 kA) successful with no breakdown
- full-current (12 kA) operation with new modulator in 2014 Apr.





FC assembly

- FC assembly (FC +target + bridge-coils + steering-coils+ vacuum-chamber) in fabrication, completed in 2013 Sep.
- beam-line installation in 2013 Nov.
- beam commissioning at half-current (6kA) start in 2013 Dec.
- operation at test stand at full-current (12 kA) in 2014 Apr.
- beam commissioning at fullcurrent in 2014 Sep.



(4) CONSTRUCTION STATUS

Construction in progress







- Construction of capture section started.
- Large aperture S-band structures and solenoids are carefully installed.

Summary on SuperKEKB e+ source

- 1) e+ generation at 3mm offset for on-axis e- passage in solenoids
- 2) beam spoiler for primary e- spot size >= 0.7 mm
- 3) all (large aperture) S-band capture section, no L-band
- 4) high gradient deceleration to eliminate satellite particles
- 5) SLAC/IHEP type flux concentrator prototype test and fabrication
- 6) **construction** of capture section in progress
- Linac stand-alone e- preliminary commissioning: 2013 Sept ~
- ♦ Linac stand-alone e+ preliminary commissioning: 2013 Dec ~
- Linac full-spec beam commissioning: 2014 Sep ~
- ♦ HER(e-) commissioing: 2015 Jan ~
- ◆ LER(e+) commissioing w/o DR: 2015 Jan ~
- DR+LER commissiong: 2015 May ~