JLab Plans for Integrated Cavity Processing (ICP)

Charles Reece

SRF Materials Mtg, February 2010

(Informal contribution)

<u>JLab SRF Strategic Interest for DOE</u> >> next 20 years

Continue to lead the way in applied accelerator cavity preparation development

- Performance
- Flexibility
- Efficiency
- Quality assurance

>> **ICP** is the label we apply to the means

Supporting this strategic interest requires ongoing

Process research

Process development with – single cell -> multi-cell structures

Deployment for standard use on multiple projects

Packaged tool specification for technology transfer

Local surface conditions
 Local process parameters

electrochemistry topography HPR

Building understanding in this domain is *research*.

Translating the current understanding into workable, desired application to cavities is *development*.

ILC 9-cells JLab upgrade VEP

Implementing an intentional tool that provides a reliable application process is *process engineering*.

ICP

Controlled production processing

SNS HB cavity vertical EP prototype attempt at JLab

- One step forward
- Used helium vessel as water cooling jacket
- Limited by available power supply current
- Management of hydrogen bubbles is the greatest challenge
- Labor intensive, and just one process step



J. Mammosser

We dream of something ten steps forward:

The next step, ICP:

We need confident <u>and</u> variable multi-parameter process control.

- ICP units will integrate VEP, BCP, HPR, US, and HWR in an automated tool in a clean environment.
- The concept is to leave the cavity stationary and bring the sequential processes to the cavity.



ICP will integrate multiple process steps with minimum handling



The Jefferson Lab TEDF Project is providing an appropriate facility envelope and necessary services for ICP units.

Technical and Engineering Development Facility (TEDF)

A major DOE infrastructure upgrade at JLab

- New home for Engineering Division
- New home for Physics Div. detector development
- All new technical work areas for SRF
- Full renovation of the Test Lab to LEED Gold standards

ferson Lab





TEDF Project Schedule

		4	Activity Name		FY 08			FY 09					FY 10				FY 11				FY 12			FY 13				FY 14				
		P		4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4
2		•	Critical Decisions	 (>			•	2				2	3	A	♦ 3B						4	A							4 E	3	
10			Engineering and Design																													
11			Early Construction																													
12			TED Building Construction																													
13			Test Lab Addition Construction																													
14			Test Lab Renovation																													
15			Schedule Contingency																													

TEDF will have the required process support infrastructure for multiple ICP units

Presently we are:

- Prototyping key interface elements
- Developing design requirements
- Soliciting partnerships with candidate toolmakers



