

# HQ Progress and Plan


Helene Felice

LARP Collaboration Meeting 14

April 26-28 2010

FNAL

- **Coil Fabrication status and plan**
  - Coil fabrication summary
  - Instrumentation
- **HQ01a Magnet**
  - Characteristics
  - Assembly
  - Cool-down
- **1 meter tests schedule**
- **2 meter extension**




# Coil Fabrication Status

Coil #	Cable number	Strand type	Gap during winding and curing	L1/L2 pinning	Reaction Potting	Status
1	992R	54/61	N	Y	LBL	HQ01a
2	992R	54/61	N	Y	BNL	HQ01a
3	991R	108/127	Y	Y	LBL	HQ01a
4	1000R	108/127	Y	Y	BNL	HQ01a
5	1000R	108/127	Y	N	BNL	instrumented
6	1000R	108/127	Y	Y	BNL	potted
7	1000R	108/127	Y	Y	LBL	reacted
8	996R	54/61	Y	Y	BNL	wound and shipped
9	996R	54/61			BNL	winding prep
10	996R	54/61			LBL	
11		108/127 Ti dopped			LBL	
12		54/61 Ta dopped 1 pass			LBL	


# FY10 coil fabrication schedule

<b>Coil 7</b>	<b>Mon 2/1/10</b>	<b>Thu 6/24/10</b>	<b>104 days?</b>
Coil 7 Wind/Cure	Mon 2/1/10	Mon 2/15/10	11 days?
Coil 7 React / Impreg LBL	Tue 2/16/10	Mon 6/7/10	80 days?
Coil 7 Instrum - Elec	Tue 8/8/10	Thu 6/24/10	13 days?
<b>Coil 8</b>	<b>Mon 3/29/10</b>	<b>Wed 8/25/10</b>	<b>108 days?</b>
Coil 8 Wind/Cure	Mon 3/29/10	Thu 4/15/10	14 days?
Coil 8 Shipping to BNL	Fri 4/16/10	Fri 4/23/10	6 days?
Coil 8 React / Impreg / Instrum BNL	Mon 4/26/10	Fri 7/9/10	55 days
Coil 8 shipping to LBL	Mon 7/12/10	Fri 7/16/10	5 days
Coil 8 Instrum - Elec	Mon 8/9/10	Wed 8/25/10	13 days
<b>Coil 9</b>	<b>Mon 4/19/10</b>	<b>Thu 10/21/10</b>	<b>134 days?</b>
Coil 9 Wind/Cure	Mon 4/19/10	Fri 5/7/10	15 days?
Coil 9 Shipping to BNL	Mon 5/10/10	Mon 5/17/10	6 days?
Coil 9 React / Impreg / Instrum BNL	Mon 7/12/10	Fri 9/24/10	55 days?
Coil 9 Shipping to LBL	Mon 9/27/10	Mon 10/4/10	6 days
Coil 9 Instrum - Elec	Tue 10/5/10	Thu 10/21/10	13 days?
<b>Coil 10</b>	<b>Tue 6/15/10</b>	<b>Thu 9/16/10</b>	<b>68 days?</b>
Coil 10 Wind/Cure	Tue 6/15/10	Mon 7/5/10	15 days?
Coil 10 React / Impreg LBL	Tue 7/6/10	Thu 8/26/10	38 days?
Coil 10 Instrum - Elec	Fri 8/27/10	Thu 9/16/10	15 days?
<b>Coil 11</b>	<b>Fri 8/27/10</b>	<b>Tue 11/30/10</b>	<b>68 days?</b>
Coil 11 Wind / Cure	Fri 8/27/10	Thu 9/16/10	15 days
Coil 11 React / Impreg LBL	Fri 9/17/10	Tue 11/9/10	38 days?
Coil 11 Instrum - Elec	Wed 11/10/10	Tue 11/30/10	15 days?
<b>Coil 12</b>	<b>Fri 9/24/10</b>	<b>Tue 12/28/10</b>	<b>68 days?</b>
Coil 12 Wind / Cure	Fri 9/24/10	Thu 10/14/10	15 days?
Coil 12 React / Impreg LBL	Fri 10/15/10	Tue 12/7/10	38 days?
Coil 12 Instrum - Elec	Wed 12/8/10	Tue 12/28/10	15 days?

Q1 10    Q2 10    Q3 10    Q4 10



# HQ01a Magnet parameters



## HQ01a:


⇒ Coils 1 and 2: 54/61 strand

⇒ Coils 3 and 4: 108/127 strand

⇒ should be the limiting coils  
 ⇒ short sample current computed based on 108/127 witness samples

	4.4 K	1.9 K
Short sample current $I_{ss}$ (kA) (54/61)	17.3 (17.7)	19 (19.5)
Gradient at $I_{ss}$ (T/m) (54/61)	195 (199)	214 (218)
Stored energy (MJ)	0.9	1.1
Inductance (mH)	6	

# HQ01 Short sample estimate



## Instrumentation per coil:

- 20 Vtaps: 10 IL and 10 OL
- 1 SG station measuring  $\theta$  and Z components located in the center: full bridge T compensated
- 1 spot heater
- 4 strips of protection heaters




Vtaps circuits + protection heaters circuits => trace  
SG + spot heaters => wired externally




## Protection heaters design:

Coverage = 60 %


### Layer 1



### Layer 2



4 strips connected in parallel



## PH circuits based on hipot:

Coil 1 A02: failed 300 K magnet hipot

Coil 1 B01 B02: passed hipot despite short to endshoe

- circuit #1: C1B01 – C1B02 – C2B01 – C3B01 => problematic OL PH belong to the same circuit
- circuit #2: C4B01 – C2B02 – C3B02 => no C4B02 to avoid losing both heaters C4 OL
- circuit #3: C1A01 – C2A01 – C3A01 – C4A01
- circuit #4: C2A02 – C3A02 – C4A02 – C4B02

HFU FNAL

HFU LBL



# HQ01a Strain gauge station location


## Assembly with Al dummy coils

- with Fuji paper

## Assembly of HQ01a

- coil pack with Fuji
- azimuthal loading up to half of coil target
- axial loading
- azimuthal loading completion

- 4 SG stations on the shell
  - $\theta$  and Z
- 1 SG station per coil
  - $\theta$  and Z




# Dummy Assembly – Coil pack

## Collar-pack assembly

	Inches
Dummy coil OD	7.198
G10 nominal shim	0.037
Medium P Fuji	0.004
<b>Shimmed Dummy OD</b>	<b>7.280</b>
<b>Collar ID</b>	<b>7.276</b>

Slot for the key



**2 mils radial interference** between dummy and shimmed collar


=> ~ 1.5 mils per side of the key

=> ~ 1 mils average measured after torque


**Coil-pack assembly**



**Insertion in the vertical yoke-shell subassembly**





## Bladder operation





Fuji paper test shows a good contact between collar and coil during bladder operation

## Comparison with ANSYS




Layout	
Coil theoretical OD	7.198"
G10 nom. / Shim stack	0.037" / 0.034"
Mylar shim / Low P Fuji	0.004" / 0.007"
<b>Nom. Shimmed coil OD</b>	<b>7.280"</b>
<b>Collar ID</b>	<b>7.276"</b>

- 41 mils of total shimming  
=> 2 mils of radial interference coil/collar
- Pressure pattern similar to LQS01a in the straight section
- In the end: contact at the mid-plane because end part at nominal size



20.5" from RE



8.5" from RE




2.5" from RE



Layout	
Coil theoretical OD	7.198"
G10 nom. Shim / Shim stack	0.037" / 0.029"
No addition. Shim / Low P Fuji paper	0.008"
<b>Nominal Shimmed coil OD</b>	<b>7.272</b>
<b>Collar ID</b>	<b>7.276</b>

**Nominally: no interference between coil and shimmed collar**




**RE**

No key in the end + endshoe  
=> **No clearance**


**Center**

=> **8 mils clearance measured**  
between key and collar per  
side





- Coil pack oversize in the center : agreement with coil measurements
- Decision to go ahead with nominal shim 37 mils

# ANSYS 2D – Bladder operation Targets (I)




- Coil pack is oversized in the center
- gap key / collar gap of  $\sim 8$  mils  
=> behavior “no key”
- Decision to pre-stress to 1.9 K short sample: 19.05 kA






Same shim stack needed: 24 mils

- Similar shell strain
  - same stretching of the shell in both cases
- Much higher pole strain in “no key” case


Coil/Pole contact elements at Iss 1.9 K with key




Coil/Pole contact elements at Iss 1.9 K without key




# SG data during bladder operation



Coil gauges responding to the bladder pressure and to the shimming of the load keys








- Some shimming needed to straighten the coil?

- The slope => no contact with the key

ANSYS With key MPa		ANSYS Without key MPa		SG measur. (MPa)
L1	L2	L1	L2	
-61	-37	-91	54	
-92		-150		
-97		-157		-114 ± 9
96		89		115 ± 7.6

Comparison with Dummy  
=> coil pack 3 mils bigger on the radius than dummy coil / nominal pack





- Only 60 to 75 % of the coil target
- 90 % of the shell target

$$\sigma_{\theta \text{ pole SG}} \sim -150 \text{ MPa} \pm 8$$

$$\Rightarrow \sigma_{\theta \text{ layer 1}} \sim -110 \text{ Mpa}$$


$\Rightarrow$  Pre-stress required for 17.3 kA

# SG data during cool down



Target piston:  
1260  $\mu\epsilon$  / 90 MPa


Average measured:  
1211  $\mu\epsilon$  / 85 MPa




Target cold:  
2280  $\mu\epsilon$  / 180 MPa

Average measured:  
2483  $\mu\epsilon$  / 190 MPa

Total axial force applied  $\sim$  600 kN



Fri Apr 23 17:31:12 2010



Fri Apr 23 17:30:11 2010

- **Test #1: HQ01a test at LBNL**

Coils 1, 2, 3 and 4

- Ongoing until mid-May
- Based on performance
  - Disassembly of HQ01a
  - Replacement of some coils: 5 and 6 should be available by then
  - Adjustments of the mechanical structure
  - Re-assembly as HQ01b

- **Test #2 CERN in summer 2010**

Coils 5 and 6 available

- Motivation to test at CERN: 1.9 K
  - Current leads limitation at FNAL
- Discussion with CERN about HQ compatibility with test facility
  - Cryostat size
  - Magnet stored energy (?)

- **Test#3 at FNAL in Fall 2010**

Coils 7,8 and 10 available  
Possibly 9

**Goal:** comparison with the NbTi models on all issues that may be relevant to a technology decision in 2013-2014

Several changes may be required:

- **Coil design**
  - Cross-section iteration for field quality
  - End optimization
  - Cooling channels in the pole
  
- **Coil fabrication and tooling**
  - Correction to oversized coils
  - Protection heaters design

- **Structure**


- Segmented aluminum shell
  - Required to minimize variation of azimuthal stress along the magnet length
- LQ-like modular assembly
  - In preparation for further length extension
- Collar design
- Pad and yoke design optimization
  - Include Phase-type I cooling areas and features
- Compatibility with external SS cylinder for LHe containment
- Fiducials external cylinder to yoke
- Axial support
  - End plate and axial rods
  - End plate welded to SS cylinder

- Implementation
  - Coil fabrication:
    - Use existing 1 meter parts when possible:
      - Winding mandrel
      - Reaction / Impregnation tooling
  - Structure
    - Extension of the existing shell? Yoke? Pads?
- Capability to continue making 1 meter models?
- Schedule/cost





# ANSYS 2D – Cool down Targets



Pole: -1396  $\mu\epsilon$   
 Shell: 2670  $\mu\epsilon$   
 Pole: -1800  $\mu\epsilon$   
 Shell: 2564  $\mu\epsilon$

With key – $\sigma_\theta$ at 4.2 K	L1	L2
Avg preload on the coil	-143	-96
Peak stress in the coil	-193	
Pole SG location	-181	
Shell SG location	211	

Without key – $\sigma_\theta$ at 4.2 K	L1	L2
Avg preload on the coil	-169	-112
Peak stress in the coil	-227	
Pole SG location	-234	
Shell SG location	202	