

Project X/ILC/SRF Integrated Plan

Steve Holmes

Fermilab

DOE Annual Science & Technology Review


July 12-14, 2010

Outline

- Project X Current Status
- PX/ILC/SRF Integrated Plan
- Integrated Funding Profile

Project X Mission Objectives (unchanged)


- A neutrino beam for long baseline neutrino oscillation experiments
 - 2 MW proton source at 60-120 GeV
- High intensity, low energy protons for kaon and muon based precision experiments
 - >1 MW operations simultaneous with the neutrino program
- A path toward a muon source for a possible future Neutrino Factory and/or a Muon Collider
 - Requires upgrade potential to 4 MW at ~5-15 GeV



Initial Configuration – 1: Issues

- The originally established configuration featured strong alignment with ILC: 8 GeV superconducting pulsed linac
- IC-1 does a great job of meeting the long baseline neutrino mission, but...
- It does not provide a strong platform for mounting a low energy rare processes program
 - Recycler is ill-suited to providing high intensity slow spilled beam
 - Debuncher appears limited to <150 kW in this mode
 - ⇒ **We believe there is a fundamental limit on the amount of beam power that can be delivered via a resonant extraction system**
 - Difficulties supporting multiple users with differing spill structure requirements
- ⇒ **These considerations have led to the development of IC-2**

Initial Configuration-2



- 3 GeV CW linac provides greatly enhanced rare process program
 - 3 MW; flexible provision for beam requirements supporting multiple users
- Options for 3-8 GeV acceleration: RCS or pulsed linac
 - Linac would be 1300 MHz with 4-25 msec pulse length
- Initial Configuration Document-2 in preparation for summer release

Initial Configuration-2: Performance Goals

Linac

Particle Type	H ⁻
Beam Kinetic Energy	3.0 GeV
Average Beam Current	1 mA
Linac pulse rate	CW
Beam Power	3000 kW
Beam Power to 3 GeV program	2870 kW

RCS/Pulsed Linac

Particle Type	protons/H ⁻
Beam Kinetic Energy	8.0 GeV
Pulse rate	10 Hz
Pulse Width	0.002/4.3 msec
Cycles to MI	6
Particles per cycle to Recycler	2.6×10^{13}
Beam Power to 8 GeV program	200 kW

Main Injector/Recycler

Beam Kinetic Energy (maximum)	120 GeV
Cycle time	1.4 sec
Particles per cycle	1.6×10^{14}
Beam Power at 120 GeV	2200 kW

simultaneous

Initial Configuration-2: Operating Scenario

1 μ sec period at 3 GeV

mu2e pulse ($9e7$) 162.5 MHz, 100 nsec



600 kW

Kaon pulse ($9e7$) 27 MHz


1200 kW

Nuclear pulse ($9e7$) 27 MHz

1200 kW



Initial Configuration-2: Provisional Siting



Initial Configuration-2: Technology Map



Section	Freq	Energy (MeV)	Cav/mag/CM	Type
SSR0 ($\beta_G=0.11$)	325	2.5-10	26 /26/1	SSR, solenoid
SSR1 ($\beta_G=0.22$)	325	10-32	18 /18/ 2	SSR, solenoid
SSR2 ($\beta_G=0.4$)	325	32-160	44 /24/ 4	SSR, solenoid
LB 650 ($\beta_G=0.61$)	650	160-520	42 /21/ 7	5-cell elliptical, doublet
HB 650 ($\beta_G=0.9$)	650	520-2000	96 /12/12	5-cell elliptical, doublet
ILC 1.3 ($\beta_G=1.0$)	1300	2000-3000	64 / 8/ 8	9-cell elliptical, quad

Project X: Collaboration Status

- Multi-institutional collaboration established to execute the Project X RD&D Program.
 - Fermilab as lead laboratory
 - International participation via in-kind contributions, established through bi-lateral MOUs.

- MOU outlines basic goals, and the means of organizing and executing the work. Signatories:

ANL	ORNL/SNS	BARC/Mumbai
BNL	MSU	IUAC/Delhi
Cornell	TJNAF	RRCAT/Indore
Fermilab	SLAC	VECC/Kolkata
LBNL	ILC/ART	

- Collaborator R&D responsibilities largely defined
- Other interested parties: CERN, IHEP, Korea, ESS
- Collaboration meeting 9/8-9

Project X/ILC/SRF Integrated Plan

Goals

- Provide integrated management of all superconducting rf development activities at Fermilab
- Provide coherent development of facilities and utilization of resources to meet the needs of the ILC, Project X, and ultimately Muon Accelerator Programs
- Align HINS activities directly with Project X needs
- Meet all commitments to the ILC program between now and FY2012

Project X/ILC/SRF Integrated Plan

Strategy

- Bring all srf activities under the purview of the ILC/SRF Program Director
 - ILC and Project X management define requirements
- Redefine the High Intensity Neutrino Source (HINS) program to directly support the needs of Project X
- Establish the General Accelerator R&D category as the primary funding source for srf cavity development outside of ILC applications.

Project X/ILC/SRF Integrated Plan

Strategy (cont.)

- Establish a set of srf R&D deliverables that are distinguishable from infrastructure
- Redefine the scope of the following programs consistent with the above strategy:
 - SRF Infrastructure
 - Project X R&D
 - General Accelerator Development
 - HINS
 - ILC
 - SRF Operations

Project X/ILC/SRF Integrated Plan

Plan

- Discontinue the (HINS) program as a stand-alone R&D program
 - Rescope the beam facility to support chopper and instrumentation development for Project X. Fund via Project X R&D
 - Retain low beta cavity development within General Accelerator Development
 - Eliminate HINS as a budget line item

Project X/ILC/SRF Integrated Plan

Plan (cont.)

- Establish clear deliverables for the srf program over the period FY2010-15:
 - Six 1300 MHz cryomodules, culminating in a CW Project X prototype. High power rf test.
 - One 650 MHz cryomodule for Project X. High power rf test.
 - One 325 MHz cryomodule for Project X. High power rf test.
 - Complete Project X test facility at Meson Lab
 - ILC rf unit test, with beam, at NML based on three (ultimately six) 1300 MHz ILC cryomodules

Project X/ILC/SRF Integrated Plan

Plan (cont.)

- Establish a new SRF Operations line to support maintenance and operations of SRF facilities once infrastructure is complete and being utilized for ILC and Project X development.
- Implement the plan starting in FY2011

Integrated SRF Plan: Project X and ILC

U.S. Fiscal Year	2008	FY09	FY10	FY11	FY12	FY13	FY14	FY15
1.3 GHz								
CM1 (Type III+)		CM Ass'y	Install CM	CM Test			Operate Complete RF Unit @ Design Parameters	
CM2 (Type III+)	Omnibus Delay	Process & VTS/Dress/HTS	CM Ass'y	sw ap				
CM3 (Type IV)		Design	Order Cav & CM Parts		2/3 CM			
CM4 (Type IV)						sw ap		
CM5 (Type IV)						sw ap		
CM6 (Type IV+) CW Design					Design CM 1.3 GHz CW			Install in CMTF
NML Extension Building		Design	Construction					
NML Beam					Move injector/install beam components	Beam Available to RF Unit test except during installation periods (contingent upon cryogenic load/capacity)		
CMTF Building			Design	Construction				
650 MHz								
Single Cell Design & Prototype								
Five Cell Design & Prototype								
CM650_1				Design	Order 650 Cav & CM Parts	Process & VTS/Dress/HTS	650 CM Ass'y	
325 MHz								
SSR0/SSR2 Design & Prototype			Design (RF & Mechanical) all varieties of Spoke Reonators		Prototype (as required)	Process & Test (as required)		
SSR1 Cavities in Fabrication (14)			Procurement (already in progress)	Process & VTS/Dress/HTS				
CM325_1			Design	Procure 325 CM Parts		325 CM Ass'y		
		Design	Procure	Process & VTS Dress & HTS	Assemble	Install	Commission & Operate	

Project X/ILC/SRF Integrated Plan

Funding Plan


- The funding plan is consistent with that presented at the DOE budget briefing as Scenario B (COL on FY2010).
 - Supports primary deliverables of ILC and Project X, including preparations for a Project X construction start in FY2015.
- Project X assumed critical decision dates
 - CD-0: January, 2011
 - CD-1: July, 2012
 - CD-2: August, 2013
 - CD-3: September, 2014

Project X/ILC/SRF Integrated Funding Plan

Core Technologies R&D		FY 10	FY 11	FY 12	FY 13	FY 14	FY 15	FY 16
KA1502011	General Accelerator Development ops	15,150	16,782	22,324	28,874	31,039	28,137	20,708
	<i>SRF Development Activities</i>	7,557	11,731	16,713	23,151	25,201	22,182	14,635
Total Core Technologies		15,150	16,782	22,324	28,874	31,039	28,137	20,708
KA1102034	R&D - Project X	11,003	15,566	19,692	19,128	19,035	0	0
39KA	Project X Construction	0	0	0	0	0	39,173	60,955
Total Project X		11,003	15,566	19,692	19,128	19,035	39,173	60,955
KA1502012	Superconducting RF	20,500	16,866	5,900	0	0	0	0
KA1502012	Superconducting RF - MIE	0	3,200	0	0	0	0	0
Total SRF Infrastructure		20,500	20,066	5,900	0	0	0	0
KA1502021	Lab ILC Accel R&D	11,321	10,650	10,650	5,325	5,485	5,677	0
Total ILC R&D (wo/GDE)		11,321	10,650	10,650	5,325	5,485	5,677	0
Total		57,974	63,064	58,566	53,327	55,558	72,986	81,664
KA 11 XX XX	Superconducting RF - operations	0	0	11,000	11,220	11,444	11,673	11,907

PX/NF/MC Evolution

- Project X shares many features with the proton driver required for a Neutrino Factory or Muon Collider
 - NF and MC require ~ 4 MW @ 10 ± 5 GeV
 - Primary issues are related to beam “format”
 - NF wants proton beam on target consolidated in a few bunches; Muon Collider requires single bunch
 - Project X linac is not capable of delivering this format



⇒ It is inevitable that a new ring(s) will be required to produce the correct beam format for targeting.

- MAP Collaboration formed, DOE Review in August

Strategy/Timeline

- Next six months: Complete all preliminary design, configuration, and cost range information for IC-2
 - ICD-2v2.0
 - Cost estimate
 - Updated RD&D Plan with resource loaded schedule
- Continue conceptual development on outstanding technical questions
 - Baseline concept for the chopper
 - Concepts for marrying a 3-8 GeV pulsed linac to CW front end
 - Injection into RCS or Recycler
- Pursue R&D aimed at the CW linac
 - Emphasis of srf development at all relevant frequencies
 - Engage external collaborators and identify roles
- Department of Energy has advised that the earliest possible construction start is FY2015
 - Requires CD-0 in FY2011
- We believe that we could construct Project X over a five year time period, assuming a commensurate funding profile
 - ⇒ **Project X could be up and running ~2020**

Summary

- Project X is central to Fermilab's strategy for development of the accelerator complex over the coming decade
 - World leading programs in neutrinos and rare processes
 - Aligned with ILC and Muon Accelerators technology development;
 - Potential applications beyond elementary particle physics
- The design concept has evolved over the last year, providing significantly enhanced physics capabilities
 - >2 MW at 60-120 GeV, simultaneous with 3 MW at 3 GeV
 - Flexibility for supporting multiple experiments
 - CW linac is unique for this application, and offers capabilities that would be hard/impossible to duplicate in a synchrotron
- Project X and ILC (and HINS) srf activities are now integrated
- The accelerator concept is sufficient to support CD-0
- Details in Breakout Session (Nagaitsev & Kephart)