

# Massive Gravitino Decays, Residual Dark Matter Annihilations, Nuclear Reaction Uncertainties and the Cosmological Lithium Problems

arXiv:0907.5003, 1007.4173, 1109.?

Feng Luo

with Richard H. Cyburt, John Ellis, Brian D. Fields,  
Keith A. Olive, Vassilis C. Spanos

University of Minnesota

Aug. 29, 2011

# Motivation

Constrain particle decay or/and annihilation scenarios by BBN

e.g.,  $m_{3/2} + \text{CMSSM} \{m_{1/2}, m_0, A_0, \tan \beta, \text{sgn}(\mu)\}$

Try to solve  ${}^7\text{Li}$  or/and  ${}^6\text{Li}$  problem

▶  ${}^7\text{Li}$

$$\text{observations, } \left(\frac{{}^7\text{Li}}{\text{H}}\right)_{\text{halo}^*} = (1.23^{+0.34}_{-0.16}) \times 10^{-10}$$

$$\left(\frac{{}^7\text{Li}}{\text{H}}\right)_{\text{GC}} = (2.35 \pm 0.05) \times 10^{-10}$$

$$\text{standard BBN, } \left(\frac{{}^7\text{Li}}{\text{H}}\right)_{\text{SBBN}} = (5.12^{+0.71}_{-0.62}) \times 10^{-10}$$

▶  ${}^6\text{Li}$

$$\text{observations, } \left(\frac{{}^6\text{Li}}{{}^7\text{Li}}\right)_{\text{halo}^*} \sim 0.05 \implies {}^6\text{Li}/\text{H} \sim (6 - 25) \times 10^{-12}$$

$$\text{standard BBN, } {}^6\text{Li}/\text{H} \sim 10^{-14}$$

# Method Outline

★ CMSSM input (4 parameter and a sign)

↓ RGEs

sparticle masses and couplings

↓ input  $m_{3/2}$

decay spectra

↓ PYTHIA

hadronic and electromagnetic showers

↓  $\zeta_{3/2} \equiv \frac{m_{3/2} n_{3/2}}{n_\gamma}$  and BBN code including non-thermal reactions

light element abundances prediction

↓ compare with observations


constraints on  $m_{3/2}$ ,  $\zeta_{3/2}$  and CMSSM parameters,  
 ${}^7\text{Li}$  and/or  ${}^6\text{Li}$  solved?

Goto ★


$$\Gamma_{hb \rightarrow \ell} = \int N_h(\epsilon) v \sigma_{hb \rightarrow \ell}(\epsilon) d\epsilon$$

# Nuclear reactions of non-thermal particles

	Reaction	Uncertainty $\epsilon$		Reaction	Uncertainty $\epsilon$
1	$p^4\text{He} \rightarrow d^3\text{He}$		2	$p^4\text{He} \rightarrow np^3\text{He}$	20%
3	$p^4\text{He} \rightarrow ddp$	40%	4	$p^4\text{He} \rightarrow dnpp$	40%
5	$d^4\text{He} \rightarrow ^6\text{Li}\gamma$		6	$t^4\text{He} \rightarrow ^6\text{Li}n$	20%
7	$^3\text{He}^4\text{He} \rightarrow ^6\text{Li}p$	20%	8	$t^4\text{He} \rightarrow ^7\text{Li}\gamma$	
9	$^3\text{He}^4\text{He} \rightarrow ^7\text{Be}\gamma$		10	$p^6\text{Li} \rightarrow ^3\text{He}^4\text{He}$	
11	$n^6\text{Li} \rightarrow t^4\text{He}$		12	$pn \rightarrow d\gamma$	
13	$pd \rightarrow ^3\text{He}\gamma$		14	$pt \rightarrow n^3\text{He}$	
15	$p^6\text{Li} \rightarrow ^7\text{Be}\gamma$		16	$p^7\text{Li} \rightarrow ^8\text{Be}\gamma$	
17	$p^7\text{Be} \rightarrow ^8\text{B}\gamma$		18	$np \rightarrow d\gamma$	
19	$nd \rightarrow t\gamma$		20	$n^4\text{He} \rightarrow dt$	
21	$n^4\text{He} \rightarrow npt$	20%	22	$n^4\text{He} \rightarrow ddn$	40%
23	$n^4\text{He} \rightarrow dnnp$	40%	24	$n^6\text{Li} \rightarrow ^7\text{Li}\gamma$	
25	$n$ (thermal)		26	$n^7\text{Be} \rightarrow p^7\text{Li}$	
27	$n^7\text{Be} \rightarrow ^4\text{He}^4\text{He}$		28	$p^7\text{Li} \rightarrow ^4\text{He}^4\text{He}$	
29	$n\pi^+ \rightarrow p\pi^0$		30	$p\pi^- \rightarrow n\pi^0$	
31	$p^4\text{He} \rightarrow ppt$	20%	32	$n^4\text{He} \rightarrow nn^3\text{He}$	20%
33	$n^4\text{He} \rightarrow nnnpp$		34	$p^4\text{He} \rightarrow nnpnp$	
35	$p^4\text{He} \rightarrow N^4\text{He}\pi$		36	$n^4\text{He} \rightarrow N^4\text{He}\pi$	



**Figure:** For benchmark C, with  $m_{1/2} = 400$  GeV on the WMAP coannihilation strip for a CMSSM scenario with  $\tan\beta = 10$ ,  $A_0 = 0$ . The white regions in each panel are those allowed at face value by the light-element abundances.



**Figure:** For the reaction 21 ( $n^4\text{He} \rightarrow npt$ ,  $\epsilon = 20\%$ ), showing the effects on deuterium (upper left),  ${}^3\text{He}$  (upper right),  ${}^7\text{Li}$  (lower left) and  ${}^6\text{Li}$  (lower right).




Figure: The  ${}^7\text{Li}$  abundance as a function of  $\epsilon$ .  $\Gamma'_i = (1 + \epsilon_i)\Gamma_i^0$ .


## $\chi^2$ analysis

$$\chi^2 \equiv \left( \frac{Y_p - 0.256}{0.011} \right)^2 + \left( \frac{\frac{D}{H} - 2.82 \times 10^{-5}}{0.27 \times 10^{-5}} \right)^2 + \left( \frac{\frac{{}^7\text{Li}}{H} - 1.23 \times 10^{-10}}{0.71 \times 10^{-10}} \right)^2 + \sum_i s_i^2,$$

where  $\Gamma'_i = (1 + \epsilon_i s_i) \Gamma_i^0$

- ▶  $\frac{D}{H}$ :  $(2.82 \pm 0.21) \times 10^{-5}$  (high-redshift quasar absorption systems)  
 $(2.52 \pm 0.17) \times 10^{-5}$  (SBBN)
- ▶  $Y_p$ :  $0.256 \pm 0.011$  (observations)  
 $0.2487 \pm 0.0002$  (SBBN)





**Figure:** Contours of the  $\chi^2$  function in the  $(m_{3/2}, \zeta_{3/2})$  planes for the benchmark CMSSM scenarios C (upper left), E (upper right), L (lower left) and M (lower right), incorporating the uncertainties.

**Table:** Results for the best-fit points for CMSSM benchmarks C, E, L and M. The second set of results for C and M correspond to the globular cluster value for primordial  ${}^7\text{Li}/\text{H}$ . The third and fourth entries for point C correspond to the higher adopted uncertainty for  $\text{D}/\text{H}$  ( $\pm 0.53 \times 10^{-5}$ ) in field stars and to the globular cluster  ${}^7\text{Li}$  abundances, respectively.



	$m_{3/2}[\text{GeV}]$	$\text{Log}_{10}(\zeta_{3/2}/[\text{GeV}])$	$Y_p$	$\text{D}/\text{H} (\times 10^{-5})$	${}^7\text{Li}/\text{H} (\times 10^{-10})$	$\sum s_i^2$	$\chi^2$
BBN	—	—	0.2487	2.52	5.12	—	31.7
C	4380	-9.69	0.2487	3.15	2.53	0.26	5.5
E	4850	-9.27	0.2487	3.20	2.42	0.29	5.5
L	4380	-9.69	0.2487	3.21	2.37	0.26	5.4
M	4860	-10.29	0.2487	3.23	2.51	1.06	7.0
C	4680	-9.39	0.2487	3.06	2.85	0.08	2.0
M	4850	-10.47	0.2487	3.11	2.97	0.09	2.7
C	3900	-10.05	0.2487	3.56	1.81	0.02	2.8
C	4660	-9.27	0.2487	3.20	2.45	0.16	1.1

*But recall that we only have 1 d.o.f.*



*Nevertheless, for  $\chi^2 \sim 5.5$ , alleviate  ${}^7\text{Li}$  from a 4- or 5- $\sigma$  problem to a  $\lesssim 2$ - $\sigma$  issue.*

## ${}^6\text{Li}$ problem and residual dark matter annihilations

**Idea:**  ${}^6\text{Li}$  abundance is very small, maybe hadronic and electromagnetic showers from dark matter annihilations after freeze-out are enough to cure the  ${}^6\text{Li}$  problem, while leaving the other light element abundances almost unaffected.



$$\Delta Y({}^6\text{Li}) \sim 7 \times 10^{-13} \left( \frac{\langle \sigma v \rangle_{\text{ann}}}{10^{-26} \text{ cm}^3 \text{ s}^{-1}} \right) \left( \frac{300 \text{ GeV}}{m_\chi} \right)^2$$



## Conclusions and future work

- ▶ heavy particle decays or/and annihilations scenarios are constrained by BBN
- ▶  ${}^7\text{Li}$  and/or  ${}^6\text{Li}$  problems point to new physics?
- ▶ uncertainties of non-thermal nuclear reaction rates needed to be pin down to help constrain the scenarios better
- ▶ Future work: both decay and annihilations, bound state effects

*Thank You : )*