



MICE Spectrometer Solenoid

Muon Accelerator Program (MAP)

PMG Meeting

January 12, 2011

Steve Virostek

Lawrence Berkeley National Lab



Topics



- MICE technical review
- Magnet analyses
- Responses to committee report
- Design modification plan
- Schedule, budget and manpower
- Current Status



MICE Technical Review



- An assessment and analyses of various aspects of the magnet design has been carried out by LBNL
- A preliminary design modification plan was presented to a MICE technical review committee on 10/27/10
- Preliminary comments were received from the committee on 11/22/10
- The committee's final report with recommendations was issued on 12/14/10



Heat Load Analysis



- The heat leaks due to the dominant static sources have been re-evaluated
- The focus of the calculations was the heat leaks into the 4.2K cold mass as these directly relate to the issue of LHe boil-off during operation
- Other aspects of magnet thermal performance including heat loads on the shield and vacuum insulation have also been considered
- The dynamic heat loads that occur during cooldown or current ramp-up when the magnet system is not in equilibrium have been ignored as they are negligible during long-term operation



Electromagnetic Calculations



- The design of the passive magnet protection system is being reviewed and analyzed under the various operational regimes
- The areas covered include
 - Peak voltages to ground and inter-layer
 - A more clear understanding of coupling between coils during various quench scenarios
 - A detailed estimate of the current decay and current seen by the shunt resistors, and feedback on possible improvements to the selected resistance values
 - An estimate of the role of quenchback from the aluminum mandrel
- The suitability of the existing passive quench protection system and the possible need for an active system is being assessed



Responses to Committee Report



- The committee report includes a series of recommendations for the Spectrometer Solenoid team
- The LBNL team has reviewed the recommendations and has prepared responses that are detailed in a separate document
- The committee recommended that an active quench and lead protection system be implemented on the magnets
- LBNL is conducting a series of analyses to determine whether or not an active system will be necessary
- Other recommendations related to the heat load calculations are currently being undertaken at LBNL





Design Modification Plan



- A preliminary design modification plan has been developed by LBNL. The plan includes the following:
 - reduction of heat leaks to the cold mass
 - the addition of more cryo cooling power
 - assessment of the suitability of the passive quench protection system
 - modification of the LTS leads to prevent burn-out
- The plan has been detailed in a separate document and posted on the website for this meeting

Proposed 5 + 1 Cryocooler Layout





Schedule, Budget and Manpower



- A detailed straw man schedule has been assembled based on LBNL experience that provides a compilation of the tasks with an estimate of the required durations
- A final, resource loaded schedule will be developed with the vendor once the repair plan is complete
- An estimate of the remaining costs to MAP to complete the Spectrometer Solenoids has been compiled, including both manpower and hardware
- Contingency was estimated to account for uncertainties, including the possible need for active quench protection
- Required manpower has been identified and is available



MAP Tech Board



- Preliminary plan presented to MAP TB yesterday
- Several comments arose from the meeting:
 - A coupled quench analysis should be carried out with all MICE magnets in place
 - The effects of stray fields on the coolers (particularly the 1-stage GM) and the need for local shielding needs to be assessed
 - The means for protecting the leads in a power outage needs to be established
- The possible concept for an active quench protection system was questioned
 - A system using heaters may be inadequate
 - A design study will be conducted if an active system is needed



Current Status



- The electromagnetic and heat load analyses are under way and expected to be complete by the end of this month
- The quench and lead protection issue presents a major uncertainty in the completion of the plan
- Upon completion of the analyses and the final modification plan, the Spectrometer Solenoid team will present the plan to the MICE tech board
- LBNL has been meeting with the vendor to ensure the project can restart promptly when the plan is complete