


DESY Test Beam Facilities


- Status and Plan



Testbeam Workshop
January 17th 2007
Fermilab

DESY Test Beam


- DESY provides three test beam lines with 1-6 GeV/c electrons
- Very simple system, no beam optics, only momentum selection via magnet



- Bremsstrahlung beam generated by DESY and PETRA (in the circulating beam of the electron/positron synchrotron DESY II)
 - For DORIS: DESY delivers every second cycle (1.60ms) single bunches with 10^{10} electrons to a detector with 10 positron pairs with a metal plate.
- Beam is spread out into a horizontal fan with a dipole magnet. Collimator cuts out final beam.
 - 10^{10} electrons (10^{10} positrons) at 7 GeV
 - Test beam runs in PETRA mode
- The revolution frequency is 1 MHz, the RF frequency 500 MHz, and the bunch length around 30 ps. The average radius is 46.6 m

DESY Test Beam



- Ideal DESY II Cycle (no extraction)



- The rates are influenced by many parameters.
- Ideally, the maximum rate around 1 kHz (3 GeV, 3mm Cu convert, Collimator ca. 5mm x 5mm, DESY II maximum energy at 7 GeV, no beam extraction, no DESY III ramp).
- Few hundred Hearts are realistic



Rates	Target	
	3mm Cu	1mm Cu
Energy		
1 GeV	~330 Hz	~220Hz
2 GeV	~500 Hz	~330 Hz
3 GeV	~1000 Hz	~660 Hz
5 GeV	~500 Hz	~330 Hz
6 GeV	~250 Hz	~160 Hz

Carbon Fibre




- The carbon fibre has a thickness of 6-10 μm .
- Six fibres are prepared inside the fibre holder. By rotation of the inner part, a broken fibre can be replaced without opening the machine vacuum.

Conversion Target



- There are different conversion targets available:
 - Al, Cu,
- The selection of the conversion target is under control of the testbeam user

Test Beam Layout




Facilities for Test Beam User

- All three testbeam lines have
 - Interlock systems
 - Magnet control
 - Patch panels with preinstalled cables
 - Gas warning systems
 - Fast internet connection (DHCP)
- You can ask for:
 - Translation stages
 - Premixed gases
- You have to bring:
 - Data Acquisition incl. computers
 - Trigger scintillators



Test Beam Area 21

- Mainly used by HCAL, ECAL and TPC (ILC)




E. Garutti

- Plans for first half of 2007
 - calibration of HCAL modules - 4 at the time as soon as they get produced (HCAL Group DESY)
 - commissioning of Japanese scintillator ECAL with SiPM readout (Shinshu and Kobe universities + HCAL group DESY)

Testbeam 22: ZEUS Telescope

- Location of ZEUS MVD telescope (build in 1998)
- Telescope parameters:
 - 300 um thick single-sided Si strip sensors
 - Each plane with 2 sensors perpendicular to each other
 - Strip pitch: 25um
 - Readout pitch: 50um
 - Active area: 32x32 mm²
 - Trigger window: 8x8 mm²
- Plans for next years: keep telescope running

Contact: Uli Koetz and Ingrid Gregor



HERMES test 2004

Testbeam 24: EUDET



- “Reserved” for EUDET JRA1 initiative (Telescope and Magnet)
 - See talk from Felix Sefkow

Future Changes at Testbeam

- 2007: small improvements
 - Light, paint, webpages, ...
- First half of 2008: long shutdown
 - New Vacuum System
 - New Control System
- Plans for the future
 - Maintain testbeam facilities
 - Proof of principle
 - Calibrations etc.
- Impact of PETRA3 on test beam right now under evaluation

Summary

- DESY provides three test beam lines with 1-6GeV/c electrons
- Very simple system, no beam optics, only momentum selection via magnet
- Infrastructure simple and flexible
- If you need to use the DESY testbeam -> request beam time through Norbert Meyners (testbeam.desy.de)