



# PIP-II power couplers cleaning and RT RF power tests

Nikolay Solyak, Sergey Kazakov  
(for coupler team)

PIP-II Technical Workshop

Dec 1-3, 2020


In partnership with:  
France/CNRS/IN2P3 - IJCLab  
India/DAE - BARC

# Agenda

---


- SSR1/SSR2 coupler
  - Designs, acceptance and cleaning
  - Test statistics
  - Current status
- 650 MHz coupler design for LB650/HB650
  - Coupler Prototypes and final design
  - RF test results for 2 types of prototype (A & B)
  - Summary

# SSR1/SSR2 coupler design



“SSR1 prototype design”,  
17 couplers build and  
tested, 8 was assembled  
in SSR1 prototype CM  
(PIP@2IT)

New version is shorter and lighter.



“SSR2 prototype design”,  
8 in production:  
4 - FNAL/CPI  
4 - IN2P3/PNB

**New design was made based on experience with prototype couplers**



# SSR1 cold-end couplers: processing/qualification




## RF conditioning at room temperature


- Visual inspection and leak check
- Cleaning and installation of the vacuum end assembly on the RF test stand in cleanroom
- 120C baking 48 hours
- Testing up to specified power (10kW) in full reflection to check the structural performance of the ceramic window.
- During the test we check the RGA scan to monitor the emission of undesired substances (i.e. hydrocarbons) from the antenna.
- All activities of assembling/disassembling take place in the cleanroom

## Fully integrated test at cold temperature

- After qualification at room temperature, the vacuum-end coupler is cleaned, installed on the jacketed cavity in class 10 cleanroom and undergo to 120C baking 48 hours





# Diagram of RT test stand for testing 325 MHz couplers







# 325 MHz coupler test stand



# Antennas coupling in test stand (coupling chamber)



# Results of testing at room temperature test stand.

Total number produced and tested couplers is 17 (CPI/Coorstek/MEGA). Tests were done at CW mode with full reflection. The reflection phases were changed with 90 degrees step, totally 4 phases were tested for each pair of couplers. Test was considered as completed if couplers sustain more than 1 hour at each phase point at maximum power. Results of testing is presented at table. Test shows that multipactor can be successfully suppressed by DC bias with voltage  $\geq 3$  kV. No attempts to do processing without DC bias.


RF power	Number of tested couplers	Number of failures couples	Reason of failure
10 kW	17	0	
20 kW	5	1	Low quality ceramic.
30 kW	2	0	
47 kW	2	1	High power.



# SSR1 coupler checkout in STC tests

## Coupler performance was checked out in STC SSR1 integrated tests:



- Total number of SSR1 cavities with couplers tested - 10
- At 2K, cavity tuned off-resonance, HV bias 4kV on coupler, 4 SCFM air flow
- Forward power gradually increased to 5 kW (administrative limit for SSR1) in pulsed mode with duty factor 2% (20 Hz pulse rep. rate, 1ms pulse duration), dwelled at maximum power for 15 min, making sure that there no FEP, PMT and vacuum activity, no bias current/voltage spikes/dips
- Repeat with 4%, 8% and 15% DF (2ms, 4ms and 7.5ms)
- Repeat in CW mode



Courtesy of A.Sukhanov

# Proto SSR1 CM assembly

- Eight qualified couplers are installed in SSR1 prototype CM.
- SSR1 CM under testing @PIP2IT. Some coupler heating data are available for analysis.





# Current status of SSR couplers:


---

- Four SSR2 couplers will be produced by CPI and four coupler will produced by French colleagues (procurement awarded).
- All couplers are supposed to pass trough high power acceptance test at room temperature test stand. **Acceptance criterium is successful operation at power level 12 kW, CW, full reflection (requirements for SSR2 coupler).**
- “Successful operation” is to stay at each reflected phase point (4-8 pints) for 1-2 hour (to reach thermal equilibrium).
- Cleaning, baking, RGA scan at vendor. Fermilab will assembly cold parts for RF tests at clean room, bake 120C/48hrs. After RF test coupler will be disassembled in clean room and put on vacuum manifold. For prototype series procedure can be different.



# Two type of prototypes were designed, built and tested

## 650 MHz coupler without copper coatings (with EM shields):




## Vacuum parts of couplers:

- a) copper coated
- b) with EM shields




## 650 MHz coupler with copper coatings



# New design of 650MHz coupler based on prototype experience

## Coupler Assembly F10056895



# 650MHz Coupler Testing Requirements (ED0010867)

---

- The maximum power delivered by HB650 cavities to the beam is about 43 kW at 2 mA beam current with ~20% reflection.
- Considering an additional allowance for microphonics compensation and coupling mismatch and assure operational reliability with suitable overhead coupler shall be tested and qualified **at 50 kW input RF power with full reflection and arbitrary reflection phase (see PIP-II TRS)**. The total propagating power (forward + reflected) inside the coupler will be 100kW.

## Testing Protocol for 650 MHz couplers (repeated 4 times for each phase point).

- Pulse length 10ms, Power ramp 0 => 100 kW, Rep.rate 1 Hz (max. aver. power 1 kW)
- Pulse length 100ms, Power ramp 0 =>100 kW, Rep.rate 1 Hz (max. aver. power 10 kW)
- Pulse length 650ms, Power ramp 0 => 80 kW, Rep.rate 1 Hz (max. aver. power 52 kW)
- Pulse length CW, Power ramp 0 => 50 kW, after that stay 2 hours at 50kW.


*\*Note: The pulse length in each step may vary depending of outgassing activity during processing.*

**HV bias +4 kV (adjustable up to +5kV maximum) to suppress multipactoring.**

**Air flow should be above 10 SCFM (standard cubic feet per minute), typical value 23 SCFM (5 g/s).**




# Coupler Test stand schematic and RF power



Power source used for the coupler test is IOT with maximum CW power 30kW. Power available for the coupler test ~100kW obtained due to resonance conditions between movable reflector and movable short (amplification x 5-7 )

# Test stand configuration


- Assembled with chamber in the clean room. Antennas connected by **bridge** made of multi-wire (1<sup>st</sup> test) or solid copper (2<sup>nd</sup>).
- Vacuum assembly leak checked and baked at 120°C 48 hrs. Warm parts connected at test stand later.
- In first test the simple copper tubes used (no bellows). Later we use designed parts.





## Temperature sensors:

RF window (1,2); 5K intercept (5,6); 50K intercept (7,8); Air outlet tube (3,4); chamber ("Air").


# Antennas inter-connections



Connection between antennas before tests



After tests  
Everything looks OK







# Testing history

---


- **Prototype B (conventional):**
  - **Test#1** (antennas connected with multi-wire bridge).
    - Slow processing (outgassing).
    - Achieved 50kW@90°, 32kW@180°, 28@270°, 3kW@0°.
    - Metallization on Cu plating surfaces
  - **Test#2:** (antennas connected with solid Cu bridge):
    - HP processing with DS;
    - Waveguide heating test
- **Prototype A (EM shielded):**
  - HP processing with DC (nominal)
  - DC polarity test
  - HP processing w/o DC bias
  - Test with nominal warm parts (SS copper plated with bellows)
  - Memory test

# Test results for conventional design (prototype B)



Fast processing at 90 and 0 degree phase, longer processing at 270 deg, no bias current


# Temperature in coupler





- Maximum temperature at air outlet tube (50°C)
- Temp signals show kind of mirror symmetry at 270 deg ( $T1=T2$ ;  $T5=T7$ ;  $T6=T8$ )  
→ high fields in chamber and bridge area.
- Air flow  $\sim 5$  g/s in each coupler



# Waveguide heating test (narrow WG).



- Waveguide was heated during coupler tests.
- For comparison with simulation we tested temperature of waveguide for different levels of power in CW regime 10kW, 20kW, 30kW & 40kW.
- Reflection phase was **0 degrees** in this test. For test all fans were switched off to provide pure convective cooling regime, short plate of the narrow waveguide was water cooled as designed.



# Waveguide heating simulations


Power dissipation (W) and maximum temperature in the aluminum waveguide and adapter, convection cooling is assumed (simulation results).

	100kW, TW	50kW, 0°	50kW, 90°	50kW, 180°	50kW, 270°
Power dissipation in “narrow” WG, W	199	78.7	245.3	314.5	148
Power dissipation in current Adapter, W	105	96.6	88.8	112.7	120.5
Total power dissipation	304	175.3	334.1	427.2	268.5
Temp with water cooling	59 C°	51 C°	57 C°	68 C°	62 C°
Temp w/o water cooling	100 C°	66 C°	114 C°	137 C°	89 C°

To compare with 176 W and  $T_{\max}=57\text{ C}^{\circ}$  in standard WR-1150. Standard WR-1150 is used in new coupler design, no water cooling


# Coupler EM-shielded design (prototype A)-test with DC bias

## RF power and Vacuum



- HP processing history for EM shielded design for 4 different configuration for reflection: phases: 90; 0; 180; 270 degrees.
- DC bias 4-4.5kV.


## Temperature (C) at different coupler locations






# HV bias polarity test.

To understand effect of bias polarity on coupler performance the polarity was switched from positive to negative and processing was repeated using same protocol (270 deg phase).




- Positive and negative 3kV bias was applied for short pulses (10ms) to compare the MP threshold.
- For **negative** polarity the MP activity starts at about 18 kW, while for the positive bias the threshold was moved to 50 kW power level. W/o bias MP starts at ~6 kW at full reflection.
- For negative polarity couplers were conditioned for ~ 4 hrs at 10 ms pulses ramping power up to 100 kW. The vacuum was ~ 4.E-6 Torr and signal noisy ('hairy'), which indicates that MP was not suppressed completely.




- For positive +3.2kV bias coupler was processed 4 hrs: 10ms, 100ms, 650ms and CW up to 50 kW. No any unusual vacuum activity, no MP for this polarity
- For negative polarity -5kV, processing is better, but still signature of MP on vacuum signal.

# 650 Coupler processing(v.A) without HV bias

Green-power(W)  
Magenta-vacuum  
Yellow/Red-Temp



270 deg




0 deg

90 deg


+3kV bias on

+3kV bias off



(no MP) 90 deg

180 deg



180 deg, 50kW, CW

# RF conditioning w/o HV bias for EM shielded coupler

---

## Results and conclusion:

- 1) Couplers were conditioned at 4 phase points.
- 2) Total time of conditioning was about 30 hours (all phases).
- 3) Couplers can be conditioning at all phase points to vacuum level  $P < 1\text{E-}6$  Torr, which allows to work at full power without HV bias,
- 4) At some reflected phase points MP does not disappear completely. Some small activity still exists. When HV bias +3kV is applied vacuum becomes better (for example from  $7\text{E-}7$  to  $2\text{E-}7$ )
- 5) Place of MP is not known. It can be ceramic window, connecting chamber, etc.




## Testing with baseline warm parts (SS tubes and bellows, copper plated inner and outer conductors)



Two EM-shielded couplers were re-assembled with baseline warm parts:  
Some extra-reflection in the coupler chain (most likely bridge geometry change)

# Test with nominal warm parts (SS copper plated tubes/bellows)


With nominal warm parts coupler tested with bias (OK), then were conditioned w/o bias. More conditioning required for 180 deg and 270 deg reflection phases




- no MP activity, fast processing for 0°; 90°, sign of MP at 180°, more activity at 270°.
- 270 deg phase after processing was used for “Memory test”

# Memory test (without HV bias):

Goal: After RF processing w/o HV bias for 270 deg (worst case), then fill system with dry nitrogen, pump it again and check if coupler remember processing



Nov.12 - Fill with 1bar Nitrogen for 2hrs



After N infusion;

Test up to 60kW 500ms, no bias, no MP

Conclusion: coupler remember rf processing after exposition to nitrogen

# Summary

---

## Conventional design:

- With modifications done after 1<sup>st</sup> test couplers reached required CW power level w/o MP after short processing (DC bias +4.5kV)

## EM shielded design:

- 50kW CW power level was achieved after short processing for each reflection phase.
- Repeated for nominal configuration of warm part

**Finally both couplers were qualified at 50kW full reflection at arbitrary reflection phase.**


## Extra tests (EM-shielded design)

- **HP processing without bias successfully demonstrated (~30hrs for all phases).**
- **Waveguide heating was measured. Temperature is high, Standard WR1150 was proposed to reduce power heating (current design)**
- **“Memory Test” to demonstrate that coupler remember RF processing w/o bias after explosion on dry nitrogen for several days. Yes it works.**




# New vacuum chamber of the test stand with capacitive coupling


New chamber with dummy couplers:



Thermal simulations:



Max. T < 60C for 50 kW, CW, full reflection



Other upcoming test stand upgrades: Pumping station with better pumping rate, water cooling manifold for strap connections

---

# Thank you

# Coupler Incoming Inspection (QC) at FNAL

- Incoming inspection will be governed by a Vector traveler which will be developed prior to receipt of couplers
- Will rely in part on vendor supplied QA/QC documentation
  - Vendor will follow QA plan that developed and approved at initiation of contract
  - Similar to plan followed for LCLS-II coupler procurement
- Areas covered in the incoming QC at FNAL are:
  - Documentation completeness
  - Component completeness (are all the parts there?)
  - Visual inspection
  - Leak check
  - Dimensional inspection reports review
  - RGA and bakeout results
  - Cleanliness