



PIP-II Requirements Management Process

Lidija Kokoska/ Fermilab

PIP-II Technical Workshop

December 2nd, 2020

A Partnership of:

US/DOE

India/DAE

Italy/INFN

UK/UKRI-STFC

France/CEA, CNRS/IN2P3

Poland/WUST



Background Bio

- Lidija Kokoska
 - Organization: PIP-II Technical Integration Office
 - Role: PIP-II Project Engineer since start of 2020 (1 year)
 - Responsible for coordinating PIP-II project-wide systems engineering processes
- Other Roles
 - 8 years at Fermilab
 - Deputy Department Head of APS-TD Magnet Test & Instrumentation Department (3 years)
 - Fermilab Mechanical Engineer (8 years)
 - 5 years in private industry
 - High Pressure Filtration Equipment for Aerospace, Renewable Energy, and Oil & Gas Industries
- lkokoska@fnal.gov

Overview

- PIP-II Requirements Management Plan
- Requirement Types
- Requirement Development & Guidelines
- Requirement Validation & Review
- Requirement Traceability & Metadata
- Requirements Verification
- Approval & Revision
- Additional Requirements Management Documents
- Partner Requirements

PIP-II Requirements Management Plan

PIP-II Requirements Management Plan

Document number: ED0008235 Rev. A

Document Approval

| Signatures Required | Date Approved |
|---|----------------|
| Originator: Integration Team | - |
| Approver: Alex Martinez, Integration Coordinator | Approved in TC |
| Approver: Jeremiah Holzbauer, SRF Coordinator | Approved in TC |
| Approver: Allan Rowe, In-Kind Technical Integration Coordinator | Approved in TC |
| Approver: Lidija Kokoska, Project Engineer | Approved in TC |
| Approver: Eduard Pozdeyev, Project Scientist | Approved in TC |
| Approver: Arkadiy Klebaner, Technical Director | Approved in TC |

Revision History

| Revision | Date of Release | Description of Change |
|----------|-----------------|-----------------------|
| - | 7/12/2019 | Initial Release |

“The Requirements Management Plan provides a process to control, identify, manage, review, approve, release, and revise PIP-II requirements for the PIP-II Work Breakdown Structure (WBS) systems.”

Table of Contents

| | |
|--|-------|
| 1. Scope..... | 4 |
| 2. Acronyms | 4 |
| 3. Roles and Responsibilities | 4 |
| 4. Requirements Framework..... | 5 |
| 4.1. Global Requirement Document (GRD)..... | 5 |
| 4.2. Physics Requirement Document (PRD)..... | 6 |
| 4.3. Functional Requirements Specifications (FRS)..... | 6 |
| 4.4. Technical Requirements Specifications (TRS)..... | 8 |
| 5. FRS Development..... | 8 |
| 6. Validation and Review..... | 9 |
| 7. Requirements Traceability and Metadata..... | 11 |
| 7.1. GRD and PRD Traceability | 11 |
| 7.2. TRS Traceability | 12 |
| 7.3. Verification..... | 12 |
| 8. Verification Process | 13 |
| 9. Approval and Revision | 15 |
| 10. Partner Requirements..... | 16 |
| | .. 16 |




Requirement Types and Flowdown

- Requirements Framework derived from Mission Need Statement:


“The current beam power of 700 kW is insufficient to meet the P5 goal of delivering 120 MW-kton-years by 2035. Increasing the beam power to 1.2 MW would roughly double the DUNE data-taking rate, significantly increasing the competitive edge of the experiment by halving the time it would take to achieve significant scientific results. This in turn raises the probability that the U.S. neutrino physics program will continue to outperform the Japanese program – the closest competitor – in the 2020s. This need for higher proton beam power comes at a time when many components of the existing Fermilab accelerator complex that delivers beam to the Main Injector - especially the linear accelerator (Linac) and the Booster - are approaching 50 years old. Thus, a proton beam power upgrade is proposed to meet two main capability gap and mission need goals:

- 1. To reduce the time for LBNF/DUNE to achieve world-first results.*
- 2. To sustain high reliability operation of the Fermilab accelerator complex.”*



Requirement Types & Flowdown

- GRD – Global Requirements Document (ED0001222)
 - Highest project-level requirements document
 - Specifies performance requirements derived from Key Performance Parameters (KPPs) defined in Mission Need Statement
- PRDs – Physics Requirement Documents
 - Summary parameters and configuration definitions (not only related to physics)
 - Top Level requirements that cross boundaries between multiple systems
- FRSs – L3 Functional Requirements Specifications
 - Contains project needs or requested behavior of L3 system
 - Specifies core functions for system
- TRSs – L3 Technical Requirements Specifications
 - Contains technical parameters that the L3 system or complex component must fulfill
 - Impact the overall sub-systems' performance
- Sub-Level FRSs and TRSs
 - Managed at the discretion of the L2 and L3 manager



PRDs

- Physics Requirements Documents derived from the PIP-II Preliminary Design Report
- Establish a traceable link to lower level FRSs and TRSs
- Impact beam or machine performance
- Contains basic parameters and configurations of the overall design of PIP-II accelerator and complex

Table 4-1. List of Physics Requirements Documents (PRDs)

| # | Physics Requirement Document | Teamcenter # |
|----|---|--------------|
| 1 | PIP-II Parameters PRD | ED0010216 |
| 2 | PIP-II Linac RF System PRD | ED0010220 |
| 3 | SRF Cavity Parameters PRD | ED0010221 |
| 4 | RT Linac RF Cavity Parameters PRD | ED0010222 |
| 5 | Accelerator Upgrades RF Cavity Parameters PRD | ED0010223 |
| 6 | Controls PRD | ED0010225 |
| 7 | Magnet PRD | ED0010226 |
| 8 | Vacuum PRD | ED0010228 |
| 9 | Timing system PRD | ED0010229 |
| 10 | Beam Instrumentation PRD | ED0010230 |
| 11 | Misalignment Tolerances PRD | ED0010231 |
| 12 | Machine Protection System PRD | ED0010232 |
| 13 | Beam Dumps and BTL Collimators PRD | ED0010235 |
| 14 | Booster Dampers PRD | ED0010236 |
| 15 | Booster Collimators PRD | ED0010237 |
| 16 | MI Gamma_t jump PRD | ED0010238 |
| 17 | Injection into Booster PRD | ED0010242 |
| 18 | Beam Loss PRD | ED0010243 |
| 19 | Cryogenic Heat Load PRD | ED0008200 |

Fermilab

FERMILAB
FEDERATED NATIONAL ACCELERATOR LABORATORY

PIP-II Parameters
Physics Requirement Document (PRD)

Document number: ED0010216

Document Approval

| Signature Required | Date Approved |
|---|-------------------------|
| *Original: Lowell Pritch, Warm Front End L3 Manager | - |
| *Original: Aaron Lee, SPS/PS/RF Development Department | - |
| *Original: Shigeo Tanabe, Transfer Line/Beam Absorber L3 Manager | - |
| *Original: Yu Wang, Instrumentation L3 Manager | - |
| *Original: Bruce Hines, Magnets/PS L3 Manager | - |
| *Concurrence: Alan Martinez, Integration Coordinator | - |
| *Concurrence: Genda Wu, RF and Cryo Systems L3 Manager | - |
| *Concurrence: Brian Hansen, Accelerator Systems L3 Manager | - |
| *Concurrence: Fernando G. Garcia, Laser Installation and Commissioning L3 Manager | - |
| *Concurrence: James Kewell, Accelerator Complex Upgrades L3 Manager | - |
| *Approved: Michael Rydstrom, Project Scientist | Approved on: 12/20/2020 |

Revision History

| Revision | Date of Revision | Description of Change |
|----------|------------------|-----------------------|
| 1 | 12/20/2020 | Initial release |

Managed by Fermilab Research Alliance, LLC for the U.S. Department of Energy, Office of Science
www.fnl.gov

U.S. DEPARTMENT OF ENERGY
Office of Science

PIP-II Parameters

7. Warm Front End

The PIP-II Warm Front End (WFE) consists of two ion sources, a LEET, an RFQ, and a MEET. The H-beam originates from a DC ion source and is transported through the LEET to a CW normal-conducting RFQ, where it is bunched and accelerated to 2.1 MeV. The MEET transports and matches the beam to the first SRF cryomodur. In the MEET, a fast, bunch-by-bunch chopper provides the required bunch pattern, removing 60-80% of the bunches according to a pre-programmed timeline. The pictogram of the WFE is shown in Figure 7-1.




Figure 7-1. WFE Pictogram.

Table 7-1 lists the beam line components that form the ion source and the LEET. Figure 7-2 shows the beam horizontal emittance (u2) for the partially air-insulated LEET optics section simulated with TraceWin for the nominal beam current of 5 nA.

Fermilab National Accelerator Laboratory

PIP-II Parameters

Table 7-4. MEET Components List

| Parameter | Units | Value | Comment |
|---|-------|------------------------|----------------------------|
| Power amplifiers (ED000357/ED000358) | | | Solid state |
| RF frequency | MHz | 162.5 | - |
| Maximum power output at saturation | kW | 75 | CW |
| Couplers (ED000359/ED000360) | | | |
| RF power rating (max) | kW | 75 | Full reflection capability |
| Duty factor (nominal) | % | 100 | - |
| Beam power supply (DC) | kV | 5 | - |
| Cryomodur (ED000361) | | | |
| RF power rating (max) | kW | 75 | CW |
| Minimum bandwidth | MHz | 1 | - |
| Operating temperature | °F | 86 | Water cooled |
| Water cooling system | | | |
| Nominal temperature | °C | 30 | (i.e. 86°F) |
| Water temperature stability (rms) | °C | ± 0.1 | Steady state |
| Vacuum (ED000362) | | | |
| Operating pressure | torr | < 0.1x10 ⁻⁹ | - |

Table 7-4 lists the beam line components that form the MEET.

Table 7-4. MEET Components List

| Component | Count | Comment |
|--------------------------------|-------|--|
| Quadrupole doublets | 2 | 2 Longitudinally doublets per doublet. Additional information in ED000312 / ED000347 |
| Quadrupole triplets | 9 | 2 Shortitudinally triplets and 1 Longitudinally triplet per triplet. Additional information in ED000347 / ED000387 |
| Steering optics assemblies | 11 | Both horizontal and vertical per assembly. Additional information in ED000387 |
| Bunching cavities | 4 | Additional information in ED000387 |
| BPM (1.25") | 11 | - |
| ADCT | 2 | - |
| DCCT | 1 | - |
| Long Pk-LP (BPM) | 4 | 2 upstream of the absorber and 2 downstream |
| Endurance scanner (Alcon-type) | 1 | Two heads: 1 horizontal and 1 vertical |

Fermilab National Accelerator Laboratory

7

12/2/2020

Kokoska | Requirements Management/Technical Workshop | PIP-II

FRS Development & Guidelines

- FRS Guidance Document and Template (ED0007977)
- FRS required for each individual L3 sub-system
- Individually listed in tabular form
- Unique identifier assigned to individual requirement (F-WBS#-xxx)
- “Shall” term used to develop definitive statements

Table 5-1. Example FRS Format

| Requirement # | Requirement Statement |
|--------------------|---|
| F-121.2.03.02-C001 | The SSR1 cryomodule shall contain Beam Position Monitoring systems adjacent to each focusing element. |
| F-121.2.03.02-C002 | The SSR1 cryomodule internal wiring shall be of a material and size that minimizes heat load to the internal systems. |
| F-121.2.03.02-C003 | The SSR1 cryomodule shall have thermometry to allow for monitoring and control under all expected operational scenarios. |
| F-121.2.03.02-C004 | The SSR1 cryomodule shall have pressure instrumentation to allow for monitoring and control under all expected operational scenarios. |
| F-121.2.03.02-C005 | The SSR1 cryomodule shall have vacuum instrumentation to allow for monitoring and control under all expected operational scenarios. |
| F-121.2.03.02-C006 | The SSR1 cryomodule shall have cryogen level instrumentation to allow for monitoring and control under all expected operational scenarios. |
| F-121.2.03.02-C007 | The SSR1 cryomodule shall have internal magnetic field probes to allow for monitoring and control under all expected operational scenarios. |

TRS Development & Guidelines

- New TRS Guidance Document and Template (ED0012980)
- TRS required for each individual L3 sub-system or as a set of TRSs written at device level
- Background context and justification narrative allowed, but requirement individually listed.
- Requirements summary table listed as separate meta-data sheet.
- Unique identifier assigned to individual requirement (T-ED#-xxx)
- “Shall/will/should” terms used to develop definitive statements




Figure 5.2-1 – Basic schematic of cryogenic circuit.

5.2.1. Cryogenic System Pressure Ratings

Anchoring and thermal contraction of each cryogenic circuit will consider worst case pressure, temperature and alignment extremes.

T-ED0009659-A001: Each cryogenic circuit identified in Table 5.2 shall be capable of cool-down and warm-up to their noted design temperatures, independent of the state of other circuits.

T-ED0009659-A002: The cryogenic circuits shall be capable of the associated MAWP at the noted temperature as specified in Table 5.2.

Table 5.2 CRYOGENIC SYSTEM PRESSURE RATINGS

| System | Warm MAWP | Cold MAWP |
|-------------------------------|---|---------------|
| 2 K, low pressure | 2.05 bar @ 300K | 4.1 bar @ 2 K |
| 2 K, positive pressure piping | 20 bar @ 300K | 20 bar @ 2 K |
| 5 K piping | 20 bar @ 300K | 20 bar @ 5 K |
| 35-50 K piping | 20 bar @ 300K | 20 bar @ 50K |
| Insulating vacuum | 1 bar @ 300K (external) vacuum inside | N/A |

| TRS Requirement Information | | | | Impacted Stakeholders | | | Upward Traceability | | | | | |
|-----------------------------|----------|-----------------|-----------------------------|--|---------------------------|---------------------------|------------------------------|---------------|-----------------|--------------------|-------------|-------------------------------|
| TRS Name | TRS TCR# | Requirement ID | TRS Statement | Impacted L3 System or Stakeholder Organization | Assigned Stakeholder Name | Comments from Stakeholder | Driving Document Type | Document Name | Document Number | Requirement Number | Sub-Heading | Driving Requirement Statement |
| | | | | | | | (sub-section, if applicable) | | | | | |
| Technica ED000XXX | | T-ED000XXX-A001 | Device XXXYYYZZZ shall | | | | FRS | | | | | |

Requirement Validation & Review

- Requirements to be validated and reviewed against stakeholder expectations
- Assures the given design will meet the system and project objectives
- Performed through the project lifecycle as requirements change (ideally prior to design reviews)
- Ensures requirements are:
 - Achievable
 - Clear
 - Complete
 - Consistent
 - Singular
 - Traceable
 - Verifiable




Figure 6-1. Functional Requirements Management Process

Requirement Traceability & Metadata

- Requirements traceability is done at the L3 functional requirement level
- Meta-Data Sheets for each L3 FRS
 - Lists all the FRS requirements individually with the unique requirements identifier
 - Displays the requirement description
 - Includes sections for documenting upper GRD and PRD traceability
 - Includes a section for documenting lower TRS traceability
 - Includes a section for verification information (description, method, timeline, etc.)

| | | | | | | | | | |
|------------------------------------|-----------|---|-------------------------------|-------------------------|---|--------------------------------------|--------------------------------|---|-----|
| PIP-II High Power RF FRS | | | ED0008023 | FRS Metadata Datasheet | | | | | |
| Tier 1 Upward Traceability (GRD) | | | Tier 2 Upward Traceability | | | FRS Existing Requirement Information | | | |
| T1 Document Name | T1 TC # | Tier 1 Statement | T2 Document Name | T2 TC # | Tier 2 Statement | Requirement #2 | Sub-Heading3 | Requirement Statement4 | TR |
| Global Requirements Document (GRD) | ED0001222 | Requirement I4 states the reliability requirement for the SRF Linac. | Best Practices | None | Best practice for equipment protection. | F-121.3.03-C001 | Self-Preservation Requirements | The HPRF system amplifiers shall not re-enable the output after being disabled by a trip until the trip is RESET. | 32/ |
| Global Requirements Document (GRD) | ED0001222 | Requirement I4 states the reliability requirement for the SRF Linac. | Best Practices | None | Best practice for equipment protection. | F-121.3.03-D001 | Cavity Protection Requirements | The HPRF system amplifiers shall accommodate an input signal that will disable the output of the amplifier in a fail-safe manner. | TB |
| No further upward traceability | None | NA | Machine Protection System PRD | ED0010220 | Section 5 of the MPS PRD on system architecture discuss signal inputs to the MPS such as RF status. | F-121.3.03-D001 | Cavity Protection Requirements | The HPRF system amplifiers shall provide an output signal that represents the output disabled state of the amplifier (for MPS). | TB |
| TRS Downward Traceability | | | | | | Requirement Verification | | | |
| TRS Name | TRS TC # | TRS Statement | Verification Method | Verification Document # | Verification Description | Verification Timeframe | Verification Status | | |
| 325 MHz 7 kW SS RF Amplifier TRS | ED0004290 | Section 7.3 on internal protection, item X lists the requirement regarding the RESET command. | Demonstration/Test | Commissioning documents | Design verification will be done during the review cycle and finally during commissioning. | During commissioning | Open | | |
| TBD | TBD | TBD | Demonstration/Test | Commissioning documents | Design verification will be done during the review cycle and finally during commissioning. | During commissioning | Open | | |
| TBD | TBD | TBD | Demonstration/Test | Interface documentation | Design verification will be done during the review cycle and finally during commissioning. | During commissioning | Open | | |

Requirement Traceability & Metadata

- FRS's are centerpiece of requirements management
- FRS's bridge gap between higher level project requirements & lower-level design technical requirement




Figure 7-1. Example Traceability Flow Chart for SSR1


Requirement Traceability & Metadata

- GRD & PRD traceability upstream of FRS
 - “Self-Derived” or “Best Practice” noted where there is no direct traceability of FRS origin
- TRS traceability downstream of FRS
 - “Self-Derived” or “None” noted where there is no direct traceability of TRS to FRS
- Verification Traceability:
 - Verification Method
 - Verification Document #
 - Verification Description
 - Verification Timeline
 - Verification Status

| | | | | | | | | | | | | | |
|------------------------------------|-----------|--|-------------------------------|---------|---|--------------------------------------|--------------------------------|---|--------------------------|-------------------------|--|------------------------|---------------------|
| PIP-II High Power RF FRS | | | ED0008023 | | | FRS Metadata Datasheet | | | | | | | |
| Tier 1 Upward Traceability (GRD) | | | Tier 2 Upward Traceability | | | FRS Existing Requirement Information | | | | | | | |
| T1 Document Name | T1 TC # | Tier 1 Statement | T2 Document Name | T2 TC # | Tier 2 Statement | Requirement #2 | Sub-Heading3 | Requirement Statement4 | TR | | | | |
| Global Requirements Document (GRD) | ED0001222 | Requirement I4 states the reliability requirement for the SRF Linac. | Best Practices | None | Best practice for equipment protection. | F-121.3.03-C001 | Self-Preservation Requirements | The HPRF system amplifiers shall not re-enable the output after being disabled by a trip until the trip is RESET. | 32! | Amplifier | | | |
| Global Requirements Document (GRD) | ED0001222 | Requirement I4 states the reliability requirement for the SRF Linac. | Best Practices | None | Best practice for equipment protection. | F-121.3.03-D001 | Cavity Protection Requirements | The HPRF system amplifiers shall accommodate an input signal that will disable the output of the amplifier in a fail-safe manner. | TB | Amplifier | | | |
| No further upward traceability | None | NA | Machine Protection System PRD | ED00102 | | TRS Downward Traceability | | | Requirement Verification | | | | |
| | | | | | | TRS Name | TRS TC # | TRS Statement | Verification Method | Verification Document # | Verification Description | Verification Timeframe | Verification Status |
| | | | | | | 325 MHz 7 kW SS RF Amplifier TRS | ED0004290 | Section 7.3 on internal protection, item X lists the requirement regarding the RESET command. | Demonstration/Test | Commissioning documents | Design verification will be done during the review cycle and finally during commissioning. | During commissioning | Open |
| | | | | | | TBD | TBD | TBD | Demonstration/Test | Commissioning documents | Design verification will be done during the review cycle and finally during commissioning. | During commissioning | Open |
| | | | | | | TBD | TBD | TBD | Demonstration/Test | Interface documentation | Design verification will be done during the review cycle and finally during commissioning. | During commissioning | Open |

Requirements Verification

- Process that confirms the given design and implementation meets the functional requirements
- Verification performed in three ways:
 - Inspection
 - Demonstration/Test
 - Analysis
- Completed at various stages of the project
 - L3 FRSs reviewed for compliance at each review stage



Requirements Approval & Revision

- May occur at any time during the project lifecycle
- Change control required to assure:
 - Latest approved requirements are used
 - Changes aren't made without authorization
 - Changes are traceable
 - Impact analysis on other systems is performed
- At a minimum, approval is required by L2M and impacted stakeholders

Additional Requirement Management Documents

- Occasionally additional documents are required for “customer” and “supplier” agreements:
 - PIP-II Cryogenic Heat Load Analysis (ED0008200) ➔ Cryoplant Requirements



PIP-II Cryogenic Heat Load Analysis Physics Requirement Document (PRD)

Document number: ED0008200, Rev. - B


Table 2: HWR cryogenic heat load summary

| HWR | Each unit (W) | | | | | # | Total (W) | | | | |
|---------------------------|------------------------------|------------------------|-----------------|-------------------|-----------------------|---|------------------------------|------------------------|-----------------|-------------------|-----------------------|
| | HTTS (40 K Supply/Return) | LTTS (4.5 K Return) | 4.5 K Supply | 2 K Isothermal | 2 K Non-isothermal | | HTTS (40 K Supply/Return) | LTTS (4.5 K Return) | 4.5 K Supply | 2 K Isothermal | 2 K Non-isothermal |
| Cavity dynamic | 0.00 | 1.00 | 0.0 | 0.80 | 0.00 | 8 | 0.0 | 8.0 | 0.0 | 6.4 | 0.0 |
| Input coupler (dynamic) | 5.90 | 0.60 | 0.0 | 0.09 | 0.00 | 8 | 47.2 | 4.8 | 0.0 | 0.7 | 0.0 |
| Current leads (dynamic) | 15.00 | 2.00 | 0.0 | 0.50 | 0.00 | 8 | 120.0 | 16.0 | 0.0 | 4.0 | 0.0 |
| Beam (dynamic) | 0.00 | 0.00 | 0.0 | 5.90 | 0.00 | 1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Input coupler (static) | 2.60 | 1.60 | 0.0 | 0.06 | 0.00 | 8 | 20.8 | 12.8 | 0.0 | 0.5 | 0.0 |
| Current leads (static) | 6.00 | 9.00 | 0.0 | 1.50 | 0.00 | 8 | 48.0 | 72.0 | 0.0 | 12.0 | 0.0 |
| Strongback hangers | 0.00 | 0.00 | 0.0 | 0.05 | 0.00 | 6 | 0.0 | 0.0 | 0.0 | 0.3 | 0.0 |
| Conduction beam line | 0.20 | 0.10 | 0.0 | 0.10 | 0.00 | 2 | 0.4 | 0.2 | 0.0 | 0.2 | 0.0 |
| Thermal shield | 116.00 | 0.00 | 0.0 | 3.00 | 0.00 | 1 | 116.0 | 0.0 | 0.0 | 3.0 | 0.0 |
| View ports | 0.20 | 0.00 | 0.0 | 0.70 | 0.00 | 4 | 0.8 | 0.0 | 0.0 | 2.8 | 0.0 |
| Relief line | 1.00 | 0.00 | 0.0 | 0.50 | 0.00 | 1 | 1.0 | 0.0 | 0.0 | 0.5 | 0.0 |
| Valves & Instrumentations | 10.00 | 2.19 | 0.8 | 2.00 | 0.00 | 1 | 10.0 | 2.2 | 0.8 | 2.0 | 0.0 |
| Helium manifold | 0.00 | 0.00 | 0.0 | 5.00 | 0.00 | 1 | 0.0 | 0.0 | 0.0 | 5.0 | 0.0 |
| Vacuum manifold | 0.00 | 0.00 | 0.0 | 0.50 | 0.00 | 1 | 0.0 | 0.0 | 0.0 | 0.5 | 0.0 |
| Slow tuner | 0.00 | 0.00 | 0.0 | 0.05 | 0.00 | 8 | 0.0 | 0.0 | 0.0 | 0.4 | 0.0 |
| Total dynamic | | | | | | | 167.2 | 28.8 | 0.0 | 11.1 | 0.0 |
| Total static | | | | | | | 197.0 | 87.2 | 0.8 | 27.18 | 0.00 |



Additional Requirement Management Documents

- Occasionally additional documents are required for “customer” and “supplier” agreements:
 - PIP-II Room Data Sheet (ED0009544) → CF Linac Complex Requirements




Room Data Sheet PIP-II

#N/A = Denotes missing information
= These cells are automatically calculated, no input required
= Data cells not applicable

Auto-filled cells **Start Here** ↓

| Identifier | WBS Level 2 | WBS ID | WBS Name | Space Designation Location | Sub-System | User Defined Sub-System | Component | Description | Quantity |
|------------|-------------|-----------|-----------------|----------------------------|-----------------------------|-------------------------|----------------|--|----------|
| DM-001 | 121.03 | 121.03.07 | Controls | LG-BTL | Computers, Front End | Candidate for F37 | Racks | Networking, permits etc. | 3 |
| DM-002 | 121.03 | 121.03.08 | SS | LG-BTL | Interlocks | Candidate for F37 | Racks | ESS interface | 1 |
| DM-003 | 121.03 | 121.3.06 | Controls | BTL-F3 Building | PLCLCW Controls | Candidate for F37 | Racks, Rittal | Rittal half size cabinet (needs to remain at F3) | 1 |
| DM-004 | 121.03 | 121.03.06 | Vacuum | BTL-F3 Building | Ion Pump PS System | Candidate for F37 | Racks | Bulk, ion pump PS, gauge interface, network switch | 2 |
| DM-005 | 121.03 | 121.03.09 | Instrumentation | LG-BTL | BPM | Candidate for F37 | Racks | | 2 |
| DM-006 | 121.03 | 121.03.09 | Instrumentation | BTL-F3 Building | BPM | Candidate for F37 | Racks | | 1 |
| DM-008 | 121.03 | 121.03.05 | Magnets | BTL-F3 Building | Fast Dipole Switch | Candidate for F37 | Racks | Pulse Magnet Power Supply | 1 |
| DM-009 | 121.03 | 121.03.05 | Magnets | LG-BTL | Fast Dipole Switch | Candidate for F37 | Cables | Power Supply | 8 |
| DM-010 | 121.03 | 121.03.05 | Magnets | LG-BTL | Fast Dipole Switch | Candidate for F37 | Magnets | Power Supply | 1 |
| DM-011 | 121.03 | 121.03.05 | Magnets | BTL-F3 Building | Magnets, Dipole | Candidate for F37 | Power Supplies | TeV PS | 1 |
| DM-012 | 121.03 | 121.03.05 | Magnets | BTL-F3 Building | Magnets, C-dipole | Candidate for F37 | Power Supplies | 125KW Spange PS | 1 |
| DM-013 | 121.03 | 121.03.05 | Magnets | BTL-Beamline Tunnel | Magnets, Dipole | | Cables | Dipole cables | 134 |
| DM-014 | 121.03 | 121.03.05 | Magnets | BTL-Beamline Tunnel | Magnets, Dipole | | Cables | Specialty magnet cables | 18 |
| DM-015 | 121.03 | 121.03.05 | Magnets | BTL-F3 Building | Magnets, Regular Quadrupole | Candidate for F37 | Racks | Quadrupole Power Supplies | 3 |



Level of Design Spatial Requirements Floor Requirements

ED0009544 PIP-II Room Data Sheet

| By Area Designation | Power | | | | By System | Power | | | | By Feeders | Power | | | |
|--------------------------|-------|-----|-------|----|-------------------------|-------|-----|-------|----|-------------------------|-------|-----|-------|----|
| | 21638 | KVA | 19943 | KW | | 21638 | KVA | 19943 | KW | | 21638 | KVA | 19943 | KW |
| HBB | 703 | | 702 | | HWR | 0 | | 0 | | Feeder 1 (23-1)* | 6301 | | 5419 | |
| HBB-Lower High Bay | 456 | | 456 | | SSR | 0 | | 0 | | HB650 Amplifiers | 4201 | | 3612 | |
| HBB-Upper High Bay | 236 | | 235 | | Elliptical | 0 | | 0 | | LG-Upgrade* | 2100 | | 1806 | |
| HBB-Control Room | 7 | | 7 | | CP | 3245 | | 3245 | | Feeder 2 (23-2) | 5518 | | 4821 | |
| HBB-Tech Support Space | 0 | | 0 | | CDS | 119 | | 119 | | HWR Amplifiers | 126 | | 113 | |
| HBB-Computer Space | 3 | | 3 | | MPS | 5 | | 5 | | SSR2 Amplifiers | 244 | | 220 | |
| HBB-Exterior Space | 0 | | 0 | | HPRF | 11832 | | 10253 | | SSR2 Amplifiers | 1513 | | 1362 | |
| LT | 41 | | 41 | | LLRF | 27 | | 24 | | LB650 Amplifiers | 3635 | | 3126 | |
| LT-HWR | 2 | | 2 | | Magnets | 753 | | 685 | | Feeder 3 (23-3) | 5797 | | 5713 | |
| LT-SSR1 | 3 | | 3 | | Vacuum | 71 | | 63 | | Racks, other, etc. | 1817 | | 1733 | |
| LT-SSR2 | 12 | | 12 | | Controls | 102 | | 100 | | Building Power | 3980 | | 3980 | |
| LT-LB650 | 15 | | 15 | | SS | 11 | | 11 | | Feeder 4 (23-4) | 4022 | | 3990 | |
| LT-HB650 | 7 | | 7 | | Instrumentation | 78 | | 76 | | Cryoplat Building | - | | - | |
| LT-Upgrade* | 2 | | 2 | | WFE | 639 | | 639 | | Cold Box Station | 135 | | 135 | |
| LG | 12541 | | 10922 | | Bldgl | 771 | | 739 | | Warm Compressor Section | 3110 | | 3110 | |
| LG-General | 66 | | 66 | | BeamCommissioning | 0 | | 0 | | UP | - | | - | |
| LG-HWR | 158 | | 146 | | RingsInst | 0 | | 0 | | Compressed Air | 206 | | 175 | |
| LG-SSR1 | 296 | | 272 | | BTLBAL | 5 | | 5 | | LCW | 567 | | 567 | |
| LG-SSR2 | 1679 | | 1526 | | Upgrades | 0 | | 0 | | Controls | 2 | | 2 | |
| LG-LB650 | 3755 | | 3236 | | Conventional Facilities | 3980 | | 3980 | | | | | | |
| LG-HB650 | 4295 | | 3702 | | | | | | | | | | | |
| LG-Upgrade* | 2101 | | 1806 | | | | | | | | | | | |
| LG-BTL | 192 | | 168 | | | | | | | | | | | |
| LG-Exterior Space | 0 | | 0 | | | | | | | | | | | |
| BTL | 7 | | 7 | | | | | | | | | | | |
| BTL-Tunnel | 0 | | 0 | | | | | | | | | | | |
| BAL-Beam Absorber | 7 | | 7 | | | | | | | | | | | |
| BTL-F3 Building** | 344 | | 300 | | | | | | | | | | | |
| F37 | 0 | | 0 | | | | | | | | | | | |
| Cryoplat Building | 3247 | | 3247 | | | | | | | | | | | |
| Cold Box Station | 135 | | 135 | | | | | | | | | | | |
| Warm Compressor Section | 3110 | | 3110 | | | | | | | | | | | |
| Network Room/General DAQ | 2 | | 2 | | | | | | | | | | | |
| UP | 775 | | 743 | | | | | | | | | | | |
| Compressed Air | 206 | | 175 | | | | | | | | | | | |

Choose Amplifier Power Estimate

CW Beam Select Dropdown Here

*Pulsed Beam or CW Beam

F37 building option, yes or no

No Select Dropdown Here

*F37 option is subject to DCR approval

Additional Requirement Management Documents

- Occasionally additional documents are required for “customer” and “supplier” agreements:
 - PIP-II BI Instrument Air & Nitrogen Usage (ED0012529) ➔ Building Infrastructure Requirements
 - PIP-II BI Water Usage Document (ED0012655) ➔ Building Infrastructure Requirements

Fermilab

Fermi National Accelerator Laboratory

PIP-II Building Infrastructure Instrument Air and Nitrogen Usage Document

Document number: ED0012529

Table 3-1. Instrument Air End User Usage

| Component | Quantity | Unit Consumption | Total Consumption |
|---------------------------------------|----------|------------------|-------------------|
| | [#] | [scfm] | [scfm] |
| RFQ Couplers | 4 | 4 | 16 |
| HWR Couplers | 8 | 1.67 | 13.4 |
| SSR1 Couplers | 16 | 3.5 | 56.0 |
| SSR2 Couplers | 35 | 6.17 | 216.0 |
| LB650 Couplers | 36 | 6.17 | 222.1 |
| HB650 Couplers | 36 | 7.03 | 253.2 |
| Cryomodule JT Control Valves | 25 | 0.141 | 3.5 |
| Cryomodule CD Control Valves | 25 | 0.066 | 1.7 |
| Beam and Vacuum Valves | All | 0** | 0** |
| CDS | | | |
| Tunnel Control Valves | All | - | 28.3 |
| Distribution Box Control Valves | All | - | 1.4 |
| Cryoplant | | | |
| Coldbox Control Valves | All | - | 64.9 |
| Warm Compressor System Control Valves | All | - | 14.8 |
| Warm Header Control Valves | 2 | 0.2 | 0.4 |
| Cryoplant ORS and GMP Control Valves | All | - | 11.8 |
| Recovery Compressor Control Valves | All | - | 0.2 |
| Liquid Helium Dewar Control Valve | 1 | 0.1 | 0.1 |

Fermilab

Fermi National Accelerator Laboratory

PIP-II Building Infrastructure Water Usage Document

Document number: ED0012655




Figure 3-1. LCW System (placeholder)

Table 3-1. LCW End User Usage

| Component | Quantity | Unit Consumption | Total Consumption |
|-----------|----------|------------------|-------------------|
| | [#] | [gpm] | [gpm] |
| | | | |
| | | | |



Additional Requirement Management Documents

- Occasionally additional documents are required for “customer” and “supplier” agreements:
 - PIP-II Cable Database → CF & Building Infrastructure Requirements

PIP-II Cable Database

List

New Entry

Dashboard

Expected vs Pulled Entry Count

Administration (Restricted)

Activity

Add a new Cable Type

Approve Cable Requests

Authorization List

Batch Configuration / Expected Numbers

Location to Area Mapping

Machine Section Configuration

Notification for order confirmation config

Pulled Report / Overage Report

Report Builder

System Contact Configuration

Update the Machine mapping list

Update the System mapping list

Approvals Legend

Entry L4M L3M Cable Coordinator L2M

Number of Records found: 3 Start: 1

| Requester | Spool / Batch | Approved ? | Function | Machine / Line | Origin | Destination | Cable (Code) / Length | System | Building / Penetration |
|---|---------------|------------|-----------------|--|----------|-------------|-------------------------------|-------------|------------------------|
| Fernanda Garcia 0002 Jun 27 2019 Entered by: Michele McCusker-Whiting | / HBB | | fish (more) | Other R&D Activities at Other Places (Z) | G1-RR1-1 | M1-101 | Telephone, 50 Pair (AF) / 100 | Control (E) | / |
| Fernanda Garcia 0001 Jun 27 2019 Entered by: Michele McCusker-Whiting | / HBB | | fishpole (more) | Other R&D Activities at Other Places (Z) | M2-808 | M1-101 | (C1) / 100 | Control (E) | / |
| Fernanda Garcia 0001 Apr 16 2018 Entered by: Michele McCusker-Whiting | / BTL | | fish (more) | Other R&D Activities at Other Places (Z) | G1-RR1-1 | M1-101 | Telephone, 50 Pair (AF) / 100 | Control (E) | / |

Actual Displayed rows 3
For Selected Entries:

Narrow down list by using the following search criteria.

Cable Code

Service Building

Machine

System

Requester's Email

Function

Comments

CANUMBER

Entry Date

Origin

Status

Machine Section

Purchase

Batch

Pulled Date

Destination

Pulled?

Priority

Apply Search Criteria

This will search only selected items, if any.



Partner Requirements

- Sub-level FRSs (below L3) are managed at the discretion of the system L3M
- Formal requirement management still required for:
 - Partner to L3 collaboration
 - Partner to Partner collaboration
- Assists in controlling design efforts
- Maintains consistent requirement definition and compliance among different components in system

THANK YOU!