Update from J-PARC Slow Extraction


2020.11.16 US-JAPAN CM (remote by ZOOM)

M. Tomizawa

- Last SX RUN Report
- Next SX RUN Plans


New Target (A-line) and new beam line (B-line)

J-PARC PAC, H. Takahashi



- Part of primary proton beam is split from existing primary beam line (A-line) and is directly used for user experiments.
- Max intensity: 2.6 x 10¹⁰ protons/spill (24W equivalent)
- Beam splitting is made with Lambertson magnet.

Beam intensity in B-line is very sensitive to main beam hallo!



Last SX Operation Summary (RUN84, 85)

2020.4.13-4.14 Abort Dump mode Tuning

- 2020.5.19 Abort Dump mode Tuning
- 2020.5.23 SX Start
- 2020.5.29 50kW SX user operation start


2020.6.25 50kW SX operation finished

- The scheduled 50kW SX operation has completed (efficiency 99.45%, Spill duty 50-55%).
- The SX beam has been successfully delivered to A and B beam lines at the same time.

ESS2 had a dark current 10-15 μA and small vacuum pressure spikes at nominal 104.4kV before RUN84. -> RUN84,85 ESS1 (Ti ESS) 70kV -> 104.4 kV ESS2 (SUS ESS) 104.4kV->75kV


At the beginning of the RUN, frequent sparks in ESS1 were seen, however they gradually decreased in frequency with the beam operation increasing the beam intensity several steps.

Instability during debunch process for SX




2020.7.10 run meeting, H. Takahashi MPS due to a large amount of beam extraction to B-line





The beam intensity in B-Line is very sensitive to the Instability Those events have any problem in A-Line only operation mode Mitigated by RF phase offset injection 60deg -> 65deg




B-Line Spill Spikes


at the beginning of spills did not induce B-line MPS, But have a potential to give a damage to detectors

Actual shot number: 245420, 245650, 245700

Good case



B-Line Spill Spikes




O Mechanism Qx+Qy=43 effect


The beam with a large H-amplitude can have a large V-amplitude.


- \bigcirc Mitigations
 - Qy, (Qx) optimized avoiding the resonance in whole acceleration pattern
 - Further resonance correction by four Skew Q magnets

Vertical main beam position drift at MWPM (MR exit to HD beam line)



The Y drift could affect A-line targeting and B-line beam intensity.






The Y drift correlates with MR tunnel temperature.


The reason is unknown.

The drift could be corrected by exciting 4-vertical steering magnets around MR exit (DY=+1mm DPY=0mrad @RINGEXIT extreme case)



$_{\Box}$ Before Seach dK0[rad] $_{\Box}$				
ZSV31_72	0.000000			
ZSV32_74	0.000000			
ZSV33_77	0.000000			
ZSV34_79	0.000000			
ZSV35_81	000035			
ZSV36_83	000065			
ZSV37_86	0.000077			
ZSV38_88	000115			
ZSV39_90	0.000000			


60 kW SX Demonstration



extraction eff. 99.38% spill duty 61.5% spill length 1.92s (global offset 70deg)


Beam loss before and at the begin of the extraction will be reduced by tuning of horizontal betatron tune and chromaticity.

Time Response Measurement for Future TRF feedback





Beam Spill FFTs

TRF Response Setup System check for sinusoidal attenuation










500Hz peak seen


TRF FB time response > 500Hz


1KHz peak?


Extinction




Empty buckets by a chopper (residual rate 10⁻⁶ level) The residual beam is killed by a MR kicker timing shift (Front bunch Injection)








Demonstration of Injection error correction for normal Injection Scheme using correction kicker <u>A and B</u> (CKM-A, CKM-B)




Further Mitigations of debunch Instability in the next RUN

- 0. RF Phase offset injection tuning
- 1. Vertical TRF during debunch (Preliminary)
- 2. RF Phase offset injection + w/ second harmonic RF @ top -> debunch
- 3. RF Phase offset injection +fundamental RF with phase modulation in ACC. -> debunch
- 4. Slippage change by optics change

(option: Phase offset injection -> dp/p offset and second h. injection)



Two Diffusers



Predictions by FLUKA (R. Muto)

2020.11.12

	diff t [um]	diff0 L [mm]	diff1 t [um]	diff1 L [mm]	beam loss
diff0 only	200	0.5	-	-	0.42
diff1 only	-	-	100	2	0.47
diff0 and 1	200	0.5	100	2	0.35


1.0 is ordinary SX

Two Diffusers Installation (Oct. 2020)


Diffuser0 t 0.2mm L:0.5mm tantalum



The vessel and mover are new







Next Slow Extraction Plans

- ◎ 30GeV SX Schedule
- Dec. 10 → Dec. 22, 2020 30 GeV SX year-end , new year: beam stop
- Jan. 12 → Feb. 3, 2021 30 GeV SX
- ◎ 30GeV Operation Topics
 - Suppressing debunch instability、 Spill spike in B Line 、 V-position drift
 - Beam power 50kW -> 60 kW
 - Diffuser, TRF FB and ripple canceler tests in the last 16 hours
- \bigcirc 8 GeV SX test for COMET
 - Feb. 4 \rightarrow Feb. 10
 - 10⁻¹¹ extinction in all K1 to K4
 - Reducing beam loss at ESS2