

Project X Program and India Collaboration

Steve Holmes
July 29, 2011





-
- Fermilab Long Range Plan
 - Project X Reference Design
 - R&D Plan
 - Timeline & Strategy
 - India Institutes and Fermilab Collaboration


Project X website: <http://projectx.fnal.gov>



Fermilab is the sole remaining U.S. laboratory providing facilities in support of accelerator-based Elementary Particle Physics. Fermilab is fully aligned with the strategy for U.S. EPP developed by HEPAP/P5.


⇒ **The Fermilab strategy is to mount a world-leading program at the intensity frontier, while using this program as a bridge to an energy frontier facility beyond LHC in the longer term.**


Project X is the key element of this strategy





- A neutrino beam for long baseline neutrino oscillation experiments
 - 2 MW proton source at 60-120 GeV
- High intensity, low energy protons for kaon and muon based precision experiments
 - Operations simultaneous with the neutrino program
- A path toward a muon source for possible future Neutrino Factory and/or a Muon Collider
 - Requires ~4 MW at ~5-15 GeV
- Possible missions beyond P5
 - Standard Model Tests with nuclei and energy applications





Reference Design Capabilities



- 3 GeV CW superconducting H- linac with 1 mA average beam current.
 - Flexible provision for variable beam structures to multiple users
 - CW at time scales $>1 \mu\text{sec}$, 10% DF at $<1 \mu\text{sec}$
 - Supports rare processes programs at 3 GeV
 - Provision for 1 GeV extraction for nuclear energy program
 - 3-8 GeV pulsed linac capable of delivering 300 kW at 8 GeV
 - Supports the neutrino program
 - Establishes a path toward a muon based facility
 - Upgrades to the Recycler and Main Injector to provide ≥ 2 MW to the neutrino production target at 60-120 GeV.
- ⇒ Utilization of a CW linac creates a facility that is unique in the world, with performance that cannot be matched in a synchrotron-based facility.



Linac


Particle Type	H ⁻	
Beam Kinetic Energy	3.0	GeV
Average Beam Current	1	mA
Linac pulse rate	CW	
Beam Power	3000	kW
Beam Power to 3 GeV program	2870	kW


Pulsed Linac

Particle Type	H ⁻	
Beam Kinetic Energy	8.0	GeV
Pulse rate	10	Hz
Pulse Width	4.3	msec
Cycles to MI	6	
Particles per cycle to MI	2.6×10^{13}	
Beam Power to 8 GeV	340	kW

Main Injector/Recycler

Beam Kinetic Energy (maximum)	120	GeV
Cycle time	1.4	sec
Particles per cycle	1.6×10^{14}	
Beam Power at 120 GeV	2200	kW








- The primary elements of the R&D program include:
 - Development of a wide-band chopper
 - Capable of removing bunches in arbitrary patterns at a 162.5 MHz bunch rate
 - Development of an H- injection system
 - Require between 4.4 – 26 msec injection period, depending on pulsed linac operating scenario
 - Superconducting rf development
 - Includes six different cavity types at three different frequencies
 - Emphasis is on Q_0 , rather than high gradient
 - Typically $1.5E10$, 15 MV/m (CW)
 - $1.0E10$, 25 MV/m (pulsed)
 - Includes appropriate rf sources
 - Includes development of partners
- Goal is to complete R&D phase by 2015

SRF Linac Technology Map




Section	Freq	Energy (MeV)	Cav/mag/CM	Type
SSR0 ($\beta_G=0.11$)	325	2.5-10	18 /18/1	SSR, solenoid
SSR1 ($\beta_G=0.22$)	325	10-42	20/20/ 2	SSR, solenoid
SSR2 ($\beta_G=0.4$)	325	42-160	40/20/4	SSR, solenoid
LB 650 ($\beta_G=0.61$)	650	160-460	36 /24/6	5-cell elliptical, doublet
HB 650 ($\beta_G=0.9$)	650	460-3000	160/40/20	5-cell elliptical, doublet
ILC 1.3 ($\beta_G=1.0$)	1300	3000-8000	224 /28 /28	9-cell elliptical, quad


Fermilab SRF infrastructure



VTS



VTS



Cavity tuning machine



HTS



String Assembly



MP9 Clean Room



Final Assembly



1st U.S. built ILC/PX Cryomodule



1st Dressed Cavity



-
- The DOE has a formalized process for moving projects from pre-conceptual designs through construction
 - Current activities
 - Design development
 - R&D
 - A set of documentation exists that form the basis for the first step
 - CD-0 = “Mission Need”
 - Reference Design Report
 - R&D Plan
 - Cost Estimate
 - The timeline for Project X has not been established within the DOE
 - Internal planning has been based on a start of construction in late 2015/early 2016
 - 5 year construction period (spans two Indian 5-year plans)



- A multi-institutional collaboration has been established to execute the Project X RD&D Program.
 - Organized as a “national project with international participation”
 - Fermilab as lead laboratory
 - International participation established via bi-lateral MOUs.
 - Collaboration MOUs for the RD&D phase outlines basic goals, and the means of organizing and executing the work. Signatories:

ANL	ORNL/SNS	BARC/Mumbai
BNL	MSU	IUAC/Delhi
Cornell	TJNAF	RRCAT/Indore
Fermilab	SLAC	VECC/Kolkata
LBNL	ILC/ART	
- It would be natural for collaborators to continue their areas of responsibility into the construction phase.

Review of Current Institutional Responsibilities



	Front End	Cav & CMs	RF	Cryo	Instru	Cntrls	MI/Recycler	Beam Trnspt	Accel Phys	System Integ	Test Facil
ANL		X	X						X		
BNL		X						X			
Cornell		X					X				
Fermilab	X	X	X	X	X	X	X	X	X	X	X
LBNL	X				X				X		
SNS					X						
MSU		X		X							
TJNAF		X									
SLAC	X		X				X		X		X
ILC/ART		X									X
BARC	X	X	X	X	X	X			X		X
IUAC		X		X							
RRCAT		X	X	X							X
VECC		X		X							



- Phase 1 and 2 (R&D)
 - Collaboration initiated in 2007
 - ILC/SRF
 - Reorientation to High Intensity Proton Accelerator in 2009
 - SRF at low betas
 - Expanded into other technical areas in 2010
 - All major technical components in the CW linac
 - Formalized management structure for IIFC implemented in 2010
- Phase 3 (Construction)
 - In process of outlining a schedule of Indian deliverables
 - Alignment of Indian technical aspirations with Project X requirements
 - Indian participation in installation and commissioning of Project X
 - Two Indian projects under discussion
 - SNS: 1-2 GeV linac + ring
 - ADS: ~1 GeV CW linac



-
- Accelerating cavities
 - 325 MHz: SSR1, SSR2 ?
 - 650 MHz; $\beta=0.6, 0.9$
 - RF Power
 - 325 MHz
 - 650 MHz
 - Cryomodules
 - 325 MHz: focusing solenoids
 - 650 MHz: focusing quadrupole + other components
 - Cryogenic Plant
 - Instrumentation/controls
 - 325 MHz: BPMs, LLRF components
 - 625 MHz: BPMs, LLRF components
 - Personnel
 - ~20 Scientist/engineer
 - Management, design, fabrication, installation, commissioning
-





Figure 8: Quality factor Q_0 as a function of accelerating gradient at 2 K, on the second 1.3 GHz single cell cavity.



TE1CAT003 with RRCAT-IUAC & FNAL team members



Die- Punch Set at RRCAT





Aluminum blank, 3mm thickness




India Delegation - S. Holmes
Die-Punch Set mounted on Press at RRCAT




Beginning of forming trials with aluminum




HTS-2 COOLING CIRCUIT OPTION



Preliminary cooling circuit design



IIFC Joint Management (iifc.fnal.gov)





-
- Project X is central to Fermilab's strategy for development of the accelerator complex over the coming decade
 - World leading programs in neutrinos and rare processes
 - Potential applications beyond elementary particle physics
 - A mature design concept has been established, offering capabilities that are unique among any high intensity facility in existence or under design
 - 2 MW to the neutrino program over 60-120 GeV
 - 3 MW to the rare processes program
 - Flexible provision for variable beam formats to multiple users
 - R&D underway with very significant investment in srf infrastructure and development
 - Strategy for moving the project forward is being developed with DOE
 - Likely staging with CW linac as initial stage
 - Indian collaboration has been a primary driver in getting Project X to where it is today
 - Project X could be constructed over the period ~2016 – 2020
-