

# Indian Accelerator Programme

**P. Singh**

**Bhabha Atomic Research Centre  
Mumbai, India**

## Plan of the Talk:

- 1. Accelerators in India (BARC, RRCAT, VECC, IUAC)**
- 2. New proposals**
- 3. Activities under IIFC**



# Accelerators in India



## Heavy Ion

- 6 MV Folded Tandem Ion Accelerator (BARC, Mumbai)
- 14 MV Pelletron ( Mumbai)
- Superconducting Linac booster at Mumbai (Pb plated cavities)-Mumbai
- 16 MV Pelletron ( IUAC, New Delhi)
- Superconducting Linac Booster at IUAC (Niobium cavities)-IUAC
- K=130 Room temp cyclotron ( VECC, Kolkata)
- K= 500 Superconducting Cyclotron at Kolkata ( VECC, Kolkata-under commissioning)
- 3 MV Tandatron at Hyderabad
- 1.7 MV high current Tandem Accelerator at IUAC
- 8 MeV Cyclotron at Chandigarh

## Electron

- 450 MeV INDUS-I ( SRS at RRCAT, Indore)
- 2.5 GeV INDUS-II ( SRS at RRCAT, Indore)
- 10 MeV, 10 kW Linac at Mumbai for industrial application (BARC, Mumbai)
- 20 MeV Microtron ( Mangalore)
- 10 MeV Electron Linac at RRCAT
- 7 MeV Electron accelerator ( BARC, Mumbai)
- 2 MeV Electron Linac (ILU-6) at Mumbai
- 750 keV Electron DC accelerator at RRCAT

## Proton (projects) and R&D

- ✓ 1 GeV, 30 mA Linac (Injector: 20 MeV LEHIPA)- BARC
- ✓ 1 GeV SNS [100 MeV H<sup>-</sup> Linac+ RCS]- proposal by RRCAT, Indore

---

# Present Accelerators

# 14 MV BARC-TIFR Pelletron at Mumbai



a)




b)

a) 14 UD Pelletron Facility at Mumbai    b) High voltage column section



28 Pb plated QWR in 7 Cryomodules , Energy Gain 14 MeV /q



QWRs: Required 27, built 30


Automation of the linac operation is undertaken with 2 modules. Beam delivered with two modules.

Piezotuner for cryostats 2 & 3 are being planned


3 cryostat also tested upto LN2 temperature.



Accelerating Field reached in QWR, 5-6 MV/m



## K=500 Superconducting Cyclotron




Magnet assembly  
at the fabrication  
site



Vertical cross-sectional view




Pole tip assembly



Trim coils wound on  
pole tip before potting



# SCHEMATIC OF INDUS COMPLEX at RRCAT, Indore



**Indus-2, 2.5 GeV SR**  
(Trials to store the beam began)

December 2005

**Indus-1**  
(450 MeV, 100 mA)

**Both Indus-1 & Indus-2 are being run for users.**






# 6 MV Folded Tandem Ion Accelerator



6 MV FOLDED TANDEM ION ACCELERATOR AT TROMBAY, MUMBAI







---

# Major High Intensity Proton Accelerator Projects

# Schematic of SNS at RRCAT




|                                     |                          |
|-------------------------------------|--------------------------|
| <b>Linac output energy:</b>         | <b>1 GeV</b>             |
| <b>Type of particle:</b>            | <b>H<sup>-</sup> ion</b> |
| <b>Average linac pulse current:</b> | <b>20 mA</b>             |
| <b>Pulse repetition rate:</b>       | <b>50 Hz</b>             |
| <b>Pulse duration:</b>              | <b>1 ms</b>              |
| <b>Duty factor:</b>                 | <b>5%</b>                |



# Phase I


Building of a Low Energy High Intensity Accelerator  
LEHIPA (20 MeV, 30 mA)



ECR Ion source RFQ 4 Vane type 20 MeV, 30 mA  
50 keV, 35mA. 3MeV, 30 mA Alvarez type DTL

- LEBT** : Low Energy Beam Transport System
- RFQ** : Radio Frequency Quadrupole
- MEBT** : Medium Energy Beam Transport System
- DTL** : Drift Tube Linac

# RFQ, & DTL and PMQ Prototypes




**Anatomy of drift tube  
( exploded view)**



**Prototype Drift Tube with permanent magnet  
quadrupole focussing and coolant channels**





# DAE & US Accelerator Laboratories MOUs



Memorandum of Understanding  
between  
US Universities & Accelerator Laboratories  
and  
Indian Universities & Accelerator Laboratories  
concerning  
Collaboration on R&D for Various Accelerator Physics and High  
Energy Physics Projects  
January 9, 2006




## 1. Introduction

### 1.1 General Description

This Memorandum of Understanding (MOU) establishes a collaboration framework between various US and Indian Accelerator Laboratories and

### 4.2 Approvals

The following concur in the terms of this Memorandum of Understanding:

|  |   |
|--|---|
| <br>Piermaria Oddone, Director, FNAL<br>Date: 1/9/06    | <br>Vinod C. Sahni, Director, IUCAT<br>Date: March 8, 2006       |
| <br>Jonathan Durkin, Director, SLAC<br>Date: 1/23/06    | <br>Bikash Sinha, Director, VECC<br>Date: March 9, 2006          |
| <br>Christoph Lechner, Director, TJNAF<br>Date: 1/18/06 | <br>Amit Roy, Director, IUAC<br>Date: March 9, 2006              |
| <br>Maury Tigner, Director, Newnan Lab<br>Date:        | <br>S. Bhattacharya, Director, TIFR<br>Date: April 17, 2006     |
| <br>Date:  | <br>S. Banerjee, Director, BARC<br>Date: March 14, 2006        |
| <br>Date:  | <br>Deepak Pental, Vice Chancellor, DU<br>Date: April 10, 2006 |

## ADDENDUM

to the

Memorandum of Understanding  
between

US Universities & Accelerator Laboratories  
and

Indian Universities & Accelerator Laboratories  
concerning

Collaboration on R&D for Accelerator Physics and High Energy Physics  
Projects

Addendum I: "Fermilab, RRCAT, BARC, IUAC and VECC Collaboration on ILC Main Linac SRF Accelerator Technology R&D"

October 2, 2007

## 1. Introduction

The work detailed in this document falls within the scope of the Memorandum of Understanding (MOU) between US and Indian Institutions dated January 9, 2006. It

### 7 Management and Approval:

The work under this MOU will be jointly managed by Dr. Shekhar Mishra, Fermilab and Dr. Vinod C. Sahni, India. They represent the institutions in the respective countries and serve as a single point of contact.

The following concur on the terms of this Memorandum of Understanding:

  
Dr Vinod C. Sahni,  
Director, RRCAT  
Date: Oct 2, 2007

  
Dr. Piermaria Oddone  
Director, FNAL  
Date: 10/2/07


  
Dr. Shekhar Mishra  
Deputy ILC Program Director, FNAL  
Date: 10/2/07

# Addendum III


## Addendum III: Fermilab and Indian Accelerator Laboratories Collaboration on High Intensity Proton Accelerator & SRF Infrastructure Development



# Schematic of Project-X



Ion Source, RFQ



---

2 Committees were formed for Indian Institutes Fermilab Collaboration (IIFC).

1. **Apex IIFC Committee (Policy matters)**
2. **IC-IIFC Committee (Technical matters)**

**6 documents were signed on August 22, 2011 at OYC, Mumbai: Fermilab and Indian Accelerator Laboratories collaboration for High Intensity Proton Accelerator on:**

1. RF Power Development (325 MHz) - Addendum V
2. RF Power Development (650 MHz) - Addendum VI
3. Instrumentation and Control - Addendum VII
4. Accelerator Physics Issues - Addendum VIII
5. Cryo-module Test Facility (CMTF)
6. Supplement 1 to Addendum III (to MoU) between Fermilab and Indian DAE Laboratories (BARC, RRCAT, VECC) & IUAC

# Addendum Signing at Mumbai on Aug 22, 2011



## **BARC:**

1. Accelerator Physics,
2. 1,3 and 7 kW Solid State Power Amplifier at 325 MHz
3. LLRF system, RF protection system, Cryogenic Temperature Monitoring System, Beam Position Monitor (BPM) System
4. Design and development of CMTF

## **VECC:**

1. R&D of 650 MHz ,  $\beta=0.61$  elliptical cavity
2. R&D for Helium vessel & Blade Tuner for 650 MHz,  $\beta=0.61$ , 5 cell cavity
3. SS Jacketing for single spoke  $\beta=0.20$  resonator.
4. Design of Test Cryostat for 650 MHz,  $\beta=0.61$ , 5 cell elliptical cavity
5. High Power RF source development (60 kW IOT based)

## **RRCAT**

1. Vertical and Horizontal Test Stands
2. R&D for 650 MHz ,  $\beta=0.90$  elliptical cavity and cryomodule
3. 30 kW Solid State Amplifiers at 650 MHz
4. Development of RF components for 650 MHz
5. Infrastructure developments for cavity fabrication, processing and testing

## **IUAC**

1. Design and fabrication of SSR1, 325 MHz,  $\beta=0.22$
2. EBW of superconducting cavities


## Phase 1:

| Institutions | Components to Fermilab                                     | Quantity | Date      | Indian POC     |
|--------------|--|----------|-----------|----------------|
| IUAC         | SSR1   | 2        | May 2011  | P. N. Prakash  |
|              | SSR1   | 4+1      | Oct 2014  | P. N. Prakash  |
| IUAC+VECC    | Spoke Resonator<br>Cryomodule Design and<br>Prototype      |          | Oct 2014  | A. Duttagupta  |
| RRCAT        | 1.3 MHz 1-cell, beta=0.9                                   | 2        | May 2011  | A. Puntambekar |
|              | 1.3 MHz 5-cell, beta=0.9                                   | 1        | July 2011 | A. Puntambekar |
|              | 650 MHz 1-cell, beta=0.9                                   | 1+1      | Oct 2011  | A. Puntambekar |
|              | 650 MHz 5-cell, beta=0.9                                   | 1        | Oct 2012  | A. Puntambekar |
|              | 650 MHz 5-cell, beta=0.9                                   | 4+1      | May 2014  | A. Puntambekar |
| RRCAT        | 650 MHz 5-cell, He Vessel                                  | 4+1      | May 2014  | J. Dewedi      |
| RRCAT        | 650 MHz 5-cell, Blade Tuner                                | 4+1      | May 2014  | J. Dewedi      |
| VECC         | 650 MHz 1-cell, beta=0.6                                   | 1+1      | Oct 2011  | S. Som         |
|              | 650 MHz 5-cell, beta= 0.6                                  | 1        | Oct 2012  | S. Som         |
|              | 650 MHz 5-cell, beta= 0.6                                  | 2+1      | May 2014  | S. Som         |
| VECC         | 650 MHz 5-cell, He Vessel                                  | 2+1      | May 2014  | S. Som         |
| VECC         | 650 MHz 5-cell, Blade Tuner                                | 2+1      | May 2014  | S. Som         |
| RRCAT        | 650 MHz Cryomodule<br>Design, beta = 0.9                   | 1        | Dec 2011  | P. Khare       |
| RRCAT        | 2 cavities HTS   | 1        | Oct 2012  | P. Kush        |
| Fermilab     | 2 cavities VTS (to RRCAT)                                  | 1        | May 2011  | S. Joshi       |
| BARC         | Cryomodule Test Stand<br>1300 MHz Pulsed/650 MHz<br>Design | 1        | June 2012 | Manjit Singh   |
| BARC         | Cryomodule Test Stand<br>1300 MHz Pulsed/650 MHz<br>CW     | 1        | Oct 2014  | Manjit Singh   |

## Phase II:

| Institutions             | Components to Fermilab                  | Quantity | Date     | Indian POC      |
|--------------------------|---|----------|----------|-----------------|
| BARC                     | 325 MHz RF Power (1 KW)                 | 1        | Dec 2011 | M Pande         |
|                          | 325 MHz RF Power (3 KW)                 | 1        | Dec 2012 | M. Pande        |
|                          | 325 MHz RF Power (7 KW)                 | 1        | Dec 2014 | M. Pande        |
| RRCAT                    | 650 MHz RF Power (250 W)                | 1        | Dec 2011 | P. R. Hannurkar |
|                          | 650 MHz RF Power (1 KW)                 | 1        | Dec 2012 | P. R. Hannurkar |
|                          | 650 MHz RF Power (30 KW)                | 1        | Dec 2014 | P. R. Hannurkar |
| BARC                     | Low-Level RF System                     | 1        | Dec 2014 | C. K. Pithawa   |
|                          | RF Protection Interlock System          | 1        | Dec 2014 | C. K. Pithawa   |
|                          | Cryogenic Temperature Monitoring System | 1        | Dec 2014 | C. K. Pithawa   |
|                          | Beam Position Monitor                   | 4        | Dec 2013 | C. K. Pithawa   |
| BARC+RRCAT + VECC + IUAC | Cryomodule Test Facility at 650 MHz     | 1        | Dec 2014 | M. Singh        |


## Scheme for 200 MeV High Intensity Proton Accelerator (a front end of the 1 GeV Linac)



**Current : 30 mA**


**We may go in steps but the design needs to be done for 30 mA**

In collaboration with A. Saini and Shekhar Mishra under IIFC



Beam envelopes

## Evolution of Beam emittances



---

# Accelerator Physics of High Intensity beams (working together under IIFC)

- **Beam Dynamics**
- **Cavity design**
- **Halo formation**
- **Space Charge Effects**
- **HOM**
- **Codes writing**



# Solid-State Power Amplifier (SSPA) Development



Deliverables under the collaboration for TPD, BARC

Design and development of :



- 1 kW, 3 kW, 7 kW at 325 MHz SSPA -- 1 No each

- ❖ One prototype amplifier assembled
- ❖ Bolted to water cooled heat sink
- ❖ Test set-up arranged with
  - SMPS power supply, Power meters along with sensors
  - VNA & SPA, Signal generator, Drive amplifier
  - Spectrum Analyzer, Directional couplers, Test Load

# Test results

The first prototype 325 MHz Amplifier has been tested.

1. Short time test (1/2 hr) : 1 kW
2. Long term test (8 hrs) : 800 W
3. Power gain (1 dB) : 19.5 dB
4. Efficiency : 68 %



# Comparison of Specifications

| Specification          | Fermi Lab | SSPA Developed @ RFSS, TPD, BARC | Remarks                     |
|------------------------|-----------|----------------------------------|-----------------------------|
| Center frequency (MHz) | 325       | 325                              |                             |
| Bandwidth (kHz)        | 100       | >100                             |                             |
| Power output (kW)      | 1         | 0.8                              | 1 kW test is under progress |
| Power Gain (dB)        | 67        | >70                              | Inclusive of drive PA       |
| Efficiency (%)         | 60        | 68                               |                             |

**CMTF consists of following five main sub systems:**

**(a) Feed box**

**(b) Feed Cap**


**(c) End cap**

**(d) Transfer lines**


**(e) Mechanical structure with Supporting & alignment facility for Cryo-Module**

**(A K Sinha and V.K. Mishra, CDM, BARC )**


# Feed box



Normal view




Transparent view





Top view

# END CAP SUBASSEMBLY



END CAP  
SUBASSEMBLY








# 650 MHz, $\beta=0.61$ , elliptical cavity simulation at VECC



**Accelerating mode**

**Field flatness:  
Very good!**




**Data:  
Generated by  
VECC**

**Results:  
Very good!**


**kc = 1.24%  
( Riris=48 mm.)**

|                                    | $\frac{A}{B}$<br>mm./<br>mm. | $\frac{a}{b}$<br>mm./<br>mm. | Equator<br>radius<br>D/2<br>mm. | Iris<br>radius<br>R <sub>iris</sub><br>mm. | Half-cell<br>L/2<br>(inner)<br>mm. | $\frac{R}{Q}$<br>$\Omega$ | G=Q.R <sub>s</sub><br>$\Omega$ | E <sub>acc</sub><br>MV/m | $\frac{E_p}{E_{acc}}$ | $\frac{B_p}{E_{acc}}$ | f <sub><math>\pi</math>-mode</sub><br>MHz | Remarks   |
|------------------------------------|------------------------------|------------------------------|---------------------------------|--|------------------------------------|---------------------------|--------------------------------|--------------------------|-----------------------|-----------------------|---|---|
| <b>VECC<br/>Design1<br/>Result</b> | $\frac{54}{58}$              | $\frac{11.99}{27}$           | 198.175                         | 48   | 70.335                             | 290                       | 197                            | 16.95                    | 3.34                  | 4.90                  | 650.000                                   | 2D SUPERFISH<br>3D CST MWS<br>$\left(\frac{\alpha}{b}\right)_{end} = \frac{20.66}{46.54}$<br>$\left(\frac{A}{B}\right)_{end} = \frac{45.94}{49.35}$<br>$\alpha=3.6$ deg<br>Energy=118.8 J<br>Mesh size=0.05                     |
| <b>VECC<br/>Design2<br/>Result</b> | $\frac{54}{58}$              | $\frac{13.68}{30.82}$        | 197.4                           | 48   | 70.335                             | 296                       | 200                            | 17.00                    | 3.00                  | 4.84                  | 649.99869                                 | 2D SUPERFISH<br>3D CST MWS<br>$\left(\frac{\alpha}{b}\right)_{end} = \frac{10.67}{24.02}$<br>$\left(\frac{A}{B}\right)_{end} = \frac{54}{58}$<br>$\alpha = 2.4$ deg (mid)<br>=4.5 deg (end)<br>Energy=118.8 J<br>Mesh size=0.05 |



Electric field lines inside the cavity


**Frequency : 650 MHz**  
 $\beta : 0.61$



Magnetic field lines inside the cavity

## Latest Design Results

**Half-cell Length =  $L/2 = 70.335$  mm.**  
**Iris radius =  $R_{iris} = 48$  mm.**  
**Equator radius =  $D/2 = 197.4$  mm.**  
**Equator ellipse ratio =  $A/B = 54$  mm./  $58$  mm.**  
**Iris ellipse ratio =  $a/b = 13.68$  mm./  $30.82$  mm.**  
**Wall angle =  $\alpha = 2.4$  deg. (mid-cell) =  $4.5$  deg. (end-cell)**  
 **$E_p/E_{acc} = 3.00$**   
 **$B_p/E_{acc} = 4.84$**   
 **$E_{acc} = 17$  MV/m**  
**Stored Energy (U) = 118 Joule**



Plot of E-fields along the axis



INSPECTION OF SCALED DOWN CAVITY FORMER  
UNDER CMM at VECC Workshop

# NIOBIUM SHEET


- **Dimension: 600 mm. x 600 mm. x 4 mm.**
- **Tolerances:  $\pm 1.5$  mm. x  $\pm 1.5$  mm. x  $\pm 0.125$  mm.**
- **RRR value: 300 or better**
- **Surface texture: better than  $3.175 \mu\text{m}$  finish**
- **Surface roughness: better than  $1.6 \mu\text{m}$**
- **Deep drawing quality, grain size ASTM#5 or finer, local grain sizes ASTM#4 allowable, min. 90% recrystallized**
- **Grain size: Typically  $50 \mu\text{m}$**
- **Yield strength  $> 50 \text{ N/mm}^2$**
- **Tensile strength  $> 100 \text{ N/mm}^2$**
- **Elongation  $> 30\%$ ,**
- **Vicker Hardness  $< 50 \text{ N/mm}^2$**
- **ATI Wah Chang, USA.**
- **15 Nos. Nb sheet Received.**
- **Procurement of further 15 Nos. in progress.**

**Specs matches with Fermilab Specs.**

## Impurities:

|                                      |                          |
|--------------------------------------|--------------------------|
| $\text{H}_2 \leq 2 \text{ Wt. ppm}$  | $\text{W} \leq 0.007\%$  |
| $\text{C} \leq 10 \text{ Wt. ppm}$   | $\text{Ti} \leq 0.005\%$ |
| $\text{N}_2 \leq 10 \text{ Wt. ppm}$ | $\text{Fe} \leq 0.003\%$ |
| $\text{O}_2 \leq 10 \text{ Wt. ppm}$ | $\text{Si} \leq 0.003\%$ |
| $\text{Ta} \leq 500 \text{ Wt. ppm}$ | $\text{Mo} \leq 0.005\%$ |
|                                      | $\text{Ni} \leq 0.003\%$ |

- **Design has been done for Test Cryostat that can accommodate the 5-cell elliptical shape 650 MHz,  $\beta=0.61$  cavity**
- **Overall dimension of the Test Cryostat:  
2360 mm. Height x 1762 mm. Diameter**
- **LHe vessel dimension of the Test Cryostat:  
1050 mm. Length x 512 mm. Diameter**
- **Cryostat consists of:**
  - **LHe vessel, LN2 shield**
  - **Internal & external magnetic shielding**
  - **Pump out port**
  - **LN2/LHe in, LN2/LHe gas out, Safety port,**
  - **LN2/LHe instrumentations**
  - **RF probe in/out --- adjustable from outside**
  - **RF power coupler arrangement etc.**



Fermilab


## CAVITY PLACED VERTICALLY IN CRYOSTAT



- SCRF cavity can be placed in the same CRYOSTAT in two possible ways

- Vertically
- Horizontally

- Future modification: CRYOSTAT can be operated at 2K (for cavity placed horizontally) adding components (Heat Exchanger, JT valve etc.) – provision for space





# Accelerator R & D Activities at RRCAT


---



- **Synchrotron radiation sources :**
  - **450 MeV Storage Ring Indus 1**
  - **2.5 GeV Booster cum storage ring Indus 2**
  - **Beamline and their utilization**
- **10 MeV Linac for irradiation of agricultural products**
- **700 keV DC accelerator for industrial applications**
- **High energy proton accelerator technology development**
- **SCRF Science and Technology program**
- **THz Free Electron Laser activity**
- **Laser plasma wake field accelerator R & D**
- **R & D in super conducting materials and cryogenics**
- **International collaboration**


# Schematic View of Indus Complex

RRCAT is the home for two  
Synchrotron Radiation Sources:  
Indus-1 & Indus-2



Microtron  
( 20 MeV )

Booster Synchrotron  
( 450/550 MeV )



TL-3


Indus-1  
( 450 MeV )

Indus-1 & Indus-2 are  
operated in round the  
clock mode.

Indus-2 currently operates  
at 2 GeV, 100 mA current  
with a beam life time of ~ 20  
Hrs.


# Indus-1 : Synchrotron Radiation Source

- Indus-1 regularly operated at 450 MeV, 100 mA
- Five beamlines are operational and made available to users



- Soft X-ray reflectivity
- Angle Integrated Photoelectron Spectroscopy
- Angle Resolved Photoelectron Spectroscopy
- Photophysics
- High resolution VUV

# Indus-2 Synchrotron Radiation Source



Beamlines already commissioned =5


Beamlines under commissioning =3

No. of straight sections for insertion devices =5

It is planned to setup 8 additional bending magnet beamlines and 5 on insertion devices

- A long term program on setting up of a 1GeV Proton Accelerator is envisaged for the development of a Pulsed Spallation Neutron Source

## Schematic of 1 GeV pulsed proton linac for SNS



- Super conducting RF cavity technology development.
- Development of low energy front end part (H<sup>-</sup> ion source, 3 MeV RFQ).

## Plasma chamber for H-ion source




NdFeB magnets for generating multi-cusp field geometry

## Beam extraction



This will house beam extraction electrodes

## First segment of prototype 352 MHz RFQ





Fabricated in Al to validate the design



# Development of Single Cell 1.3 GHz SCRF Cavities under IIFC



- During 2009–10, two single cell Nb cavities were jointly developed under IIFC which exhibited acceleration gradient up to 23 MV/m.
- Subsequently two more cavities have been fabricated and processed under IIFC to improve the cavity performance.
- These cavities have exhibited accelerating gradients of ~ 35-37.5 MV / m with a high Q at 2 K.



- 120 T cavity forming facility
- Electro-polishing setup for 1.3 GHz
- Centrifugal barrel polishing machine for 1.3 GHz single cell cavities
- High pressure rinsing



Cavity forming facility installed



Electro-polishing setup developed



Centrifugal barrel polishing machine developed



High pressure rinsing Set up developed

- Electron beam welding machine (15 kW) and a vacuum annealing furnace are under procurement. These are expected to be installed by December 2012

# Infrastructure for SCRF Cavity Characterization

- Secondary Ion Mass Spectrometer (SIMS)
- 3D Laser Scanning Confocal Microscope
- Large 3D Coordinate Measuring Machine
- Optical Bench for internal surface inspection
- RF Measurement Setup



3D CMM installed



SIMS setup installed



Laser scanning confocal  
microscope installed



Optical bench developed

## Cavity Fabrication, Assembly & Processing Building (1400 Sq. m)

- The building will house clean rooms, Electron beam welding machine. High vacuum annealing furnace, Electro-polishing setup, Centrifugal barrel polishing machine, RF measurement set up etc.
- Building is ready.



## Lab Building ( ~ 800 Sq. m)

- It will house CMM, SIMS, material testing facility, thin film deposition facility etc
- Building is ready, facilities under commissioning.




# Development of Vertical Test Stand

- RRCAT & Fermi Lab jointly carried out design of various components of 2K VTS Cryostat:

- Liquid Helium Vessel
- 80K shield
- Vacuum Vessel
- Top Insert Plate
- Magnetic shielding (2K + room temperature)
- Piping layout for liquid helium
- 3-D model of the complete VTS-2 assembly


- Three VTS cryostats are under fabrication at US vendor under joint supervision of engineers from Fermi Lab and RRCAT.



3D model of VTS

- Expected delivery schedule : December 2011.
- Building to house VTS at RRCAT is under construction and expected to be ready by December 2011
- Cryogenics system under process
- Components of RF and DAQ system for RRCAT VTS is under process and expected to be ready by Dec 2011.


- Design effort progressing smoothly
- Major specifications of the cryomodule have been ascertained
- Engineering design has made considerable progress for vacuum vessel, thermal shield ,cavity support system etc.



Cut Section of Cryomodule & subsystems

## Horizontal Test Stand (HTS-2)

Design and development work of a horizontal test stand has been taken up in collaboration with Fermilab




### Functional requirements

- Capability to test two dressed cavities at a time but separately.
- Testing of both 650 MHz and 1.3 GHz cavities.
- Throughput of 4 cavities in 6 weeks.


An important aspect of this design effort is the improvements made to accommodate operational experience of HTS at Fermilab

- We have taken up development of 30 kW CW 650 MHz solid state amplifiers for energizing SCRF cavities

## 8 kW Amplifier Scheme



## 30 kW Amplifier Scheme



- 32 Nos. of 270 W RF modules are used with suitable combiners and dividers to make a 8 kW RF amplifier module. Four such modules will be combined to obtain 30 kW RF power output.



Two units of Solid State RF Amplifiers each of 15 kW output power at 505.8 MHz have been developed and deployed in Indus-2 operating in round the clock mode.


## Low Beta Resonator Development for IUAC Linac



**Beta = 0.05, 97 MHz**

# Collaborations on Resonator Developments

## Spoke Cavity for Fermilab Project X



$\beta = 0.22$ , 325 MHz



1.3 GHz TESLA type Cavity under IIFC. 4 Single Cells fabricated.  
Two have reached > 35 MV/m

# Summary and conclusions

---

- 1. Accelerator activities at different Indian Centres were discussed**
- 2. The collaboration with Fermilab under IIFC is making good progress and is expected to grow further.**
- 3. Scientists and Engineers from both sides are in touch and discuss regularly through WebEX meetings.**
- 4. We have gone through all the initial drawings provided by Fermilab and now engaged in detailed fabrication discussions with Fermilab.**
- 5. Two cavities fabricated in India and processed and prepared in US Labs reached 35-40 MV/m. Congratulations to all involved.**

धन्यवाद

Thank You!