





CRP consortium meeting: 17/03/2021

- Status of activities for preparing CRP of cold box tests
- Far Detector WBS
- Status of anode design and options for connecting the PCBs

Vertical Drift CRP for test in cold box



Keep original suspension system with 40mm bellows





The opening of the cold box is being increased to allow vertical insertion of the CRP with no need to have an inclination of the structures

Some optimisation going on to complete with the updated cold box model



Vertical Drift CRP for test in cold box



Goal :

centre the 3373 x 2998 mm² CRP
wrt CB opening


will lead to:

- 26,5mm clearance / length (3373mm)
- 194mm clearance / width (2998mm)

Vertical Drift CRP for test in cold box

3373 x 2998 mm² CRP centered wrt CB opening


During insertion



- 26,5mm clearances / length (3373mm)

Design for the support structure

Final hole pattern « support » layer = 58 holes



3375 mm





3000 mm

Hybrid structure:

the same structure useable for both electronics (individually or mixed)

=> Openings along the sides of the frame to allow CE module connection and the connectors for top electronics





next steps :

- Deformation modelisation with all component weight and positions
- Optimise additional opening depending on the results
- Confirm the CTE of the foreseen material compatible with anode material

CRP support frame design steps:

- Anode support hole pattern defined and frozen 3/03/21
- Support frame + anode material CTE measurements at Cryolab ongoing: expect results by 15/03/21
- Integration of 3D model of anode + adapter Boards + CE box (on going)
- Mechanical simulation to be done with the proper weight and component distribution

The 3D models for the CE FEMB and Boxes: use the ProtoDUNE-SP version for the time being.

CRU assembly (before the CRP assembly)

Discussion ongoing to understand how to manipulate the large PCB anodes and the needs for tooling.
=> depending on this discussion toolings may have to be designed


Points under study:

- Connector type, positioning and soldering (next item on the agenda)
- Anode manipulation during the CRU assembly


Adapter boards for the top electronics

After discussion last week it appears that some modifications are needed to treat identically induction 2 as for the 2 other strip directions.

Original schema



Modification proposal



In discussion with the top electronics

Make connections for induction 2 similar as the other strips including the decoupling capacitors and 50 Mohm

Task list and schedule for each main item:

Work started in order to go into the details and timing

- Anodes and CRUs (BNL, CERN)
- Top electronics interface (KEK, Lyon, BNL, CERN)
- Bottom electronics (BNL, FNAL, CERN)
- CRP structure components (LAPP)
- CRP assembly (from assembled CRUs to CRP) (LAPP, ...)
- CRP transport box design and production (LAPP)
- CRP transport box design and production (LAPP)
- CRP instrumentation (LPSC, CERN,)

Terminology

- ❑ PCB anode subpanel: perforated PCB unit produced by the company 1.7m x0.5m
- ❑ CRU layer: PCB anode layer made of 6 subpanels glued together = 1.7m x 3m
- ❑ The anode PCB with shield and induction#1 strips is called « shield layer »
- ❑ The anode PCB with induction#2 and collection strips is called « collection layer »
- ❑ a CRU is made of 1 shield layer + 1 collection layer + adapter boards

Task list for first CRP production for cold box test:

=====

Anode and CRUs (BNL, CERN)

=====

Anodes (perforated)

- design and gerber file - week of March 15
- PCB procurement - week of March 22
- PCB anode production - 6 weeks from the time of placing the order. mid April - beginning of June
- anode reception - beginning-mid of June

Connecting devices (to link the 2 PCB layers called 'shield' and 'collection' and connect the adapter boards)

- procurement - - April-May

PCB Manipulation tooling (depends on connection and assembly technics procedure)

- design - April?
- part procurement - April-May?
- reception and assembly - June?

=====

Anode and CRUs (BNL, CERN) PART 2

=====

CRU#1 shield layer

- gluing from 6 subpanels - 1 day/gluing and drying - 1 week total
- Silver connection painting - 1 day for painting and drying. 1 week total (try to parallelize with gluing) - 1 week additional in conservative estimation if we cannot parallelize with gluing
- Connector installation and soldering (depends on technical choices) - if pogo pins --> may be automated?. If manual soldering -> meeting with CERN electronics assembly workshop supervisor to know more
- Electrical test - 1-2 days

(for silver paint: assume polymerization at room temperature)

-- Dates: start mid June, finalize end of June

Manual soldering of connectors: for the 4 CRUs is 1 week

CRU#2 shield layer

- gluing from 3 subpanels - same as above
- Silver connection painting - same as above
- Connector installation and soldering (depends on technical choices) - same as above
- Electrical test - same as above

-- Dates: start beginning of July, finalize mid of July

=====

Anode and CRUs (BNL, CERN) PART 3

=====

CRU#1 collection layer

- gluing from 3 subpanels - same as above
- Silver connection painting (assume polymerization at room temperature) - same as above
- Connector installation and soldering (depends on technical choices) - same as above
- Electrical test - more channels here. 1 week of testing (induction-2 + collection)

-- Dates: assume we'll get faster with gluing and painting. Then the gained time can be used for testing.

Start mid July, finalize end of July

CRU#2 collection layer

- gluing from 3 subpanels - same as above
- Silver connection painting (assume polymerization at room temperature) - same as above
- Connector installation and soldering (depends on technical choices) - same as above
- Electrical test - 1 week

-- Dates: assume we'll get faster with gluing and painting. Then the gained time can be used for testing.

Start beginning of August, finalize mid of August

=====

Anode and CRUs (BNL, CERN) PART 4

=====

CRU#1 (made of 2 PCB anode layers + adapter boards)

- mechanical assembly and connection of both layers - **This is a handling process where we need to bring the two units together to attach them. Manipulating them precisely** - 1-2 days. (If we need to install spacers or something like that for the CRP mechanical structure it may take 1-2 more days.)
- installation of adapter boards - 1-2 days
- control test - 1-2 days (warm noise/functionality test with electronics)
- ?? cold test?? - should we plan some test?

-- Dates: 1 week from mid August

CRU#2 (made of 2 PCB anode layers + adapter boards)

- **mechanical assembly and connection of both layers - same as CRU#1**
- installation of adapter boards - same as CRU#1
- control test - same as CRU#1
- ??cold-test?? - should we plan some test?

-- Dates: 1 week at the end of August

Task list for first CRP production for coldbox test:

Top Electronics interface (KEK, BNL, CERN)

- connector procurement
- adapter boards
 - design
 - part procurement (PCB + resistors + capacitors)
 - fabrication (including connector soldering)

Bottom Electronics (FNAL, BNL, CERN)

- adapter boards
 - design
 - part procurement (PCB + resistors + capacitors)
 - fabrication
- CE FEMB
- Power and data cables
- CE boxes
 - design
 - procurement

CRP structure components (LAPP)

- CRP composite support structure
 - material characterisation (CTE) by mid March
 - concept drawing (composite vs PCB assembly) by mid March
 - design (beginning of April)
 - procurement (end of April)
 - production (6 weeks => mid June)

CRP metallic frame

- design (April)
- procurement (mid April)
- production (5 weeks => end of May)

CRP decoupling system

- design (mid April)
- prototype and test (end of April)
- procurement (mid May)
- production (?)

CRP suspension feedthroughs (use same below and flange as previous cold box tests)

- manual winch system design
- procurement
- production

CRP transport box (LAPP, ...) (could be based on additional elements to the existing metallic frame)

- CRP transport box
 - design
 - part procurement
 - assembly
 - (Maintenance test?)

CRP instrumentation (LPSC, CERN, ...)

- Sensor
 - design
 - part procurement (sensor + Read Out electronics + cables)
 -

CRP assembly (from assembled CRUs to CRP) (LAPP, ...)

CRP mounting procedure definition

CRP mounting tooling


- design
- part procurement
- reception and assembly

Metallic frame attachment


CRU attachment to support frame

CE module cable routing

Instrumentation (Pt/level meter..) installation and cabling



Task list for first CRP production for coldbox test:



First draft version of the detailed project schedule

Procedures are being refined

A preliminary version available by next week

