Z boson production in association with at least two b jets in pp collisions at 13 TeV: signal versus background

Peter Young State University of New York at Buffalo New Perspectives - August 18, 2021


University at Buffalo The State University of New York





Overview


- Motivation
- Signal vs. Background
- Data-Driven Background Estimation
- Analysis Results
- Summary





Motivation (I)

- Z boson produced in associated with bottom quark jets (b-jets) provide important tests of perturbative quantum chromodynamics (pQCD) calculations
- The processes form major background for a variety of physics analyses
 - Higgs production in association with a Z boson, ZH(H→bb/cc)
 - Beyond Standard Model (BSM) search for new generations of heavy quarks (b',t') decaying to Z boson and a b quark (Z+b jet)
- Measurements of various event kinematic properties are important to tune Monte Carlo (MC) simulations of Z + jets production







Fig 1. Feynman diagrams of tree-level contributions for $Z + \ge 1$ b-jet (top) and $Z + \ge 2$ b-jets (bottom) processes

3



Motivation (II)

- Z boson produced in association with \geq 2 b-jets ٠
 - Z boson decays into lepton (e^+e^- , $\mu^+\mu^-$) pair -
 - Expect at least 2-jets, tagged by DeepCSV as b-jets -
- Part of first on-going CMS analysis of Z+b-jets done at ٠ \sqrt{s} = 13 TeV using full Run II data, 137 fb⁻¹
- Previous Z + heavy-flavor (HF) jets done at \sqrt{s} = 8 TeV, ۲ Run I data*







Fig 2. Event candidate for Z + two b-jets, Z decay into $\mu^+\mu^-$ pair




*Eur. Phys. J. C 77 (2017) 751, arXiv:1611.06507v2 [hep-ex].





Event Selection Criteria (I)

- Full Run II data with integrated luminosity of 137.1 fb⁻¹ (2016, 2017, 2018)
- Trigger: SingleElectron, SingleMuon Trigger
- Leptons: isolated with leading (sub-leading) lepton $p_{T} > 35$ (25) GeV $|\eta| < 2.4$
- Z boson: pair of oppositely charged leading and sub-leading leptons within the mass window 71 GeV < $M_{_{Pl}}$ < 111 GeV
- Jet: jets reconstructed with anti- k_{T} algorithm with distance parameter of 0.4 $p_{T} > 30 \text{ GeV}, |\eta| < 2.4$, lepton overlap removal, tight jet ID jets from pileup events are excluded





Event Selection Criteria (II)

• b-jets: jets tagged with DeepCSV tagger

tight tagging operating point is required to reduce Drell-Yan (DY) + jets background: DY+bX, DY+XX, where X = c- or light jets

loose, medium, tight operating points correspond to approximately 80%, 60%, 50% b quark tagging efficiency and 10%, 1%, and 0.1% misidentification rate for light jets

• Missing Transverse Energy (MET), MET < 50 GeV \rightarrow reduces the background





Fig 3. Background process for $Z + \ge 2$ b-jets where c- or light (u,d,s) jets are produced in association






Events after $Z + \ge 2$ b-jets Selection

- Numerous backgrounds in signal (DY+bb) region
- tt background is not negligible, accounts for $\sim \frac{1}{3}$ of total events
- tt accounts for ~85% of overall background events

	2016		2017		2018	
	Electron	Muon	Electron	Muon	Electron	Muon
DY+bb	1976	4206	2241	4557	4361	8934
DY+bX	38	89	29	81	72	190
DY+XX	10	89	2	55	43	237
tt	784	1748	1102	2362	1825	3865
single t	18	40	22	59	48	99
VV	44	97	65	136	98	218
ZH	11	22	13	27	23	45
МС	2880	6291	3473	7278	6470	13589
Data	2549	5503	3070	6554	5070	10757
Data/MC	0.89	0.87	0.88	0.90	0.78	0.79

Table 12: Number of events after $Z + \ge 2 b$ jets selection







Fig 4. (Left to right, top to bottom) Dilepton invariant mass and leading lepton p_{T} distributions for muon channel (combined Run II data), Feynman diagram for tt production process




Signal vs. Background

• MET in tt and signal events are very different

 $t\bar{t} \to W^+ W^- b\bar{b} \to \ell^+ \ell^- \nu \bar{\nu} b\bar{b}$ $Z b\bar{b} \to \ell^+ \ell^- b\bar{b}$

- Determine optimal MET cut to optimize event selection
- 50 GeV cut → 90% signal and 30% background events are kept
- Keep events where MET < 50 GeV





Data-Driven Background Estimation (I)

- Backgrounds can be estimated using MC simulations
- tt can be more precisely estimated with data-driven methods
- Technique applied in earlier analyses at CDF (Tevatron)*, CMS**
- Outside Z signal region, events are mostly composed of background events
- Estimate background rate using sideband region

* *Phys. Rev. D* **79** (Mar, 2009) 052008, doi:10.1103/PhysRevD.79.052008. ***Eur. Phys. J. C* **77** (2017) 751, arXiv:1611.06507v2 [hep-ex].




Fig 6. e⁺e⁻ invariant mass distribution for 2018 data; the region within the dashed lines indicates the signal region






Data-Driven Background Estimation (II)

- Use same trigger, event selection criteria as analysis
- Sideband regions $40 < M_{u} < 66 \text{ GeV}$ $M_{u} > 116 \text{ GeV}$
- Enrich tt sample (suppress Z+jet events) by using events where MET > 80 GeV
- Match sideband regions (ee,µµ) with eµ events
- Fit dilepton data distribution to pull normalization constant between dilepton and eµ distributions
- Expect $c_t = 0.5$ due to combinatorics of final state particles

$$V_{\ell\ell} = c_t \cdot N_{e\mu}$$
 $\ell\ell = ee, \mu\mu$
 $c_t \sim \frac{1}{2}$





Results (I)

- Scale eµ sample by extracted coefficient
- Scaled sample matches sideband regions and tt MC simulation within uncertainty




FIG 7. Z + ≥ 2 b-jets dilepton invariant mass sideband region fitted for electron (left) and muon (right) channels, 2018 data





Results (II)

- Subtract eµ events from the dilepton invariant mass distribution to isolate the signal
- Scaled eµ sample matches tt MC over entire region within 10%




FIG 8. $Z + \ge 2$ b-jets dilepton invariant mass fit between eµ data and ttbar MC samples for electron (left) and muon (right) channels, 2018 data






Results (III)

- Same process can be applied to MET, MET Significance distributions
- Various fits match within a maximum variation of 7%

Sample	Z Mass	MET	MET Significance
2016 Electron Channel	0.526 ± 0.008	0.528 ± 0.006	0.524 ± 0.007
2017 Electron Channel	0.530 ± 0.007	0.559 ± 0.005	0.544 ± 0.007
2018 Electron Channel	0.517 ± 0.006	0.537 ± 0.004	0.519 ± 0.005

Sample	Z Mass	МЕТ	MET Significance
2016 Muon Channel	0.627 ± 0.009	0.643 ± 0.006	0.632 ± 0.007
2017 Muon Channel	0.620 ± 0.007	0.669 ± 0.005	0.640 ± 0.007
2018 Muon Channel	0.621 ± 0.006	0.656 ± 0.004	0.641 ± 0.005 13






Cross Section Results

• After $Z + \ge 2$ b-jet selection and data-driven background estimation,

CHANNEL	MEASURED (pb)	MG5_aMC (LO) (pb)
Electron	0.66 ± 0.05 (stat) ± 0.08 (syst) ± 0.02 (theo)	0.677 ± 0.04 ± 0.01
Muon	0.65 ± 0.04 (stat) ± 0.07 (syst) ± 0.02 (theo)	0.677 ± 0.04 ± 0.01
Combined	0.65 ± 0.03 (stat) ± 0.07 (syst) ± 0.01 (theo)	0.677 ± 0.04 ± 0.01


• Measurements and predictions agree with each other





Summary


- Z+HF production provides important tests of pQCD calculations. It is an important background for numerous processes such as associated Higgs boson production ZH(H→bb/cc) and searches for New Physics
- In Z + 2 b-jets production, the background is dominated by tt events which can be reduced by MET requirements.
- Background rate can be estimated more accurately with data-driven method.
- Overall results show agreement between MC and data.







Thank you for listening.







ADDITIONAL SLIDES







Additional Fits





FIG 9. $Z + \ge 2$ b-jets MET distribution (left) and MET significance distribution (right) fit between eµ data and ttbar MC samples for electron channel, 2018 data

18

tt Production

CMS

FIG 10. Feynman diagram for ttbar production



- Top quark decays into W boson and quark
- W boson decays into charged lepton and neutrino
- $\sigma(tt \rightarrow \ell \ell + MET + \ge 2 \text{ jets}) \sim 170 \text{ pb}$

CMS

Missing Transverse Energy

• In ideal case,

 $\sum_{i=0}^{N} E_{T,i} = 0$

- Neutrinos are not detected by CMS detector, leaving an imbalance in transverse energy
- Random noise in system, errors in detectors can lead to some level of imbalance
- Very few events will truly have MET = 0 GeV




FIG 10. A sample cross section demonstration of missing transverse energy

