


MICE Spectrometer Solenoid FY12 Plans

MAP L1 + L2 Management Meeting

October 20, 2011

Steve Virostek

Lawrence Berkeley National Lab




Topics




- Overview of the Spectrometer Solenoids
- Modification plans
- Current status
- Schedule
- FY12 Budget

Spectrometer Solenoid #1



Spectrometer Solenoid #2



Spectrometer Solenoid Overview



- **Key requirements:** coils must be trained to 275 amps, and the cryocoolers must maintain the LHe in the cold mass (no boil-off) **Not yet achieved for either magnet**
- Both magnets have previously been assembled and tested
- Various design issues and test failures have necessitated disassembly of both of the magnets
 - Magnet 1: blockages in the helium recondensing circuit prevented operation of the thermal siphon
 - Magnet 2: Failed HTS lead due to inadequate cooling of the upper end of the leads
 - Magnet 2B: Failed LTS lead in the cold mass and overheated quench resistors
- All design issues being addressed with recent modifications



Design and Analysis Work







- Based on the results of the previous testing and the recommendations of several review committees, LBNL has carried out an extensive series of analyses
- A variety of design improvements are being implemented based on the results of the analyses
- The focus of the analyses included:
 - Quench protection system including the suitability of the existing passive system instead of an active system
 - Heat leaks to the 4.2K cold mass
 - Thermal/mechanical performance of the radiation shield
 - Overall shield and cold mass cooling power available




Design Modification Plan



- Reduction of cold mass heat leaks:
 - Improve MLI application and QC
 - Improve vacuum insulation and measurement
 - Eliminate radiation shine in vent/fill lines
 - Implement provisions to damp thermo-acoustic oscillations
 - Reduce cold mass support intercept temperatures
- Improvement of the passive quench protection system :
 - Analyses indicate passive system will work
 - Divert current from quenched HTS leads with an active, external circuit
 - Conductively cool the quench resistors to prevent overheating
- Addition of two 2-stage cryocoolers to the system
- Stabilize the cold leads w/extra copper to prevent burnout
- Improve the radiation shield performance:
 - Reconstruct the majority of the shield with pure aluminum
 - Improve the thermal connection from the cryocoolers to the shield






Current Magnet Status




- The completed modification plan has been presented to the MAP TB
- A contract mod was made to the Wang PO for the completion of detailed design work for the system modifications (now complete)
- A 2nd contract mod was made to the Wang PO for completing the physical magnet modifications (now under way)
- The Magnet 2 cold mass has been opened to allow modification
- The radiation shields have been remade with 1100 aluminum
- Custom MLI blankets for the cold mass have been procured
- A conductively cooled quench resistor assembly has been fabricated
- Modifications to the magnet vacuum vessels for added cryocoolers have been completed
- The Magnet 2 cold mass will be ready for leak check in ~2 weeks
- Magnet 1 to follow Magnet 2 by ~ 3 months in the schedule



FY12 Schedule



Spectrometer Solenoid FY12 Schedule





Budget Scenarios (+/-20%)



- A budget variation of +/-20% is not likely to have any effect on the Spectrometer Solenoid completion during FY12
- The same source of equipment money is being used by LBNL for the MICE RFCC modules (including the coupling coils)
- A budget variation will have an impact on the RFCC FY12 work (see next talk)

MICE RFCC Module

FY12 Plans

MAP L1 + L2 Management Meeting

October 20, 2011

Steve Virostek


Lawrence Berkeley National Lab



Topics



- Overview of the RFCC Modules
- Coupling Coil status
- Coupling Coil plans
- RFCC Module status and plans
- Schedule
- FY12 Budget







RFCC Module Overview



- The MICE RF and Coupling Coil Module has been designed by LBNL and our collaborators
- MICE incorporates two RFCC modules to be provided by LBNL
- Each module consists of a single superconducting Coupling Coil integrated with four tunable 201 MHz normal conducting RF cavities and a vacuum vessel
- The Coupling Coil design was developed by the Harbin Institute of Technology in China (a MICE collaborator)
- A third Coupling Coil (first delivered) for MuCool will be sited in the MTA at Fermilab
- The 201 MHz cavity design is based on the prototype cavity developed by LBNL and J-Lab and now operating in the MTA

RFCC Module Overview






Coupling Coil Status



- The detailed design of the Coupling Coils is complete with the exception of the quench protection system and the lead stabilization detailed designs (to be undertaken by MIT)
- LBNL is currently carrying out changes to the fabrication drawings as well as translation from Chinese to English
- Winding and fabrication of the first Coupling Coil cold mass was completed at the QiHuan Company in Beijing, China
- The coil arrived at LBNL last week where cooling tube welding and epoxy potting will be completed
- Additional superconductor for the two MICE coils is currently being procured



Coupling Coil Plans




- Current plans call for all three cold masses to be tested and trained to full current at Fermilab prior to magnet assembly
- A suitable test cryostat obtained from FSU is now at Fermilab being prepared for coil testing
- All parts for the magnet cryostats will be fabricated in China by the QiHuan Company and shipped to the US
- Current plan is for QiHuan to also wind the 2nd and 3rd coils
- Various options for cryostat assembly and welding being explored: outside vendor (Meyer Tool or other), FNAL, LBNL
- Assembly of the first unit likely to occur at FNAL or LBNL
- Assembly of 2nd and 3rd units still in planning: options include QiHuan, FNAL, LBNL, RAL, outside vendor



RFCC Module Status and Plans




- Work on other RFCC components has continued at LBNL at a slower pace due to Coupling Coil delays and limited funding
- All associated design work has been completed
- Ten copper RF cavities are complete and at LBNL
- Cavity tuner prototype has been fabricated and tested
- RF and beryllium windows for first module are now on hand
- Activities at LBNL for FY12 include: surface prep and electropolishing of cavities, fabrication of tuner actuators
- FNAL FY12 activities: fabrication of RF couplers for prototype and single MICE cavities, fabrication of tuner arms for a single cavity test




FY12 Schedule



Coupling Coil FY12 Schedule



- Schedule of FY12 RFCC cavity related tasks at LBNL are not shown here



FY12 Budget



RFCC Tasks (cavities)

| Description | Labor (\$k) | M&S (\$k) |
|-------------------------------|-------------|-----------|
| Ongoing design at LBNL | 15 | |
| Management and fab oversight | 72 | |
| First cavity tuner actuators | | 30 |
| Cavity prep for electropolish | 22 | 3 |
| Cavity electropolish | 25 | 12 |
| Totals | 134 | 45 |

**Total RFCC costs: \$876k + \$210k contingency
= \$1086k**

Coupling Coil Tasks (LBNL only)

| Description | Labor (\$k) | M&S (\$k) |
|-------------------------------------|-------------|------------|
| Fab drawings and design issues | 55 | |
| Management and fab oversight | 109 | |
| Quench protection/lead design (MIT) | 198 | |
| Control system design and fab | 40 | |
| Cooling tube weld at LBNL (2 coils) | 28 | 4 |
| Epoxy potting at LBNL | 9 | 3 |
| Cryocoolers (3 each) | | 159 |
| Sensor procurement | | 40 |
| Shipping to FNAL (coils and parts) | | 16 |
| Shipping to LBNL (from China) | | 36 |
| Totals | 439 | 258 |

- Costs shown are LBNL costs only and do not include FNAL testing efforts or possible magnet assembly effort



Budget and Planning Issues



- There are still many uncertainties in the RFCC completion plan, particularly associated with the assembly of the Coupling Coil cryostats and final assembly and testing
- Not included in the budget presented here:
 - test cryostat setup/cold mass testing at FNAL (1st coil test in FY12)
 - cryostat assembly for at least 1st unit (\$200k - \$400k each)
 - 1st magnet final assembly and testing
- Further uncertainties for the assembly of the 2nd and 3rd magnets in FY13 and beyond
- The possibility of winding one or two extra coils has been discussed as a contingency, but not yet planned or budgeted



Budget Scenarios (+/-20%)



- A decrease in the LBNL budgeted work would likely result in: reduced contingency, delay of RF cavity surface processing, deferment of cryocooler purchase
- Budget increase: any additional funding would likely be used to move forward earlier with the work on the 2nd and 3rd coupling coils (primarily cryostat assembly)
- There are still big unknowns in the cost and budget for the assembly and testing of the first magnet since the plan is not yet established