
NML (ASTA) Buildout and Operations

- The Accelerator Science Test Accelerator ?**
- The Advanced Science and Technology Accelerator ?**
- The Advanced Superconducting Test Accelerator ?**
- The Advanced Superconducting Technology Accelerator ?**
- None of the above ?**

Mike Church
Accelerator Sector Planning and Strategy Workshop
Oct. 27 – 28, 2011

Beam Parameters

ASTA will be capable of operating with a wide range of beam parameters. As with all photoinjectors, many beam parameters are coupled, especially to the bunch intensity, due to space charge effects.

| parameter | ILC RF unit test | range | comments |
|-----------------------------|------------------|----------------------------|---|
| bunch charge | 3.2 nC | 10's of pC to >20 nC | minimum determined by diagnostics thresholds; maximum determined by cathode QE and laser power |
| bunch spacing | 333 nsec | <10 nsec to 10 sec | lower laser power at minimum bunch spacing |
| bunch train length | 1 msec | 1 bunch to 1 msec | maximum limited by modulator and klystron power |
| bunch train repetition rate | 5 Hz | 0.1 Hz to 5 Hz | minimum may be determined by gun temperature regulation and other stability considerations |
| norm. transverse emittance | <20 mm-mrad | <1 mm-mrad to >100 mm-mrad | maximum limited by aperture and beam losses; without bunch compression emittance is ~5 mm-mrad @ 3.2 nC |
| RMS bunch length | 1 ps | ~10's of fs to ~10's of ps | minimum obtained with Ti:Sa laser; maximum obtained with laser pulse stacking |
| peak bunch current | 4 kA | > 10 kA (?) | 4 kA based on Impact-Z simulations with low energy bunch compressor |
| injection energy | 40 MeV | 5 MeV – 50 MeV | may be difficult to transport 5 MeV to the dump; maximum is determined by booster cavity gradients |
| high energy | 810 MeV | 40 MeV – 1500 MeV | radiation shielding issues limit the maximum |

Accomplishments to Date

- **Project was started in 2006**
- **Completion of civil construction of new electrical service building and tunnel**
- **Installation of a large amount of infrastructure – power, water, cryogenics, shielding, HVAC, RF, etc.**
- **Commissioning and operation of first full Fermilab-assembled cryomodule at high RF power**
 - **>20 MeV/m average accelerating gradient @ 1 msec flattop pulse length**
- **Commissioning of SC booster cavity (“CC2”) @ 24 MeV/m**
- **Commissioning of cathode preparation chamber**

Strategy

- **The long term goal of this facility is to establish an advisory committee-reviewed, proposal-driven user beam facility to carry out advanced accelerator R&D by the world accelerator physics community.**
- **This research can be aimed at a variety of applications: HEP, light source, homeland security, instrumentation, or other fields where a medium to high energy electron beam is relevant.**
 - **A discussion of some of the possibilities will follow in P. Piot's talk.**
- **NML will be unique in the U.S.**
 - **Dedicated facility; high intensity; high repetition rate; high energy**
- **The facility will require a dedicated department of ~10 staff to operate efficiently and with high reliability to serve a user community. It will need to be well integrated into Fermilab Accelerator operational practice.**

Overall Goals and Plans

- **2012**
 - replace cryomodule 1 with cryomodule 2
 - establish 1st beam operation from gun to HE dump with a single cryomodule
- **2013**
 - establish high intensity, stable operation with a single cryomodule
 - install 2 more cryomodules
 - commission new refrigerator
 - start 1st AARD experiment (X-ray production from crystal)
 - start installation of IOTA
- **2014**
 - establish high intensity, stable operation with 3 cryomodules; start ILC string test
 - start IOTA operation
- **2015**
 - continue (complete?) ILC RF string test
 - start installation of double emittance exchange experiment
- **2016 ---**
 - Directions undetermined -- reconfiguration for FEL? addition of 2nd bunch compressor and 4th cryomodule ? addition of 3 more cryomodules ? future AARD experiments ?

“Barriers”

- **Requires the continuing commitment of Fermilab management and DOE to support AARD even if it is not directly applicable to HEP.**
- **We are in competition with other facilities for limited R&D funds....**
- **There are technical challenges, but I do not see any of these as being a “barrier”.**
 - **Learning to operate this high energy, high intensity accelerator within the Fermilab safety envelope will be a challenge.**
- **AARD experiments need to be well-chosen and require a reasonable rate of success in order for the facility to maintain credibility.**
- **We all live with manpower and \$\$ limitations. I see these potentially delaying the schedule, but not as “barriers.”**

FY12 Plans in More Detail

- Complete high power tests and feedback studies with CM1
- Install and commission new photocathode laser (1st complete laser hut)
- Complete high power conditioning of gun RF windows; finish installation of gun RF system; install gun; commission gun
- Replace CM1 with CM2 and recommission
- Remove 9-cell booster cavity from A0 (CC1); refurbish; install at ASTA; commission to high power
- Finish installation of high energy dump and RAW system
- Finish design and installation of low energy dump and RAW system
- Install beamline components – magnets, instrumentation, vacuum components, ...
- Reconfigure shielding for beam transport to the high energy dump
- Develop suite of application programs for basic operations
- Complete radiation shielding assessment and SAD
- Install Machine Protection System
- Start beam commissioning – 1st 2 Faraday cup downstream of gun, then to 40 MeV dump, then to high energy dump

- **Deliverable**

- **low intensity ~250 MeV beam to the high energy dump**

FY13 – FY14 Plans in More Detail

- Remove 5-cell deflecting mode cavity from A0; refurbish; install at ASTA
- Establish high intensity operation with a single cryomodule
- Install 1st AARD experiment (X-ray production from crystal) in 40 MeV beamline
- Install IOTA ring
- Install and commission 2 more cryomodules
- Commission new refrigerator
- Establish reliable high intensity 800 MeV beam operation

• Deliverables

- High intensity ~800 MeV beam to the high energy dump
- Installation of IOTA and x-ray production experiment

Resources

- **The vast majority of resources for this project come via Project 18**
 - see R. Kephart's talk
- **FY12:**
 - **NML buildout has been allotted 2.5 M\$ M&S; requests from task leaders amount to 4.4 M\$; this has been prioritized so that 3.0 M\$ is being requested for FY12**
- **Future operations:**
 - **A department of 10 people has been formed in AD (SRF Electron Test Facility Dept.). I believe this is adequate to operate ASTA.**
 - **I estimate an additional 5 FTE's from support groups will be required to keep the facility operating reliably.**
 - **This does not include effort for building and installing AARD experiments**

Risks

- **Primarily schedule risks**
 - **Installation, RF cavity conditioning, cryo commissioning, and beam operation conflicts may slow down overall progress**
 - **Gun may take longer to commission than anticipated**
- **Technical risks**
 - **Beam energy may be limited by cavity gradients**
 - **Beam intensity may be limited by beam losses, dark current, and radiation**
 - **Beam quality may be limited by problems with the gun**