# The ILC Project


Benno List, DESY

**Joint Discussion with AF** 

Snowmass Energy Frontier Workshop – Restart Sep 1, 2021

### The International Linear Collider





Delivers canonical Higgs factory physics programme prioritized by European Strategy

### **Key technologies**


• e<sup>+</sup>e<sup>-</sup> linear collider

- Superconducting RF main linac
- Nanobeams damping rings and final focus

# Technological Readiness: Key Technologies are Proven




### SCRF Technology: Available on Industrial Scale







### **Nanobeam Technology**



# **Upgradeable in Energy and Luminosity**




- Possible energy upgrades: 500GeV, 1TeV -> need tunnel extension
- Tunnel can be built while running
- Luminosity upgrades:

Options A, A': 250 GeV tunnel

• More RF: factor 2 (1.35 -> 2.7E34)

125GeV e-

- + Run 500GeV machine at 250GeV, 10Hz: factor 2 (2.7E34 -> 5.4E34)
- Improves power efficiency



[fb<sup>-</sup>]

4000

3000

2000

ILC, Scenario H20-staged ECM = 250 GeV

> ECM = 350 GeV ECM = 500 GeV

> > arXiv:1711.00568

20

years


# **Energy Efficient and Affordable**



### **Sustainability**


above 300GeV

Superconducting technology for energy conservation 110MW wall plug power at 250GeV



https://green-ilc.in2p3.fr/home/

Costs



Total cost, estimated by ILC advisory panel, Japan\*

635-703G¥ (6.35-7.03G\$), including human ressources

(\*) https://www.mext.go.jp/component/b\_menu/shingi/toushin/icsFiles/afieldfile/2018/09/20/1409220 2 1.pdf

# **Ready for Construction**



### Site in Kitakami

Morioka 秋田。秋田県 2. Civil Engineering 1 ILC Location ILC accelerator area: inside the granite rock bodies 宮城県 → On-going jobs : Optimal accelerator placement, land-acquisition Sendai ② Geological Surveys Electric Prospecting (crack) 新潟県 Seismic Exploration (stiffness) Boring Survey · Borehole Camera Measurement of Initial Stre

Candidate site identified 50km space for 1 TeV Geology is excellent


> → inside black curves (left) → in the pink color (right)

→ no issues from previous surveys

→ requiring : additional surveys around-access tunnel head and access tunnel inside for detailed designing

### Schedule

- 4 year Pre-Lab (hosted by KEK, Japan) phase for R&D, Engineering Design Report, Construction preparation
- ILC Laboratory (international): 10 year construction phase
- Ready for Physics in 2036



# **An International Project**



### **International Development Team**

- Mandated by ICFA
- Prepares Pre-Lab

Active Working Groups on => Welcoming your participation!

- Physics, Detectors, Software
- Accelerator Topics

### **ICFA**

### **Recent Developments**

- Pre-Lab Proposal submitted to MEXT
- Continuing support from DOE and State Dpt.
- MEXT contacted several European funding agencies to initiate consultations

### **ILC International Development Team**

### **Executive Board** Americas Liaison Andrew Lankford (UC Irvine) Working Group 2 Chair Shinichiro Michizono (KEK) Working Group 3 Chair Hitoshi Murayama (UC Berkeley/U. Tokyo) Executive Board Chair and Working Group 1 Chair Tatsuya Nakada (EPFL) KEK Liaison Yasuhiro Okada (KEK) Europe Liaison Steinar Stapnes (CERN) Asia-Pacific Liaison Geoffrey Taylor (U. Melbourne)

**Working Group 1** Pre-Lab Setup

**Working Group 2** Accelerator

**Working Group 3** Physics & Detectors

international development team

### A mature project ready to go



# **BACKUP**

# **ILC Parameters for Reference**




Quantity	Symbol	Symbol Unit Initial ${\cal L}$ Upgrades Ene		Energy U	ergy Upgrades	
Centre of mass energy	$\sqrt{s}$	${ m GeV}$	250	250	500	1000
Luminosity	$\mathcal{L} 10^{34} \mathrm{cm}$	$\mathrm{n}^{-2}\mathrm{s}^{-1}$	1.35	$2.7 \ / \ 5.4$	$1.8 \ / \ 3.6$	4.9
Polarisation for $e^-(e^+)$	$P_{-}(P_{+})$		80%(30%)	80%(30%)	80%(30%)	80%(20%)
Repetition frequency	$f_{ m rep}$	${ m Hz}$	5	5 / 10	5	4
Bunches per pulse	$n_{ m bunch}$	1	1312	2625	$1312 \ / \ 2625$	2450
Bunch population	$N_{ m e}$	$10^{10}$	2	2	2	1.74
Linac bunch interval	$\Delta t_{ m b}$	ns	554	366	554/366	366
Beam current in pulse	$I_{ m pulse}$	mA	5.8	5.8	5.8 / 8.8	7.6
Beam pulse duration	$t_{ m pulse}$	$\mu \mathrm{s}$	727	961	727/961	897
Average beam power	$P_{ m ave}$	MW	5.3	$10.5 \ / \ 21$	$10.5 \ / \ 21$	27.2
Norm. hor. emitt. at IP	$\gamma \epsilon_{\rm x}$	$\mu\mathrm{m}$	5	5	10	10
Norm. vert. emitt. at IP	$\gamma \epsilon_{ m y}$	nm	35	35	35	30
RMS hor. beam size at IP	$\sigma_{ m x}^*$	nm	516	516	474	335
RMS vert. beam size at IP	$\sigma_{ m v}^*$	nm	7.7	7.7	5.9	2.7
Luminosity in top $1\%$	$\mathcal{L}_{0.01}/\mathcal{L}$		73%	73%	58.3%	44.5%
Energy loss from beamstrahlung	$\delta_{ m BS}$		2.6%	2.6%	4.5%	10.5%
Site AC power	$P_{ m site}$	MW	111	138 / 198	173 / 215	300
Site length	$L_{ m site}$	$\mathrm{km}$	20.5	20.5	31	40


arXiv:1903.01629, AC power updated

# Technology challenge: High gradient, high Q<sub>0</sub>, high yield



- Baseline specification: 31.5MV/m, Q<sub>0</sub>=1E10, 90%yield
- With new surface treatments: 35MV/m, Q<sub>0</sub>=1.6E10 -> yield?
- >2000 cavities produced world wide, for FLASH, E-XFEL, LCLS-II, ...
- R&D pushes performance limits
- · Mass production still a challenge









# Nanobeam Technology



- ILC: 516 x 7.7 nm<sup>2</sup> beamspot @ 250GeV
- CLIC: 149 x 2.9 nm @ 380GeV
- Nanobeams are common challenge
- Accelerator Test Facility 2 (ATF-2) at KEK as test bed & demonstrator
  - 41nm beamsize at 1.3GeV (ILC goal corresponds to 37nm)
  - 2nm stabilisation with feedback possible








# **ILC: Site Selection and Civil Engineering**





1 ILC Location

青森県

Sendai

秋田の秋田県

山形県

福島県


新潟

新潟県

Morioka

ILC accelerator area: inside the granite rock bodies

- → inside black curves (left)
- → in the pink color (right)
- → possible up to 50 km




→ On-going jobs : Optimal accelerator placement, considering surface environment, land-use and

land-acquisition

### Geological Surveys

- Electric Prospecting (crack)
- Seismic Exploration (stiffness)
- Boring Survey
- Borehole Camera
- Measurement of Initial Stress of the Ground





- → no issues from previous surveys
- → requiring : additional surveys around-access tunnel head and access tunnel inside for detailed designing



A. Suzuki, LCWS 2021, https://indico.cern.ch/event/995633/contributions/4240506/

# From LCC to the Pre-Lab Proposal



- 2013-Jun 2020: Linear Collider Collaboration LCC under ICFA Mandate, governed by Linear Collider Board LCB
- 2014-2018: MEXT appointed ILC Advisory Panel reviews project, incl. new 250GeV baseline
- Feb-Jun 2020: LCB proposes International Development Team IDT to prepare an ILC-Pre-Lab
- Aug 2020: ICFA establishes IDT and appoints IDT Executive Board (\*)
- Goal: establish an ILC Pre-Lab within ~1.5 years
- IDT focusses on ILC realization, KEK provides support (admin., financial)
- June 2021: IDT submits Pre-Lab proposal



### Reminder for ICFA mandate for the IDT

- Clarifying the function and organisation of the ILC Pre-Lab based on the KEK International Working Group report,
- Developing a common understanding for the condition to start the ILC Pre-Lab,
- Providing an international framework for the ILC accelerator effort and coordinating further R&D and engineering design work for the ILC in order to sustain the community effort and to guarantee a smooth transition to the ILC Pre-Lab phase,
- Providing an international framework for the ILC physics and detector activities and coordinating physics and detector R&D effort in order to sustain the community effort and guarantee a smooth transition to the ILC Pre-Lab phase,
- Discussing with international partners (e.g. universities, national and regional laboratories)
   for resources needed for the ILC Pre-Lab, and
- Providing necessary information to the national authorities to support their discussion of the establishment of the ILC Pre-Lab.

(\*) https://icfa.fnal.gov/wp-content/uploads/ICFA\_Statement\_August\_2020.pdf

# The Pre-Lab Proposal



- Purpose of the Pre-Lab:
  - To bring the technical and engineering work of the ILC project to a point where the construction can be started.

### Mandate:


- Completion of technical preparations and production of engineering design documents for the accelerator complex
- Compilation of design studies and documentation of the civil engineering and site infrastructure work, and of the environmental impact assessment
- Community guidance to develop the ILC physics programme that will fully exploit its potential
- Provision of information to national authorities and to Japanese regional authorities to facilitate development of the ILC Laboratory
- Coordination of outreach and communication work

### ILC International Development Team publishes the Proposal for the ILC Preparatory Laboratory

1 June 2021 - ILC International Development Team

An international scientific consensus supports an electron-positron Higgs Factory as the highest-priority next collider, and timely construction of the International Linear Collider (ILC) hosted in Japan is strongly supported by the international community.

Today, the international effort to realise ILC in Japan took another step forward with the publication of the document titled "Proposal for the ILC Preparatory Laboratory (Pre-lab)". This proposal is prepared by the ILC International Development Team (ILC-IDT) and endorsed by the International Committee for Future Accelerators (ICFA).



"The IDT has achieved the major milestone of completing this proposal, which outlines the organisational framework, an implementation model and a work plan of the Pre-lab", said Tatsuya Nakada, Chair of the IDT Executive Board and Professor Emeritus at École Polytechnique Fédérale de Lausanne (EPFL) in Switzerland.

All the technical development and engineering design needed for the start of the construction of the ILC laboratory should be completed during the preparatory phase. In the same period, governmental authorities of interested nations are expected to forge an agreement on the sharing of the cost and responsibilities for the construction and operation of the ILC facility and

Proposal for the ILC Preparatory Laboratory (Pre-lab)

International Linear Collider International Development Team

1 June 2021

### Abetene

During the preparatory phase of the International Linear Collider (ILC) project, all technical development and engineering design needed for the start of ILC construction must be completed, in parallel with intergovernmental discussion of governance and sharing of responsibilities and cost. The ILC Preparatory Laboratory (Pre-lab) is conceived to execute the technical and engineering work and to assist the intergovernmental discussion by providing relevant information upon request. It will be based on a worldwide partnership among laboratories with a headquarters hosted in Japan. This proposal, prepared by the ILC International Development Team and endorsed by the International Committee for Future Accelerators, describes an organisational framework and work plan for the Pre-lab. Elaboration, modification and adjustment should be introduced for its implementation, in order to incorporate requirements arising from the physics community, laboratories, and governmental authorities interested in the ILC.


1

https://doi.org/10.5281/zenodo.4742043 arXiv:2106.00602

### **The Technical Preparation Plan**



- Technical Preparation Plan: addendum to the Pre-Lab proposal by IDT WG2 (accelerators)
- Outlines the technical work to be conducted during the Pre-lab phase
- Defines 18 R&D work packages in 5 areas:
  - · Main Linac and Superconducting RF
  - Sources
  - Damping Rings
  - · Beam Delivery System
  - Dumps
- Emphasis on critical issues identified by ILC advisory panel
- Aim: establish international collaboration to perform critical R&D during Pre-Lab phase
- International in-kind contributions



Technical Preparation and Work Packages (WPs)
during ILC Pre-lab


https://doi.org/10.5281/zenodo.4742018

# **ILC Main Linac: Superconducting RF Technology**



- ~8000 superconducting 9-cell cavities:
  1.3 GHz, 1.038m long, 31.5MV/m
- 9 cavities per 12m long cryomodule
- 10MW pulsed klystron per 4½ modules
- 2K operating temperature
  -> 4-6 cryo plants 19kW@4.5K
- Pulsed operation, 5Hz x 0.73ms
- European XFEL: 10% prototype in operation 100 cryomodules, 800 cavities
- LCLS-II, SHINE: Under construction / planned









# R&D on Main Linac and Superconducting RF



- Establish readiness of SRF technology for industrial production in Asia, Europe and Americas:
- WP01 Cavity Production
  - Produce 3x40 cavities with ILC specifications
  - Improve Q0 and gradient
- WP02 Cryomodule assembly
  - Build 3x2 ILC type cryomodules
  - "Cryomodule transportation program": ship 1 cryomodule/region to Japan, operate it
- WP03 Crab cavity
  - Develop crab cavity design for interaction region






### **Sources and Dumps**



- Electron source: Demonstrate laser-driven polarised electron gun design with a prototype
- Positron Source: 2 Concepts
  - Undulator Positron source (polarized):
     Demonstrate feasibility of target and capture device
  - Electron driven source:
     Demonstrate feasibility, design capture linac
  - Develop remote target handling concept
- Decide on positron source concept for initial operation
- Dumps:
  - Engineering design of 17MW main beam dump
  - Design photon dump for undulator source




# **Damping Rings and Beam Delivery System**



- Damping Rings:
  - Lattice and system design for damping rings
  - Evaluate permanent magnet option
  - Investigate and mitigate instabilities from collective effects (electron, fast ion)
  - Design fast kickers for injection and extraction


- Beam Delivery System:
  - Design the final focus system and test the final focus concept at ATF-3
  - Optimize the final focus doublet magnets, including prototypes



# Stapnes https://agenda.linearcollider.org/event/9203/

# **European Expertise and Pre-Lab Work Packages**





### ML & SRF

CEA, CERN, CIEMAT, UK, INFN Milano, DESY Not all European SRF labs represented

Additionally (in WBS but not in TPD):

- Long term cryo collaboration with CERN.
- HiEff RF another relevant activity
- SRF "basic" R&D for fabrication improvements or long term performance improvements (i.e. for upgrades)

### Sources

DESY, UK, CERN

Magnetic focusing

WP-10 Capture cavity

Target replacement

IJCLab also, other groups also possible (FCC-ee, Dafne)

DESY, UK, IJClab, CERN, Spain, INFN-LNF

Other light-sources labs possible (DR)

WBS design entries to be checked

ATF3 interests: UK, Germany, France, CERN, Spain



# 1.7.6 Proposals for upgrades or extensions

The ILC can be upgraded to higher energy and luminosity.

			Z-Po	ole [4]		Higgs [2,5]		500Ge	eV [1*]	TeV [1*]	
			Baseline	Lum. Up	Baseline	Lum. Up	L Up.10Hz	Baseline	Lum. Up	case B	
Center-of-Mass Energy	E <sub>CM</sub>	GeV	91.2	91.2	250	250	250	500	500	1000	Energy
Beam Energy	E <sub>beam</sub>	GeV	45.6	45.6	125	125	125	250	250	500	
Collision rate	$f_{col}$	Hz	3.7	3.7	5	5	10	5	5	4	
Pluse interval in electron main linac		ms	135	135	200	200	100	200	200	200	
Number of bunches	n <sub>b</sub>		1312	2625	1312	2625	2625	1312	2625	2450	
Bunch population	N	<b>10</b> <sup>10</sup>	2	2	2	2	2	2	2	1.737	
Bunch separation	$\Delta t_{b}$	ns	554	554	554	366	366	554	366	366	
Beam current		mA	5.79	5.79	5.79	8.75	8.75	5.79	8.75	7.60	
Average beam power at IP (2 beams)	$P_{B}$	MW	1.42	2.84	5.26	10.5	21.0	10.5	21.0	27.3	
RMS bunch length at ML & IP	$\sigma_z$	mm	0.41	0.41	0.30	0.30	0.30	0.30	0.30	0.225	
	$\gamma \mathbf{e}^*_{ imes}$	μm	6.2	6.2	5.0	5.0	5.0	10.0	10.0	10.0	
Emittance at IP (y)	$\gamma e^*_{y}$	nm	48.5	48.5	35.0	35.0	35.0	35.0	35.0	30.0	
Beam size at IP (x)	$\sigma^*_{\times}$	μm	1.118	1.118	0.515	0.515	0.515	0.474	0.474	0.335	
Beam size at IP (v)	$\sigma^*_{\scriptscriptstyle y}$	nm	14.56	14.56	7.66	7.66	7.66	5.86	5.86	2.66	
_uminosity	L	$10^{34}/cm^2/s$	0.205	0.410	1.35	2.70	5.40	1.79	3.60	5.11	Lumi.
Luminosity enhancement factor	$H_D$		2.16	2.16	2.55	2.55	2.55	2.38	2.39	1.93	
Luminosity at top 1%	$L_{0.01}/L$	%	99.0	99.0	74	74	74	58	58	45	
Number of beamstrahlung photons	ng		0.841	0.841	1.91	1.91	1.91	1.82	1.82	2.05	
Beamstrahlung energy loss	$\delta_{ extsf{BS}}$	%	0.157	0.157	2.62	2.62	2.62	4.5	4.5	10.5	
AC power [6]	Psite	MW			111	138	198	173	215	300	
Site length	Lsite	km	20.5	20.5	20.5	20.5	20.5	31	31	40	

\*There were several typos in the values of the luminosities in the TDR. They have been fixed by CR-0005. <a href="https://edmsdirect.desy.de/item/D00000001100895">https://edmsdirect.desy.de/item/D00000001100895</a>

22

Snowmass meeting on Dec.16

1.9.2021

Benno List

### References



### [1] TDR

https://ilchome.web.cern.ch/publications/ilc-technical-design-report

https://arxiv.org/ftp/arxiv/papers/1306/1306.6328.pdf

[2] "The International Linear Collider Machine Staging Report 2017", Nov. 2017:

https://arxiv.org/ftp/arxiv/papers/1711/1711.00568.pdf

[3] "Recommendations on ILC Project Implementation"

https://www.kek.jp/en/newsroom/2019/10/02/1000/

https://www2.kek.jp/ilc/en/docs/Recommendations\_on\_ILC\_Project\_Implementation.pdf

[4] "Operation of ILC250 at the Z-pole", Jan. 2020: https://arxiv.org/abs/1908.08212

https://agenda.linearcollider.org/event/8389/contributions/45113/attachments/35257/54621/ILC-CR-0019.pdf

[5] "Luminosity Upgrades for ILC", Aug.2013: https://arxiv.org/abs/1308.3726

[6] "Updated power estimate for ILC-250", Dec.2019

https://edmsdirect.desy.de/item/D0000001169675

[7] "Summary of the ILC Advisory Panel's Discussions to Date after Revision" (MEXT, Japan):

http://www.mext.go.jp/component/b\_menu/shingi/toushin/\_\_icsFiles/afieldfile/2018/09/20/1409220\_2\_1.pdf

[8] European Strategy Input and its supporting document

https://ilchome.web.cern.ch/content/ilc-european-strategy-document

https://indico.cern.ch/event/765096/contributions/

https://indico.cern.ch/event/765096/contributions/3295702/

https://arxiv.org/pdf/1903.01629.pdf

[9] "Green ILC project," http://green-ilc.in2p3.fr/home/ (2018).

Snowmass meeting on Dec.16