


2x2 in the ND-LAr consortium




(b) $E_\nu = 3.36$ GeV

M. Weber
LHEP/AEC, University of Bern




DUNE/LBNF near detector

- Neutrino oscillations are measured from the distribution of $\nu_{\mu,e}$ CC events at the far detector (FD) and the near detector (ND)
 - ND predicts distributions at the FD from production, oscillation, interaction, and detector response



- Challenge
 - High event density
 - High event rate (pile-up)

- Modular approach
 - Reduced risks
 - Contained light
 - Distributed production
 - LArTPC V2.0




“The core of the near detector is a liquid argon TPC based on the ArgonCUBE design [developed and originally proposed by the Bern group]”

ND LArTPC: From Prototyping to Production to Installation u^b


2019-2021

Module 0
SingleCube,
then 1 module (Module 0),
then 4 modules (2x2)
Operated in cryostat at Bern,
then FNAL in NuMI beam



2022-2023

**Full-scale ND
Demonstrator**



ArgonCube 2x2 (2021--)



**2024-2027
Production and testing**


35 (+5) Production modules
Each fully tested in single-module cryostat
LAr Test at MATF @ FNAL



**2028-2029
Installation**

Assemble rows of 5 modules
Support of TPC module
installation in Near Site

Activity driven by Near
Site Integration (NSI)



Neutrino event Reconstruction

Timeline and high-level dependencies

- Module-0 test are completed
They inform the Preliminary Design Review PDR, calendar Q4 2021
- **2x2 analysis from NuMI events will inform the Final Design Review (FDR) → Q3 CY 2023**
 - **Goal:** satisfy the reconstruction and physics requirements
- **Will need to iterate over reconstruction and simulation**
- **Will need initial data from the neutrino beam in CY 2022**
High level milestone
- **Start of neutrino beam operation underground at NuMI in October/November 2022 is critical**



Artistic rendering of the 2x2 Demonstrator in the NuMI ND hall

Prototyping plan and DUNE-ND CDR

ND-LAr Consortium Prototyping Plan

Last Updated: 10 Sep. 2020 by D. Dwyer

Overview

The prototyping plan for the Near Detector LArTPC detector will address a specific set of technical targets between now and the initiation of detector production. Prototyping activities fall into two categories: component-level and integration-level prototyping. Component prototyping is generally addressed via stand-alone small-scale tests, and the majority of these tests have been completed over the recent years of the ArgonCube R&D program. Integration prototyping addresses how these components come together and function coherently within the ND LArTPC design, as well as demonstrating the large-scale production and assembly processes necessary to construct the Near Detector.

Integration Prototyping Plan

There are two stages to the integration prototyping plan: the ArgonCube 2x2 Demonstrator stage and the subsequent Full-scale Demonstrator stage. The 2x2 Demonstrator is a complete, but sub-scale, LArTPC detector system focused on verifying technical readiness of the ND LArTPC design before the completion of the Near Detector design phase. The Full-scale Demonstrator is a single production-scale LArTPC module that will validate the full-scale component production, assembly, and testing processes before the Consortium proceeds to Near Detector production.

Deep Underground Neutrino Experiment (DUNE)

Near Detector Conceptual Design Report


DUNE ND CDR arxiv:2103:13910

Mar 2021

March 26, 2021



2	Liquid Argon TPC - ND-LAr	<u>36</u>
2.1	Introduction	<u>36</u>
2.2	Requirements	<u>39</u>
2.3	Overview of ND-LAr ArgonCube structure	<u>40</u>
2.3.1	Field Structures	<u>41</u>
2.3.2	Charge Readout	<u>43</u>
2.3.3	Light Readout	<u>45</u>
2.3.4	Module Structures	<u>47</u>
2.3.5	High Voltage	<u>48</u>
2.4	The LArTPC Demonstrator Program	<u>51</u>
2.4.1	Prototyping Plans	<u>51</u>
2.4.2	SingleCube Demonstrators	<u>52</u>
2.4.3	ArgonCube 2x2 Demonstrator	<u>53</u>
2.4.4	Full-scale Demonstrator	<u>55</u>
2.5	ProtoDUNE-ND physics studies	<u>56</u>
2.5.1	Combining light and charge signals	<u>60</u>

Organization: DUNE International – ND-LAr Consortium






ND LAr Consortium (red = 2x2 involvement)

- **ANL**
- **U Bern**
- BNL
- **Caltech**
- U Cambridge
- **CSU**
- **UColorado**
- **Fermilab**
- **Houston**
- **Iowa**
- **JINR**
- **Lancaster**
- **LBNL**
- Manchester
- **Minnesota Duluth**
- MSU
- Penn
- **Rochester**
- **Rutgers**
- Sheffield
- **SLAC**
- **Tufts**
- **UC Berkeley**
- UC Davis
- UC Irvine
- **UC Santa Barbara**
- **UTA**
- Warwick
- Wichita State
- **William&Mary**
- **Yale**
- **York**



Cryostat (2x2)



- Cryostat arrived in Bern in 2015
- Initial tests and rebuild 2016
- Cryogenics setup 2017
- Initial run 2018
- Runs for module extraction 2019








Pressure/vacuum test successful 6/8/2021

Arrival at FNAL in July 2021





Successful Module-0 runs (first of 4 modules)

April and June 2021




July 2021, module inserted in
the single-module cryostat
Waiting-position for shipping

Building more modules (light and charge collection)




ETA
September 2021

LArPix-v2 Pixel Anode
4.9k pixels





ETA
2021 for one additional module
Early CY 2022 for all modules



ETA field shell
G10 support ordered
DR8 resistive foil 50% delivered
End 2021/early 2022 with same technology

Top flange also serves as cryostat seal
Will ship back to Bern as new modules arrive at FNAL


Module assembly and testing



ETA 1 week per module + 1 week checkout
Timeline defined by cooldown-warmup of testing setup

Readout & powering



Several components:
either ship what we have in Bern
and duplicate for Bern;
or wait for new copy and deliver to FNAL



Trigger logic standard, HV PS



HV filter available,
can be duplicated



Charge r/o




Light r/o

Readout and controls

Readout server (standard with ethernet)
Slow-control & PLC systems ready and used in Bern

Will be shipped to FNAL
A replica for Bern being built



ArgonCube reconstrcuton and analysis


- Paper on analysis of Module-0 data
- Initial reconstruction of charge/light track/shower

11 Contents



12	1 Overview	1
13	1.1 Detector Design	1
14	1.2 LArPix Charge Readout System	2
15	1.3 Light Readout Systems	3
16	1.3.1 Data acquisition	4
17	1.4 Detector Configuration	6
18	1.5 Data Processing, Reconstruction, Simulation	7
19	2 Charge Readout Performance	7
20	3 Light readout performance	16
21	3.1 Gain measurements	17
22	3.2 Time resolution	17
23	3.3 Photon detection efficiency	19
24	4 System Performance	19
25	5 Analysis of Cosmic Ray Samples	20
26	5.1 Data Samples	20
27	5.2 Electron lifetime	20
28	5.3 Electric field uniformity	21
29	5.4 Calorimetry	22
30	5.5 Charge-light matching	23
31	5.6 Charge position reconstruction	23
32	5.7 Charge/light yield anti-correlation	24
33	5.8 Cosmic ray tracks	31
34	5.9 Michel electrons	32
35	6 Conclusions	33

~25 million events collected over
~1 week of operation

u^b



High-stats stopping muon sample: Michel e- spectrum and muon energy loss.



End-to-end analysis by end CY 2021

- Integrate light+charge in simulation
- Complete reco chain: from basic (energy, light deposition) to high level (neutrino vertex/event) reco
- ML + conventional
- Neutrino + rock

(Mini-)Workshop

[ML] Reco (2)		CAFs (1)	Interfaces (1)	Light (1)	Pileup (1)
Improve track/shower	Read detector simulation	Revisit numu CAF analysis	Truth matching	Basic light simulation integration	Revisit G4
Interaction level reco		Revisit nu+e CAF analysis	ND-LAr sample production	Truth matching	Adapt MicroBooNE algorithms
	M0 Data/MC		GAR/MPD matching	M0 Data/MC	Smear Q + L analysis
Full-chain on det. sim.		Revisit low-nu		Model tuning	
Model training		Revisit det. opt.	Model dist'n/VCS	Electronics sim	Integrate reco Q
numu reco	nue reco	Implement numu	Q/L data model	Model tuning	Reco Q + smeared L analysis
		Implement nue	Metadata & DBs	Light system Q/position reco	
Hadron reco	nu+e reco	Implement hadron & mis-IDs	Long-term production strategy	M0 Data/MC	Optimization
	Michel reco				
Documentation		Documentation	Documentation	Documentation	Documentation

Summary

- 2x2 a main activity of the ND-LAr consortium
- Critical to record good quality NuMI neutrino data starting in Nov 2022, mission critical for DUNE
- Effort ongoing for 4+ years, internationally funded, getting to the final phase (neutrino beam)
- Most detector components in hand or can be assembled as needed
 - charge readout and field shell on critical path
- Analysis / reconstruction / simulation effort to ramp up for being ready on day-1