

# MuCool Program Overview





Yağmur Torun

Illinois Institute of Technology/Fermilab



MAP Collaboration Mtg  
Mar 4, 2012 – SLAC



## MuCool

R&D program at Fermilab to develop ionization cooling components

mission:

- design, prototype and test components for ionization cooling
  - absorbers (LH<sub>2</sub>, solid LiH)
  - RF cavities
  - magnets
  - diagnostics
- carry out associated simulation and theoretical studies
- support system tests (MICE, future cooling experiments)

## MICE

System test to demonstrate and measure cooling

Serious degradation of RF cavity performance in strong external magnetic fields.

Currently main focus of MuCool.

- Magnetic field effect first seen at Fermilab's Lab-G with a 6-cell 805-MHz cavity  
J. Norem *et al.*, Phys. Rev. ST Accel. Beams 6 (2003) 072001
- Studied in more detail at MTA with 805-MHz pillbox cavity  
A. Moretti *et al.*, Phys. Rev. ST Accel. Beams 8 (2005) 072001
- Various models proposed  
A. Hassanein *et al.*, Phys. Rev. ST Accel. Beams 9 (2006) 062001  
R. B. Palmer *et al.*, Phys. Rev. ST Accel. Beams 12 (2009) 031002

# Potential Solutions



- 1 Better materials: more robust against breakdown  
(melting point, energy loss, skin depth, thermal diffusion length, etc.)

# Potential Solutions


- 1 Better materials: more robust against breakdown  
(melting point, energy loss, skin depth, thermal diffusion length, etc.)
- 2 Surface processing: suppress field emission  
(superconducting RF techniques, coatings, atomic layer deposition)

# Potential Solutions

- 1 Better materials: more robust against breakdown (melting point, energy loss, skin depth, thermal diffusion length, etc.)
- 2 Surface processing: suppress field emission (superconducting RF techniques, coatings, atomic layer deposition)
- 3 Shielding: iron, bucking coils (Rogers, Alekou)




- ④ Magnetic insulation: modified cavity/coil designs to keep  $B \perp E$  on cavity surfaces (Palmer, Stratakis)



Loss of x 2 gradient advantage in pillbox geometry



# Potential Solutions

- 4 Magnetic insulation: modified cavity/coil designs to keep  $B \perp E$  on cavity surfaces (Palmer, Stratakis)



Loss of x 2 gradient advantage in pillbox geometry

- 5 High-pressure gas: suppress breakdown by moderating electrons (Muons Inc., Yonehara *et al.*)



Dedicated facility at the end of the Fermilab Linac built to address MuCool needs



- RF power (13 MW at 805 MHz, 4.5 MW at 201 MHz)
- Superconducting magnet (5 T solenoid)
- Large coupling coil under construction
- 805 and 201 MHz cavities
- Radiation detectors
- Cryogenic plant
- 400 MeV p beamline

- RF forward/reflected power, pickup antenna signals
- Vacuum pressure
- Scintillator+PMT counters for X-ray rates, spectra
- Ionization chambers for radiation dose rates
- Spectrometer for cavity light analysis
- Acoustic sensors for spark detection (under development)
- Toroids for beam intensity
- Beam position monitors
- Multiwire chambers and scintillator screen+camera for beam profile (M. Jana poster)




# Summary of MuCool experimental program

- trying to demonstrate a working solution to RF cavity operation in high external magnetic field for muon cooling
- major MAP milestone (and technical risk for MICE)
- big impact on cooling channel design and system tests
- multipronged approach to cover maximum ground with available resources

Cavity	Outstanding issues	Proposed resolution	Experimental tests
Vacuum pillbox  rectangular open-iris	Breakdown and damage	Better materials	Mo, W, Be buttons Be-walled 805-MHz cavity
		Surface processing	Electropolished buttons 201-MHz pillbox in B-field
		Coatings	ALD-coated buttons ALD-coated cavity
		Magnetic insulation	$E \perp B$ box cavity $E \parallel B$ box cavity Modified cavity-coil geometry
Pressurized	B-field/pressure effects	Materials tests	805-MHz 4-season cavity
	Beam-induced ionization	Measure ionization lifetime	805-MHz cavity in beam
	Frequency dependence	Test at different frequency	Pressurized 201-MHz cavity


# 805 pillbox

- 805 MHz pillbox cavity used to
  - quantify magnetic field dependence of gradient
  - establish feasibility of thin windows
    - flat Cu windows unstable at high power, curved Cu and Be windows work well
  - test buttons with different materials/coatings
    - problems with Cu – Be, Mo and W looked more promising
- Rebuilt at JLab, tested again (10 MV/m at 3T)
- Ran with larger curvature Be & Cu buttons
- Modified versions with reduced coupler field (SLAC, Z. Li talk) and Be-walls (LBNL, D. Li talk) under design





# Button inspection (M. Jana, D. Hicks, T. Shen)

- Photographed after exposure to RF
- Visual inspection: very few visible marks on Be; Cu from craters deposited on endplates
- Taken to microscopy lab in Fermilab Tech. Div.
- Map of surfaces under microscope complicated by large curvature
- Profilometry and SEM over interesting areas
- Note: allowed Be dust in MTA Hall (14k cu.ft.): 0.6mg




# Box Cavity

- Rectangular geometry chosen for test cavity to allow fast fabrication and simplify analysis
- Support system designed to rotate cavity pivoting around magnet center by up to  $12^\circ$
- Rectangular coupling aperture with rounded edges and a coupling cell built to match the power coupler to waveguide
- Three CF flange tubes for rf pickups and optical diagnostics
- $f_0 = 805.3$  MHz,  $Q_0 = 27.9 \times 10^3$ , coupling factor 0.97
- YT *et al.*, IPAC10






# Box Cavity

- Operated in the MTA magnet Mar-Sep 2010
- Commissioned to 50 MV/m at  $B=0$
- Took data at  $0, \pm 1, 3, 4^\circ$  wrt B axis (3T)
- Large effect seen at  $3-4^\circ$  (stable gradient down to about 25 MV/m)
- Some degradation even at  $\leq 1^\circ$  (33 MV/m)
- Visual inspection of interior, no obvious damage
- RF, optical and X-ray signals during sparks saved for analysis
- Magnetic insulation seems to work but not well enough to make up for lost shunt impedance




## 201 MHz MICE prototype cavity


- SRF-like processing (electropolished, etc.)
- conditioned to design gradient very quickly
- ran successfully with thin curved Be windows
- operated in stray magnetic field reduced performance
- radiation output measured (MICE detector backgrounds)
- large diameter coil needed for field configuration closer to MICE
- No surface damage seen on cavity interior




## Sparking in the coupler (design now modified)



SEM images of 201 MHz coupler.




## Unipolar arc? (Norem)



# 201 pillbox – MICE


Each RFCC module has

- 4 201-MHz cavities with Be windows
- large bore magnet (coupling coil)
- 10 cavities built, to be processed (EP, etc.) at LBNL




# 201 Single-cavity module

To be tested at the MTA



# 4-Season cavity (Muons Inc., LANL)


- modular pillbox with replacable end walls
- designed for both vacuum and high-pressure  
"a cavity for all seasons"
- G. Kazakevich *et al.* PAC11
- operated at RF station 2 and again in magnet
- gradient limited by (lack of) cooling  
(28 MV/m at 2Hz)
- same stable gradient at  $B=0$  and 3T  
(25 MV/m)
- looking into Be walls



# HPRF Program

HPRF cavity beam test (K. Yonehara talk, B. Freemire poster)


- First beam experiment at MTA



# HPRF Program

HPRF cavity beam test (K. Yonehara talk, B. Freemire poster)


- First beam experiment at MTA
- Ran Jul-Aug 2011



# HPRF Program

HPRF cavity beam test (K. Yonehara talk, B. Freemire poster)


- First beam experiment at MTA
- Ran Jul-Aug 2011
- HPRF previously shown to work in high B at the MTA (P. Hanlet *et al.*, EPAC06)



# HPRF Program

HPRF cavity beam test (K. Yonehara talk, B. Freemire poster)


- First beam experiment at MTA
- Ran Jul-Aug 2011
- HPRF previously shown to work in high B at the MTA (P. Hanlet *et al.*, EPAC06)
- Goal: evaluate cavity loading from beam-induced plasma (M. Chung *et al.*, IPAC10)



# HPRF Program

HPRF cavity beam test (K. Yonehara talk, B. Freemire poster)


- First beam experiment at MTA
- Ran Jul-Aug 2011
- HPRF previously shown to work in high B at the MTA (P. Hanlet *et al.*, EPAC06)
- Goal: evaluate cavity loading from beam-induced plasma (M. Chung *et al.*, IPAC10)
  - Intense muon bunch creates lots of electron-ion pairs



# HPRF Program

HPRF cavity beam test (K. Yonehara talk, B. Freemire poster)


- First beam experiment at MTA
- Ran Jul-Aug 2011
- HPRF previously shown to work in high B at the MTA (P. Hanlet *et al.*, EPAC06)
- Goal: evaluate cavity loading from beam-induced plasma (M. Chung *et al.*, IPAC10)
  - Intense muon bunch creates lots of electron-ion pairs
  - potentially shorting the RF cavity





# HPRF Program

HPRF cavity beam test (K. Yonehara talk, B. Freemire poster)


- First beam experiment at MTA
- Ran Jul-Aug 2011
- HPRF previously shown to work in high B at the MTA (P. Hanlet *et al.*, EPAC06)
- Goal: evaluate cavity loading from beam-induced plasma (M. Chung *et al.*, IPAC10)
  - Intense muon bunch creates lots of electron-ion pairs
  - potentially shorting the RF cavity
  - may be mitigated by electronegative dopant gas (K. Yonehara *et al.*, PAC09, IPAC10)



# HPRF Beam Test



- 500 psi N<sub>2</sub>; 500, 800, 950 psi H<sub>2</sub>
- 8  $\mu$ s beam, 2 intensities, 2 dopants (N<sub>2</sub>, SF<sub>6</sub>)
- next test about to start expand range in pressure, beam intensity, more dopants
- B-field (safety doc, M. Leonova)
- gas analysis (L. Jenner, T. Schwarz)




# RF scorecard

Branch	Hardware	$E_{surf}$ [MV/m]		$E_{acc}$ (B=0)
		B=0	B=3T	
Baseline	805-pillbox	40	16	40
		20	10	20
	HPRF-Cu-button	50	-	35
Materials	805-4season	25	25	25
	805-W,Mo-buttons	38-39	18-20	22-23
	805-TiN/Cu-button	38	24	22
	805-TiN/Cu-button	35	28	12
	805-Be-button	40	31	13
Surface proc.	201-pillbox	21	14(0.4T)	21
MagIns/surf.	805-box	50	22-33	0
HPRF/Mat.	805-Mo-button	64	65	45
	805-Be-button	52	-	36



# Beam

- First beam pulse to "emittance absorber" (beam stop 2) Feb 28
- Intensity about  $1.8 \times 10^{12}$  protons/pulse at 1 pulse/min
- Scintillator screen upstream of collimator to measure beam spot
- Beamline and instrumentation upgraded
- $O(10^{11})$  protons through collimators




# Beam

- First beam pulse to "emittance absorber" (beam stop 2) Feb 28
- Intensity about  $1.8 \times 10^{12}$  protons/pulse at 1 pulse/min
- Scintillator screen upstream of collimator to measure beam spot
- Beamline and instrumentation upgraded
- $O(10^{11})$  protons through collimators





# Beam

- First beam pulse to "emittance absorber" (beam stop 2) Feb 28
- Intensity about  $1.8 \times 10^{12}$  protons/pulse at 1 pulse/min
- Scintillator screen upstream of collimator to measure beam spot
- Beamline and instrumentation upgraded
- $O(10^{11})$  protons through collimators





# Beam

- First beam pulse to "emittance absorber" (beam stop 2) Feb 28
- Intensity about  $1.8 \times 10^{12}$  protons/pulse at 1 pulse/min
- Scintillator screen upstream of collimator to measure beam spot
- Beamline and instrumentation upgraded
- $O(10^{11})$  protons through collimators





# Beam

- First beam pulse to "emittance absorber" (beam stop 2) Feb 28
- Intensity about  $1.8 \times 10^{12}$  protons/pulse at 1 pulse/min
- Scintillator screen upstream of collimator to measure beam spot
- Beamline and instrumentation upgraded
- $O(10^{11})$  protons through collimators




# Beam

- First beam pulse to "emittance absorber" (beam stop 2) Feb 28
- Intensity about  $1.8 \times 10^{12}$  protons/pulse at 1 pulse/min
- Scintillator screen upstream of collimator to measure beam spot
- Beamline and instrumentation upgraded
- $O(10^{11})$  protons through collimators





# Beam

- First beam pulse to "emittance absorber" (beam stop 2) Feb 28
- Intensity about  $1.8 \times 10^{12}$  protons/pulse at 1 pulse/min
- Scintillator screen upstream of collimator to measure beam spot
- Beamline and instrumentation upgraded
- $O(10^{11})$  protons through collimators





# Beam

- First beam pulse to "emittance absorber" (beam stop 2) Feb 28
- Intensity about  $1.8 \times 10^{12}$  protons/pulse at 1 pulse/min
- Scintillator screen upstream of collimator to measure beam spot
- Beamline and instrumentation upgraded
- $O(10^{11})$  protons through collimators





# Beam

- First beam pulse to "emittance absorber" (beam stop 2) Feb 28
- Intensity about  $1.8 \times 10^{12}$  protons/pulse at 1 pulse/min
- Scintillator screen upstream of collimator to measure beam spot
- Beamline and instrumentation upgraded
- $O(10^{11})$  protons through collimators





# Beam

- First beam pulse to "emittance absorber" (beam stop 2) Feb 28
- Intensity about  $1.8 \times 10^{12}$  protons/pulse at 1 pulse/min
- Scintillator screen upstream of collimator to measure beam spot
- Beamline and instrumentation upgraded
- $O(10^{11})$  protons through collimators





# Beam

- First beam pulse to "emittance absorber" (beam stop 2) Feb 28
- Intensity about  $1.8 \times 10^{12}$  protons/pulse at 1 pulse/min
- Scintillator screen upstream of collimator to measure beam spot
- Beamline and instrumentation upgraded
- $O(10^{11})$  protons through collimators




# Beam

- First beam pulse to "emittance absorber" (beam stop 2) Feb 28
- Intensity about  $1.8 \times 10^{12}$  protons/pulse at 1 pulse/min
- Scintillator screen upstream of collimator to measure beam spot
- Beamline and instrumentation upgraded
- $O(10^{11})$  protons through collimators




# Beam

- First beam pulse to "emittance absorber" (beam stop 2) Feb 28
- Intensity about  $1.8 \times 10^{12}$  protons/pulse at 1 pulse/min
- Scintillator screen upstream of collimator to measure beam spot
- Beamline and instrumentation upgraded
- $O(10^{11})$  protons through collimators




# Magnetic Field Mapping

- Magnetic insulation depends strongly on angle
- MTA solenoid field never mapped in detail before
- Expect good alignment of magnetic axis with bore based on manufacturing tolerances but wanted to confirm



- Fiducial holes drilled during cavity fabrication
- Machined blocks to mount NIKHEF sensors
- Used cavity as mounting fixture – data taken at corners
- Gaussmeter fixed in bore for normalization
- Bore mapped in detail with cart on rails



# Students at the MTA (past 1.5 year)

- Anastasia Belozertseva (U. Chicago) – magnetic field mapping
- Last Feremenga (U. Chicago) – magnetic field mapping
- Ben Freemire (IIT) – HPRF beam test (thesis), everything else
- Giulia Collura (Torino) – HPRF beam test
- Timofey Zolkin (U. Chicago) – dark current instrumentation
- Peter Lane (IIT) – acoustic sensors for detecting cavity sparks
- Raul Campos (NC State) – beamline magnet support
- Ivan Orlov (Moscow State) – HPRF beam test simulation
- Tom Mclaughlin (Valparaiso) – magnet mapping, circulator installation
- Jessica Cenni (Pisa) – dielectric loaded cavity
- Jared Gaynier (Kettering) – circulator installation



# MTA Schedule and Outlook

- Experimental program
  - 805 MHz pillbox cavity with Be/Cu buttons – complete surface analysis in progress
  - 805-MHz 4-season cavity in B – complete
  - HPRF cavity – 2nd beam test imminent other beam & non-beam tests as needed
  - 201-MHz single cavity module (summer?)
  - ALD cavity – under design
  - New 805-MHz Cu pillbox
  - New 805-MHz Be-wall pillbox
  - Dielectric-loaded cavity
- Infrastructure
  - beam commissioning, cryo plant upgrade, magnet field mapping complete
  - RF circulator/switch installation in progress
  - single-cavity module assembly, installation in Hall
- Expect to demonstrate a working solution to RF cavity operation in high magnetic field "soon"